


# Jenolan Caves Road, Cut Slopes Remediation

Review of Environmental Factors

RTA ENVIRONMENTAL TECHNOLOGY BRANCH

MARCH 2005



# **Document Controls**

Business Unit	Environmental Te	chnology Branch.	•
Project No	H/45083/A		
Document Description	REF Jenolan Caves Road, Cut Slopes Remediation		
	Name	Signed	Date
Approving A/Manager	Andrew Cook	A.6. 188k	11-3-2005
Reviewing Officer	Rokeya Sabur	418, (DEC	11-3-2005

Person(s) managing this document	Person(s) writing this document
Peter Ryan	Peter Ryan

Location	File No.	
g:\ops\environ\assessments_section\projects\0405 \jenolan caves slope remediation\ref\jenolan cut slopes final ref.doc	5M96	

Document Status	Date	
Final	11-3-2005	

Prepared For	Prepared By
Chris Barnett	Environmental Technology Branch
Operations, Technical Services Operations	RTA Operations Directorate
Western Region	Level 5, Pod D, 99 Phillip Street
15-33 Cooerwull Road	Parramatta NSW 2150
BOWENFELS, NSW 2790	T (02) 8837 0583
	F (02) 8837 0053
	E peter_ryan@rta.nsw.gov.au

© NSW Roads and Traffic Authority
Prepared by RTA Operations – Environmental Technology Branch
Version I

A person using RTA Environmental Technology documents or data accepts the risk of:

- Using the documents or data in electronic form without requesting and checking them for accuracy against the original hard copy version; and
- Using the documents or data for any purpose not agreed to in writing by RTA Environmental Technology.

# Contents

1	Intro	oduction and Methodology	. 1
	1.1	Name of the Proposed Activity	. 1
	1.2	Local Government Area	
	1.3	RTA Region	
	1.4	Introduction	
	1.5	Background	
	1.6	Methodology	
2	Des	cription of Proposal Site and Study Area	.4
	2.1	Location	.4
	2.2	Description of the Existing Environment	.4
		2.2.1 General	
		2.2.2 Topography and Landform	.4
		2.2.3 Geology and Soils	
		2.2.4 Climate	
		2.2.5 Drainage and Watercourses	
		2.2.6 Biodiversity	
		2.2.7 Non-indigenous Heritage	
		2.2.8 Sensitive Noise Receptors	
		2.2.9 Air Quality	
		2.2.10 Visual Amenity	
		2.2.11 Existing and Forecasted Traffic	
		2.2.12 Socio-economic Considerations	
3	Desc	cription of the Proposall	1
	3.1	Description of the Proposal	11
	3.2	Construction Activities	
		3.2.1 Construction Processes and Work Methodology	
		3.2.2 Construction Equipment	
		3.2.3 Access	
		3.2.4 Utilities	13
		3.2.5 Source of Material	
		3.2.6 Additional Truck Movements	
		3.2.7 Stockpile and Compound Sites	
	3.3	Workforce and Working Hours	
	3.4	Period of Construction	
	3.5	Proposal Cost and Source of Funds	
4	Stat	utory Position	6
	4.1	Local Environmental Plans	6
	4.2	Regional Environmental Plans	17
		4.2.1 Sustaining the Catchments – The Regional Plan to protect the drinking water catchments	ng
	4.3	State Environmental Planning Policies	

		4.3.1 SEPP 44 – Koala Habitat Protection	17
		4.3.2 SEPP 58 – Protecting Sydney's Water Supply	18
	4.4	Confirmation of Part 5 Position	18
5	Strat	tegic Stage	19
	5.1	Strategic Planning	19
	5.2	Need for the Proposal	
6	Cond	cept Stage	20
	6.1	Proposal Objectives	20
	6.2	Options Considered	
7	Back	ground Investigations and Consultation	22
	7.1	Background Investigations and Database Searches	22
	7.2	Government and Community Consultation and Involvement	
		7.2.1 Government and stakeholder consultation	
		7.2.2 Community Consultation and Involvement	27
8	Envi	ronmental Assessment	28
	8.1	General	28
	8.2	Landform, Geology and Soils	28
	8.3	Water Quality and Hydrology	29
	8.4	Biodiversity	30
	8.5	Non-Indigenous Heritage	33
	8.6	Indigenous Heritage	
	8.7	Noise and Vibration	
	8.8	Air Quality	36
	8.9	Visual Amenity / Landscape	
	8.10	Socio-economic Considerations	
	8.11	Waste Minimisation and Management	39
	8.12	Summary of Beneficial Effects	
	8.13	Summary of Adverse Effects	
9	Impl	ementation Stage	42
	9.1	Summary of Proposed Environmental Safeguards	42
	9.2	Licences and Approvals	49
10	Cons	sideration of State and Commonwealth Environmental Facto	rs50
	10.1	Clause 228(2) Factors (NSW Legislation)	
	10.2	EPBC Act 1999 Factors (Commonwealth Legislation)	53
11	Cert	ification	54

#### **APPENDICES**

Appendix A: Ecology Study

**Appendix B:** Landscape and Visual study **Appendix C:** Photographs of Proposal site

Appendix D: Concept Design

Appendix E: Results of Database Searches

Appendix F: Pejar LALC and Gundungurra Tribal Council

# I Introduction and Methodology

# 1.1 Name of the Proposed Activity

Jenolan Caves Road, Cut Slopes Remediation.

#### 1.2 Local Government Area

Oberon Council.

# 1.3 RTA Region

Western Region.

#### 1.4 Introduction

The NSW Roads and Traffic Authority (RTA) proposes to carry out remediation of cut slopes along Jenolan Caves Road (MR 253) within the Five Mile Hill Section, located 20km south east of Oberon.

This Proforma I Review of Environmental Factors (REF) has been prepared by Environmental Technology Branch (RTA Operations Directorate) on behalf of RTA Technical Services Western Region. For the purposes of these works, the RTA is the proponent and the determining authority under Part 5 of the *Environmental Planning and Assessment (EP&A) Act 1979.* 

The purpose of the REF is to describe the Proposal, to document the likely impacts of the Proposal on the environment, and to detail protective measures to be implemented.

The description of the proposed works and associated environmental impacts have been undertaken in the context of Clause 228 of the *Environmental Planning and Assessment Regulation 2000*, the *Threatened Species Conservation (TSC) Act 1995*, the *Fisheries Management (FM) Act 1994*, and the (Commonwealth) *Environment Protection and Biodiversity Conservation (EPBC) Act 1999*. In doing so, the REF helps to fulfil the requirements of Section III of the EP&A Act, that the RTA examine and take into account to the fullest extent possible, all matters affecting or likely to affect the environment by reason of the activity.

This REF has been prepared in accordance with the RTA's Proforma I REF as presented in the RTA's *Environmental Impact Assessment Policy, Guidelines and Procedures, Version 4 2001.* 

The findings of the REF would be considered when assessing:

 Whether the Proposal is likely to have a significant impact on the environment and therefore the necessity for an Environmental Impact Statement (EIS) under Section 112 of the EP&A Act.

- The significance of any impact on threatened species as defined by the TSC Act, in Section 5A of the EP&A Act and therefore the requirement for a Species Impact Statement (SIS).
- The potential for the Proposal to significantly impact on a matter of national environmental significance or Commonwealth land and the need to make a referral to the Commonwealth Environment Minister in accordance with the EPBC Act.

# 1.5 Background

The Jenolan Caves Road provides access for tourist and service vehicles to the Jenolan Caves and the Kanangra Walls, which is accessed from the Great Western Highway west of Hartley.

Under the *National Parks and Wildlife Act 1974*, the Jenolan Caves Reserve Trust (the Trust) is responsible for the conservation of the heritage and cultural resources of the Jenolan Caves. The Trust is subject to the direction and control of the NSW Minister for the Environment, and is currently being managed by an administrator.

Cut slopes along 5 Mile Hill have been assessed by the RTA as being unstable with the following features: toppling, planar sliding, wedge failures, and rock falls from overhangs and residual soil. The assessed risk level (ARL) of the cut slopes are currently high at greater than 3 (ie. ARL I and 2). The residual soils at the crest of the cut slopes have been cut oversteep, and weathering and erosion of these materials releases rock fall boulders. Minimal rock support has been employed to date. There is also no provision for surface water management at the crest of the cut slopes to limit infiltration and build up of groundwater pressures (RTA 2003a).

The RTA has identified the need to undertake remediation of cut slopes adjacent to Jenolan Caves Road at the Proposal site to provide safer road travel. Following completion of these remediation works, further remediation works are planned at other sites along Jenolan Caves Road.

Works undertaken to date include the following:

- In 2004, minor slope regrading at three sites involved cutting existing rock slopes to match existing batter slopes; and
- Installation of cantilever structures and Thriebeam guardrail at three sites commenced in 2004 and will be completed in 2005.

REF's were prepared for the above works, including preparation of a specialist ecological assessment.

# 1.6 Methodology

The method in which this document has been prepared is as follows:

- 1. A meeting was held with the Project Manager on 25 November 2004 to discuss the Proposal.
- 2. An RTA Environmental Technology representative undertook a site visit on 19 January 2005 to inspect the Proposal site.

- 3. The following agencies and RTA personnel were notified and/or consulted:
  - RTA Regional Environmental Advisor, Western Region;
  - RTA Aboriginal Programs Consultant, Western Region;
  - Oberon Council;
  - DIPNR:
  - Sydney Catchment Authority (SCA);
  - DEC (Parks Service Division);
  - Jenolan Caves Reserve Trust; and
  - Pejar Local Aboriginal Land Council (LALC) and Gundungurra Tribal Council.
- 4. A desktop search was conducted on the following databases to identify any potential issues:
  - Australian Heritage Database;
  - NSW Heritage Office State Heritage Register and State Heritage Inventory;
  - National Native Title Claims Search;
  - DEC Aboriginal Heritage Information Management System (AHIMS);
  - DEC Atlas of NSW Wildlife Threatened Flora and Fauna Records;
  - DEH Protected Matters (EPBC Act) Database;
  - DPI FishFiles Database and NSW Fisheries Threatened Species List;
  - DEC Contaminated Land Records;
  - DEC Air Quality Records; and
  - DPI Noxious Weeds List.
- 5. As part of the environmental assessment of the Proposal, ecology and visual specialist studies were undertaken to identify the Proposal constraints and to provide environmental safeguards. Details and findings from the investigations are further discussed in Chapter 8 of this REF with a copy of the specialist studies included as **Appendix A and B** to this REF.
- 6. A literature review was undertaken with regards to the following:
  - Landform, Geology, and Soils;
  - Groundwater;
  - Local Environment Plans;
  - Regional Environmental Plans;
  - State Environmental Planning Policies;
  - · Council's State of Environment Report; and
  - NSW Fisheries Policy and Guidelines.

# 2 Description of Proposal Site and Study Area

#### 2.1 Location

The Proposal site is located adjacent to Jenolan Caves, and approximately 20km south east of Oberon within the Oberon Local Government Area (LGA).

The Proposal site is defined as the area of direct impact, which would result from the Proposal, including an existing stockpile/compound site, and remediation of cut slopes (Refer to Section 3.1 for Proposal description details). Based on ecological habitat, the study area is defined as lands located within 10km of the Proposal site.

Refer to Figure 2.1 for a map of the locality.

# 2.2 Description of the Existing Environment

#### 2.2.1 General

The Five Mile Hill Section of Jenolan Caves Road (MR 253) is a two lane single carriageway road. This section of the road is narrow, has sharp curves, restricted lane widths and poor site distances. Safety posts and mesh fencing are present along this section of the road. Road shoulders are generally unformed and less than Im in width. The posted speed limit is 40kph with 20kph advisory signs.


Due to safety concerns, daily one-way traffic flow out of Jenolan Caves is currently provided for between 11.45am and 1.45pm. Additional traffic control measures (ie. boom gate and mini electronic variable message sign) have been in place since January 2004 to support the one-way traffic flow. Permanent variable message signs (VMS) are now present at Hartley, Hampton, Lithgow and Kelso. These VMS's are used to assist with traffic movements to and from Jenolan Caves.

#### 2.2.2 Topography and Landform

The topography of the study area consists of steep to very steep hills and mountains. Slopes are greater than 30% and local relief is greater than 300m. Elevation is greater than 120m to generally less than 1000m. Small narrow, convex crests occur above steep to very steep, deeply incised valleys. Occasional areas of rock occur on some slopes. Small cliffs are evident on some upper slopes (CALM, 1994). Land slopes within the Proposal site are steep to very steep.

#### 2.2.3 Geology and Soils

The Proposal site is located within the Kanangra George Soil Landscape Group. The following qualities and limitations apply to the Kanangra George Soil Landscape Group: severe water erosion hazard, steep slopes, severe foundation hazard, mass movement hazard, rock fall hazard (localised), and stony soils of very low fertility. The geology within the Proposal site consists of Devonian, Silurian and Ordovician steeply dipping metasediments (CALM, 1994).



**Figure 2.1**: Location of the Proposal site and study area. (Map extract courtesy of Land and Property Information NSW)

Soils within the Proposal site fall within the Kanangra George (ka) Soil Landscape Grouping. The soils are very shallow (<50cm), stony, well-drained Structured Loams and Lithosols on rocky, very steep to precipitous sideslopes, narrow crests and upper slopes. On lower slopes, soils are moderately deep to deep (>80cm), moderately well-drained Brown Podzolic Soils, Red Podzolic Soils and Yellow Podzolic Soils. Along narrow deeply incised drainage

lines, the soils are moderately deep (<100cm), moderately well-drained Alluvial Soils. Soil material fertility is very low, with moderate to very strong acidity.

#### 2.2.4 Climate

Records from the Jenolan Caves recording station are representative of the Proposal site, which is located in a temperate zone. The mean annual rainfall is 966mm with a slight summer dominance. In summer the mean daily maximum temperature is 25.6°C. In winter the mean daily minimum temperatures are close to freezing (0.2°C) (Bureau of Meteorology, 2004). Fog and frosts are known to occur within the Proposal site during winter.

#### 2.2.5 Drainage and Watercourses

The Proposal site is located within the Jenolan River catchment. The Proposal site is located 15m from the Jenolan River at it's closest point (ie. southern section of the Proposal site), and 100m and beyond from the river at other Proposal site locations (ie. northern sections of the Proposal site). In the vicinity of the southern section of the Proposal site, the Jenolan River has been dammed, and the riverbanks have been impacted by some trampling by tourists. The river water at this location has an attractive aqua colour due to the local limestone geology (Refer to **Appendix C** for photographs). Minor water seepage is evident at cut slopes 1.74 and 5.08.

The existing stockpile/compound site is located approximately 1.2km west of the Jenolan River. Drainage lines traverse under, and occur adjacent to Jenolan Caves Road, but none are located within any of the cut slope sites or the stockpile/compound site. The northern section of the Proposal site is located within the catchment of Pheasants Nest Creek. Pheasants Nest Creek flows into the Jenolan River. The Jenolan River flows easterly into the Coxs River, which then flows into Lake Burragorang, Sydney's major water supply storage.

The Jenolan River is subject to sediment and nutrient loads from the Oberon area (Oberon Council 2003). The SCA is responsible for management of the catchment area and waters of Lake Burragorang. Lake Burragorang forms part of the Hawkesbury-Nepean River catchment. The medium to steep hills and deeply incised gorge topography of the region provides for medium to rapid stream flows. Flooding is not evident within the Proposal site due to the steep topography and the separation distance of the Proposal site from waterways.

#### 2.2.6 Biodiversity

An ecological assessment of the Proposal was undertaken by Lesryk Environmental Consultants in February 2005. In addition, a targeted survey was undertaken by Mjadwesch Environmental Service Support to determine the presence of the Purple Copper Butterfly (*Paralucia spinifera*) (Refer to **Appendix A** for the full report).

#### Flora

Bushland is present within and adjacent to the Proposal site. The Proposal site is surrounded by the Jenolan Caves Karst Conservation Reserve. Kanangra-Boyd National Park is located approximately 1.2km east of the Proposal site, and to the immediate east of the existing stockpile/compound site. Jenolan Karst Conservation Reserve and Kanangra-Boyd National Park are part of the Greater Blue Mountains World Heritage Area. The Jenolan Karst Conservation Reserve Draft Plan of Management (2004) is in preparation, and applies to the Proposal site. No vegetation management plans apply to the Proposal site.

No critical habitat is present within the Proposal site. Eleven plants of conservation significance have been previously recorded in the Jenolan Caves region. No plants or vegetation communities of national, state or regional conservation significance (EPBC or TSC Acts) were recorded or indicated as occurring within the Proposal site. The Proposal site consists of a dry open-forest community on the upper slopes with a sparse shrub and groundcover layer, and a moist open forest on lower slopes near the Jenolan River with a dense shrub and groundcover layer. Both communities are dominated by *Eucalyptus fastigata*, *E. dalrympleana ssp. dalrympleana* and *E. viminalis*. The Proposal sites do not show a great diversity of species. At each site generally only a few species make up the majority of the vegetation community. This is common in many alpine and semi-alpine habitats. The Proposal site is not important habitat for any of the threatened plant species, plant populations or ecological communities that are known to occur in the region.

Several species of weed are declared noxious in the Upper Macquarie County Council control area. Blackberry (*Rubus ulmifolius*), a Class 3 weed, is present within the Proposal site at cut slopes 4.22, 7.02, 7.58 and 8.13. To suppress growth of weeds, the Upper Macquarie County Council undertakes regular spraying of weed species (including Blackberry) that occur along Jenolan Caves Road.

Unstable vegetation growth present at the cut slope sites currently represents a hazard to road users. Vegetation present within and adjacent to the Proposal site also presents a bushfire hazard.

#### Fauna

One fauna habitat type, a eucalypt woodland is uniformly present throughout the Proposal site and study area. The eucalypt woodland supports trees that are between 10 and 15m in height. Throughout the eucalypt woodland the tree canopy is generally continuous, though some gaps up to 8m wide are present. The understorey is either absent, or composed of isolated saplings up to 2m in height. Similarly the ground cover layer is absent, or composed of a sparse distribution of native grasses, ferns and forbs. Leaf litter, fallen trees and branches are common, as is some exposed rock.

Isolated hollow bearing trees are present on top of the cut slopes adjacent to the Proposal site. Hollow bearing trees are also present adjacent (ie. beyond the Proposal site) to the existing stockpile/compound site. No critical habitat, important wildlife corridors or endangered ecological communities are present within the Proposal site. No endangered fauna populations are expected to be present within the Proposal site, and no fauna or habitat management plans apply to the Proposal site.

The following mammals were recorded during the field investigation: Short-beaked Echidna, Brown Antechinus, Common Wombat, Greater Glider, Common Brushtail Possum, Eastern Grey Kangaroo, Red-necked Wallaby, Swamp Wallaby, Southern Forest Bat, Little Forest Bat, Gould's Wattled Bat, Chocolate Wattled Bat, Large Forest Bat, White-striped Freetail Bat, Grass Skink and Red-bellied Black Snake.

The following birds were recorded during the field investigation: Tawny Frogmouth, Wonga Pigeon, Gang-gang Cockatoo, Yellow-tailed Black Cockatoo, Sulphur-crested Cockatoo, Sacred Kingfisher, Crimson Rosella, Southern Boobook, Laughing Kookaburra, Superb Lyrebird, White throated Treecreeper, Supurb Fairy-wren, Striated Pardalote, White-browed Scrubwren, Brown Thornbill, Striated Thornbill, Noisy Friarbird, Red Wattlebird, Bell Miner, Yellow-faced Honeyeater, White-plumed Honeyeater, Eastern Spinebill, Eastern Whipbird, Grey Shrike-thrush, Black-faced Cuckoo-shrike, Grey Butcherbird, Australian Magpie, Pied Currawong, Australian Raven, Welcome Swallow and Silvereye.

Seven terrestrial fauna species listed under the Schedules of the TSC Act were recorded within the vicinity of the Proposal site. These animals include the Powerful Owl (Ninox strenua), Sooty Owl (Tyto tenebricosa), Yellow-bellied Glider (Petaurus australis), Large-eared Pied Bat (Chalinolobus dwyeri), Large-footed Myotis (Myotis adversus), Eastern Bentwing Bat (Miniopterus schreibersii), and Eastern False Falsistrelle (Falsistrellus tasmaniensis). The Gang-gang Cockatoo (Callocephalon fimbriatum) has received preliminary listing for inclusion under the TSC Act. The Proposal site currently provides some native fauna habitat for these threatened species.

Two animals listed under the Commonwealth EPBC Act were found or indicated as occurring within the Proposal site. These animals included the Large-eared Pied Bat (*Chalinolobus dwyeri*) and the Satin Flycatcher (*Myiagra cyanoleuca*). No other terrestrial fauna species listed under the TSC Act or EPBC Act are expected to utilise habitat present within the Proposal site.

Targeted surveys for the Purple Copper Butterfly (*Paralucia spinifera*) did not identify any areas of suitable habitat. During the field investigation only *Bursaria spinosa ssp. spinosa* was recorded, this plant is not known to be utilised by the Purple Copper Butterfly. As such, the Purple Copper Butterfly is not expected to be present within the Proposal site.

The Oberon Council is identified within Schedule I of SEPP 44 (Koala Habitat Protection) as a Local Government Area in which Koalas are known to occur. *Eucalyptus viminalis* was recorded during surveys, and is a listed Koala feed tree under Schedule 2 of SEPP 44. Within the Proposal site, *E. viminalis* constitutes greater than 15% of the total tree canopy and therefore, constitutes Potential Koala habitat. During the field surveys no koalas were observed, none were heard calling during the nocturnal surveys, and no characteristic scratching or scats were found. As such, the Proposal site is not considered to be Core Koala habitat (Refer to Section 4.3.1).

#### 2.2.7 Non-indigenous Heritage

The Jenolan Caves Road was first constructed on its current alignment in the 19th century, and was completed in c.1896. The alignment is consistent with construction for horse-drawn or early motorised vehicles (constant grade of about 5%, with no geometric control over horizontal alignment) and has only been slightly modified since that time.

As part of the original construction, numerous retaining structures were built to support the formation on the down slope side. These were generally dry stone structures up to about 2m in height, although some were higher. There are approximately eighty dry stone walls present along Jenolan Caves Road. Dry stone walls are present within the Proposal site. The dry stone walls are not listed on any heritage registers, but are relics under the NSW Heritage Act 1977. With reference to the State Heritage Register assessment criteria, the dry stone walls have a low local significance due to their value from a historic perspective (ie. construction in 1896).

#### 2.2.8 Sensitive Noise Receptors

The Proposal site exists within a natural bushland area that is subject to road noise (ie. tourist cars and buses), with low background noise levels. The Jenolan Caves Reserve Trust has advised that there are no private residences located nearby the Proposal site. No sensitive noise receivers are present in the vicinity of the Proposal site, except for guests staying at the Bellbird cottage approximately 100m east of the southern end of the Proposal site. Other noise receivers would be guests staying in the following Jenolan Caves Trust accommodation:

- Caves House (located approximately 400m west of the Proposal site);
- Jenolan Caves Camping ground (located approximately 600m east of the Proposal site (southern end); and
- Jenolan Caves cottages (located approximately 600m south of the existing stockpile/compound site).

### 2.2.9 Air Quality

The closest DEC Air quality monitoring site to the Proposal site is Bathurst, located approximately 60km away. The two parameters measured at Bathurst are ozone and number of particles less than 10 micrometers in diameter. Both the maximum one hour averages were well under the DEC goal measurements. Due to the absence of any nearby major pollutant sources, air quality within the Proposal site can be expected to be good.

Carter Holt Harvey Wood Products Australia Pty Limited (Carter Holt Harvey MDF) and Carter Holt Harvey Wood Products Australia Pty Limited (Structaflor Oberon) are the top two facilities for pollutant emissions for the Oberon LGA. Both facilities are located at Oberon, approximately 20km south east of Proposal site. Both facilities contribute low emissions (ie. less than 25% of total emissions for each substance) of Polychlorinated dioxins and furans, Total Volatile Organic Compounds, Polycyclic aromatic hydrocarbons and Particulate Matter (10.0 um). The Carter Holt Harvey Wood Products Australia Pty Limited (Carter Holt Harvey MDF) facility contributes medium emissions (ie. 26-50% of total emissions for each substance) of Formaldehyde (methyl aldehyde) (DEH 2005). The two facilities have a low potential to impact on air quality within the Proposal site during high wind periods.

# 2.2.10 Visual Amenity

A landscape and visual assessment of the Proposal was undertaken by Urban Design Office in February 2005 (Refer to **Appendix B** for the full report).

Jenolan Caves Road offers spectacular views of the World Heritage listed native bushland located below the roadway. The nearby Jenolan Caves are well known for recreation activity, and is a popular destination for cave tours, bushwalks, camping, picnics, bird watching and weddings (JCRT 2004). The nearby Kanangra-Boyd National Park is known for its vast gorges, high lookouts and wild and scenic rivers. Recreation activities within the national park include bushwalking, camping, picnics, bird watching and abseiling.

View corridors within the Proposal site are almost exclusively confined to the road corridor itself and therefore road users are the principal viewer group. Distant views back to Jenolan Caves Road from adjacent high ridges do not provide sufficient visual access to be of consequence due to the distance (over 1km), and due to the effective screening of vegetation growth. There is no visual access from the Jenolan Caves Camping ground to Jenolan Caves Road, and there is no visual access from nearby lookouts or rest areas to Jenolan Caves Road.

The visual amenity of the Proposal site is considered to be high, due to it being surrounded by native bushland.

Each of the cut slopes displays a similar landscape character of open forest, with trees to about 10m in height with a moderate foliage cover. The shrub layer is generally sparse with low shrubs to 1m, occasionally to 3m in height. The groundcover consists of a variable layer of sparse grasses and herbs. From distant views toward the Proposal site, the foliage cover is

generally fairly dense, screening the road completely. Within the road corridor, white guide posts (Im high) are present at 2m spacings along the road edge, and dry stone retaining walls are present on the downslope side of the road.

The existing stockpile/compound site is a highly disturbed area and has been previously used as a parking area for tourist coaches and for road materials storage. Large mounds of old road base and pavement material occur across the site and the area is vegetated by weed species. There is a secure fenced area within the existing stockpile/compound site, containing demountable offices and storage sheds. Some hardy native species occur in the disturbed area. The surrounding bushland is vegetated by the native eucalypt forest up to 15m high, with a moderate cover, and an open shrub understorey and groundcover of sparse grasses and herbs.

#### 2.2.11 Existing and Forecasted Traffic

Jenolan Caves Road is used by light and heavy vehicles (tourist coaches 6%). The light vehicle traffic load along Jenolan Caves Road consists mainly of tourist traffic (230-280 vehicles per day on weekdays, 420-500 vehicles per day on weekends), and there is currently no traffic growth.

#### 2.2.12 Socio-economic Considerations

Landuse in surrounding areas is dominated by nature-based activities (eg. cave tours, bushwalking) and nature conservation. The Jenolan Caves village is located on Jenolan Caves Road 400m west of the Proposal site. The villages of Lowther and Hampton are located on Jenolan Caves Road north of the Proposal site. The Proposal site is surrounded by the Jenolan Caves Karst Conservation Reserve. Kanangra-Boyd National Park is located approximately 1.2km east of the Proposal site, and to the immediate east of the existing stockpile/compound site. Jenolan Karst Conservation Reserve and Kanangra-Boyd National Park are part of the Greater Blue Mountains World Heritage Area. The Six Foot track is located to the immediate east of the existing stockpile/compound site. Visitation to the Jenolan Caves has been declining in recent years, and visitation to Kanangra-Boyd National Park is generally low due to it's remote location.

Jenolan Caves House provides public accommodation, and is located within the Jenolan Caves village. Jenolan Caves cottages provide public accommodation at the top of the "5 Mile Hill", approximately 600m south of the existing stockpile/compound site. Bellbird cottage is located approximately 100m to the east of the southern end of the Proposal site. Bellbird cottage provides public accommodation at a spur overlooking the Jenolan River. Hydro cottage is located nearby the Bellbird cottage. Hydro cottage is a residence owned by the Jenolan Caves Reserve Trust, but is not currently leased. Jenolan Caves Camping ground is located approximately 600m north east of the southern end of the Proposal site. Private bus companies provide public transport to Jenolan Caves via Jenolan Caves Road.

# 3 Description of the Proposal

# 3.1 Description of the Proposal

All proposed works would be undertaken within the existing RTA road reserve for Jenolan Caves Road. The Proposal would improve road safety along Jenolan Caves Road by reducing the risk level of cut slopes, and by limiting the potential for further geotechnical hazards to develop. The Proposal would include the following works at ten (10) cut slope sites:

- Scaling of loose rocks;
- Crest treatment (ie. removal of unstable rock and soil), vegetation removal and slope regrading;
- Installation of metal rock bolts and face plates (both grey in colour);
- Installation of metal rock catch fencing (the colour would be chosen to blend in with the faces of the cut slopes); and
- Minor application of shotcrete and/or mortar may be required at the cut slope sites.

Refer to Table 3.1, Section 3.2.1 and **Appendix D** for further details/design drawings of the proposed works.

 Table 3.1
 Proposed cut slope remediation work details.

	Proposed works <sup>1</sup>		
Cut slope chainage / cut slope height	Crest treatment and regrading (m <sup>3</sup> )	Scaling of loose rock (m³)	Installation of rock bolts
1.74 (6m)	70	ı	0
2.63 (5.5m)	85	8	34
3.64 (20m) <sup>2,3</sup>	0	100	0
4.22 (5m)	50	12	15
5.08 (8m)	325	20	11
5.29 (6m) <sup>4</sup>	70	30	18
7.02 (7m)	500	5	6
7.44 (5m) <sup>5</sup>	25	0	2
7.58 (7m)	70	30	17
8.13 (10m) <sup>6</sup>	73	5	25
Totals	1268	211	128

- 1: A small amount of vegetation (ground covers, shrubs and trees) would require removal.
- 2: Six small diameter holes (150mm) would be drilled, then piezometers and inclinometers inserted to monitor geotechnical conditions. Two small concrete pits would be established locally to temporarily store data loggers, and short lengths of trenching would be required to install cabling.
- 3: An access track/work area above cut 3.64 is not included in the scope of works for this REF, even though the access track/work area above cut 3.64 has been assessed by the 'Ecology' and 'Landscape and Visual' specialist studies. A separate REF would be prepared to assess the impact of an access track/work area above cut 3.64.
- 4: Between chainages 5250-5290 either the existing earth drain would be widened slightly, or a rock catch fence would be installed.
- 5: Cut slope 7.44 is also known as Wall 40/41
- 6: Between chainages 8105-8120 and 8158-8168, rock catch fencing would be installed.

The following design constraints apply to the Proposal:

- Due to physical constraints of Jenolan Caves Road, access for heavy machinery and construction vehicles would be restricted; and
- The existing road formation is very narrow, and therefore the majority of work would only be possible during nightly road closures.

#### 3.2 Construction Activities

# 3.2.1 Construction Processes and Work Methodology

Construction processes and work methodology would include the following:

#### Crest treatment and regrading

- Crest treatment would involve selected removal of identified geotechnical hazards (rocks greater than 200mm);
- Where regrading of rock cuttings is undertaken, the back slope would be cut at 0.5H:1.0V;
- In areas with remediation involving the clearing of rocks above the crest of the slope, the zone of clearing would be up to 5m from the crest; and
- Trees along the crest that present an OH&S risk would be removed.

#### Scaling of loose rock

- Scaling would involve the selected removal of rocks that represent a geotechnical hazard. This includes rocks which are isolated from the rock mass and have moved from their original in-situ location;
- · Large rocks identified as being loose would be carefully removed by an excavator; and
- Where large areas of scaling are proposed (ie. areas of root jacking), an excavator would be used.

#### Rockbolting

- Rockbolts would be installed to reinforce the cut slopes;
- Rockbolts would incorporate a polyethylene sheath and hemispherical dome with a grout injection hole, retainer ring and nut. They would be installed in a nominal 45mm diameter drilled hole;
- Rockbolts would have a minimum design life of 50 years;
- Water would be used as a lubricant to undertake the drilling;
- Prior to inserting the rock bolts into the drill holes, drill cuttings/sludge would be removed from the drill holes and placed in watertight containers; and
- Rockbolts would be 22mm in diameter, and between 2.1m and 3.6m long. Each rockbolt would be furnished with a steel face plate (150mm x 150mm).

#### Rockbolt grouting

- Cement grouting of the bolts would be completed subsequent to initial installation;
- The cement grout would be of a toothpaste consistency with a water/cement ratio (by weight) of between 0.35 to 0.4;
- The grout would be injected through a grout injection hole at the head of the bolt to provide complete coverage inside and outside of the polyethylene sheath;
- Grouting pressure would be no more than is required to fill the drill hole with grout, but would be adequate to displace groundwater from within the drill hole. Grouting would be continued until a consistent flow of grout is emerging from a breather hole in the bearing plate. The breather hole would than be plugged; and

• Rock bolt face plates would be sealed to ensure the grout is contained within the drill hole. The bolt heads would be protected by a coating of epoxy resin.

#### Rock catch fencing

- Fencing would be installed in accordance with RTA requirements (ie. DCM 161);
- Fencing would be double twist with hot-dipped galvanised steel posts; and
- The fence height above the road level would be 1500mm, and post spacing would not exceed 3m.

#### Shotcreting and/or mortar packing

- Application of shotcrete and/or mortar may be required at the cut slope sites (up to  $10m^2$  area in total).
- Use of shotcrete and/or mortar would be limited to small-scale applications to seal erodable soil seams and/or highly weathered rock.

#### Waste disposal

- Material removed (ie. rock, soil and vegetation) would be temporarily stored at the existing stockpile/compound site; and
- Rockbolting and grout waste (ie. bolts, drill cuttings/sludge, grout and epoxy resin) would be disposed of at a licenced waste facility.

#### 3.2.2 Construction Equipment

Construction equipment is expected to include:

- Scaling bars;
- Excavators;
- Cherry pickers;
- Air track:
- Small trucks:
- Chainsaws:
- Bobcats;
- Shotcreting/mortar packing equipment;
- · Augers; and
- · Lighting.

#### 3.2.3 Access

Access along Jenolan Caves Road within the Proposal site is planned to be restricted from Sunday nights to Thursday nights inclusive from 4pm to 10am. Remediation works are proposed to be undertaken during these times due to the narrowness of the road, and to prevent interruptions to traffic flow. Access along Jenolan Caves Road would be available during the winter school holiday period from 2-17 July 2005. Construction vehicles would enter/exit the Proposal site from both the northern and southern ends of the Proposal site from Hartley or Oberon. The posted speed limit of 40kph with 20kph advisory signs would remain unaffected by the Proposal.

#### 3.2.4 Utilities

No adjustment to utilities would be required to implement the Proposal.

#### 3.2.5 Source of Material

No fill material is anticipated to be required by the Proposal.

#### 3.2.6 Additional Truck Movements

Up to approximately 200 truck movements would be required to undertake the works. The truck movements would be undertaken over 20 nights, with a maximum of 10 truck movements per night (including water tankers). Water would be sourced from Lithgow or

Oberon town supplies, and would be delivered in a 10,000L water tanker (maximum one truck per night over 20 nights).

#### 3.2.7 Stockpile and Compound Sites

One stockpile/compound site (approximately 0.5ha) would be located at the northern end of the works adjacent to Jenolan Caves Road (see **Appendix C**). The site is owned by the RTA and is currently being used as a stockpile/compound site. The site has been cleared of native vegetation, and road-building materials are currently stored at the site. The site is only vegetated with weed species (no noxious plant species are present) and commonly occurring hardy native groundcovers. The majority of the stockpile/compound site ground surface is covered in loose blue-metal gravel. A fenced site office and cement washout bays are established at the stockpile/compound site. Machinery, materials (ie. grout mix, rock bolts, rock catch fencing) and waste (temporary storage) would be temporarily stored at the stockpile/compound site.

Portable toilets would be utilised at stockpile/compound site(s), and sewage would be disposed of off-site at DEC approved locations.

Temporary small stockpile/compound sites may also be established at small rest areas located along Jenolan Caves Road on a need basis. These rest areas are located within the RTA road reserve, and currently receive minimal public use. These sites have been cleared of native vegetation (no noxious plant species are present) and some road building materials are occasionally stored at the sites. These sites consist of grass cover, bare earth and loose blue-metal gravel. Construction materials from the proposed works would be stored at these stockpile/compound sites.

### 3.3 Workforce and Working Hours

The workforce would comprise up to twelve personnel. Standard working hours adopted by the RTA are detailed below:

#### Standard Working Hours:

Monday – Friday:

7.00am to 6.00pm

Saturday:

8.00am to 1.00pm

Sunday and Public Holidays:

No work.

The works would be undertaken partially during non-standard working hours (ie. from 4pm to 10am) from Sunday nights to Thursday nights inclusive.

As works would be undertaken outside of the standard working hours, the procedure contained in the RTA's *Environmental Noise Management Manual 2001*, "*Practice Note vii – Roadworks Outside of Normal Working Hours*" would be followed.

#### 3.4 Period of Construction

It is anticipated that works would commence on 14 June 2005 and be completed by 14 October 2005 given ideal working conditions.

# 3.5 Proposal Cost and Source of Funds

The Proposal would cost approximately \$2M and funding allocation would be sourced from NSW Government Maintenance Funds.

#### 4.1 Local Environmental Plans

Development on land within the Oberon Local Government Area (LGA) is controlled by Oberon Council under the *Oberon Local Environmental Plan 1998* (LEP). The zoning within the Proposal site is Zone No I (a) (Rural 'A' Zone). Zoning in nearby areas include Zone No I (d) (Non Urban 'D' Zone) south of the Proposal site at Jenolan Caves, and Zone No 8 (National Parks Zone) at the north end of the Proposal site (east side). The Proposal is not prohibited under Zone I (a). Consent would be required for works undertaken within Zone No I (a) (Rural 'A' Zone).

Section 38 of the LEP (Public Authority works) states "Nothing in this plan requires the Council or any other public authority to obtain consent for development on land within any zone for the purpose of roads, stormwater drainage, recreation areas, landscaping, gardening, bushfire hazard reduction or parking." Accordingly, the RTA would not require development consent to undertake the proposed works.

Relevant LEP clauses for which consent from Council is required have been considered below:

#### Environmentally sensitive land

The Jenolan River is classified as environmentally sensitive land in Schedule I of the LEP. The Council must not consent to the carrying out of development on environmentally sensitive land if, in the opinion of the Council, the carrying out of the development will degrade the environment. Providing the proposed site specific safeguards are implemented, the Proposal is not expected to degrade the Jenolan River. Consent would therefore not be required for the works.

#### Heritage items

The Six Foot Track, and Jenolan Caves Reserve (Heritage Conservation Area) are both listed in Schedule 2 of the LEP. The Six Foot track is located to the immediate east of the existing stockpile/compound site, and the Jenolan Caves Reserve is located adjacent to the Proposal site on either side of the Jenolan Caves Road Reserve. Development consent would be required if the Proposal would adversely affect the heritage significance of the Six Foot Track and/or the Heritage Conservation Area. The Proposal is not expected to adversely affect the heritage significance of the Six Foot Track or the Heritage Conservation Area. Consent would therefore not be required for the works.

#### Water catchment area

Where a development application is received for land considered by the Council to be within a water catchment area, the Council must not grant consent unless it has considered:

- (a) the impact of the proposed development on the water quality of stored waters within the water catchment area, and
- (b) the impact of the proposed development on the ecological integrity of the water catchment area.

The Proposal is not expected to adversely affect the water quality of stored waters within the water catchment area or the ecological integrity of the water catchment area. As consent is not required, this requirement would not affect the Proposal.

# 4.2 Regional Environmental Plans

# 4.2.1 Sustaining the Catchments – The Regional Plan to protect the drinking water catchments

This draft Regional Plan is currently on public display. Once finalised it would establish the *Drinking Water Catchments Regional Environmental Plan No 1* which would repeal SEPP 58 (see Section 4.3.2). Although the document places no legislative requirements on the RTA, consideration of the aims of the REP have been made.

It is not expected that the Proposal would result in any adverse impacts to the water quality of the catchment and would therefore be in accordance with the aims of the *Drinking Water Catchments Regional Environmental Plan No 1*. For reference, the aims of the REP are to:

- a) create healthy water catchments that will deliver high water quality while sustaining diverse and prosperous communities,
- b) provide the statutory components in Sustaining the Catchments that, together with the non-statutory components in Sustaining the Catchments, will achieve the aim set out in paragraph (a), and
- c) achieve the water quality management goals of:
  - i) improving water quality in degraded areas and critical locations where water quality is not suitable for the relevant environmental values and
  - ii) maintaining or improving water quality where it is currently suitable for the relevant environmental values.

# 4.3 State Environmental Planning Policies

The following State Environmental Planning Policies (SEPPs) apply to the Proposal:

#### 4.3.1 SEPP 44 - Koala Habitat Protection

The Oberon Council is identified within Schedule I of SEPP 44 (Koala Habitat Protection) as a Local Government Area in which Koalas are known to occur. While the requirements of the SEPP do not technically apply to this Proposal, as it is not subject to Council consent, it is the RTA's practice to consider SEPP 44 criteria in its EIA process. These criteria relate to the percentages of feed tree cover, particularly trees listed under Schedule 2 - Known Feed Trees. The assessment criteria consider the percentage cover of known feed trees, and whether these are greater or less than 15% of the total tree canopy.

Eucalyptus viminalis was recorded during surveys, and is a listed Koala feed tree under Schedule 2 of SEPP 44. Within the Proposal site, *E. viminalis* constitutes greater than 15% of the total tree canopy and therefore, constitutes Potential Koala habitat. During the field surveys no koalas were observed, none were heard calling during the nocturnal surveys, and no characteristic scratching or scats were found. As such, the Proposal site is not considered to be Core Koala habitat. Given the limited extent of the works proposed, the known ability for Koalas to traverse open ground, combined with the amount of bushland present both adjacent to and beyond the limits of the Proposal site it is not considered that the Proposal would have a significant impact on any Koala individuals, their populations or habitat. Therefore a Plan of Management for the conservation and management of areas of Koala habitat is not required to be prepared as part of the Proposal.

# 4.3.2 SEPP 58 - Protecting Sydney's Water Supply

SEPP 58 aims to limit the impact of development on water quality. This SEPP applies to the catchments that comprise Sydney's water supply. The Proposal site is within this area. Schedule 2 of SEPP 58 requires all transport facilities including major road works to obtain development consent. The Proposal is not classified as major road works.

Clause 10 of SEPP 58 sets out three matters to be considered irrespective of the Proposal requiring development consent. They are as follows:

a) whether the development or activity will have a neutral or beneficial effect on the water quality of rivers, streams or groundwater in the hydrological catchment, including during periods of wet weather.

It is not anticipated that the Proposal would have any adverse effects on the water quality of rivers, streams or groundwater in the catchment.

b) whether the water quality management practices proposed to be carried out as part of the development or activity are sustainable over the long term.

Erosion and sediment control measures would be implemented during the proposed works. In the long term, no water quality management practices would be required, as the Proposal would have no effect on the water quality of the catchment.

c) whether the development or activity is compatible with relevant environmental objectives and water quality standards for the hydrological catchment when these objectives and standards are established by the Government.

The Proposal is not expected to have an adverse affect on water quality, and therefore would not be incompatible with relevant environmental objectives and water quality standards for the catchment.

#### 4.4 Confirmation of Part 5 Position

All relevant statutory planning instruments have been examined for the Proposal. It is concluded that Section 38 of the Oberon LEP operates to remove the development consent requirements, thereby permitting assessment of the Proposal under Part 5 of the EP&A Act.

# 5 Strategic Stage

# 5.1 Strategic Planning

The Proposal would be funded by State Maintenance funds and is part of an ongoing commitment by the RTA to address road safety in accordance with the RTA's responsibilities for ensuring a maximum level of service to road users and to maintain appropriate services for adjacent landholders.

The Proposal would contribute to achieving the objectives set out in *Road Safety 2010*. Road Safety 2010 is a strategy developed to help New South Wales move towards having the safest roads in the world and sets out how the road toll can be halved through change in a number of areas. This Proposal would contribute to the objective of safer roads. The remediation of cut slopes on Jenolan Caves Road would create a safer road and therefore help the RTA achieve the objectives of *Road Safety 2010*.

# 5.2 Need for the Proposal

The remediation of cut slopes is needed to reduce the assessed risk level (ARL) of the cut slopes to 3 or better. The works would improve road safety in accordance with objectives set out in *Road Safety 2010*.

<sup>&</sup>lt;sup>1</sup> The RTA's Guide to Slope Risk Analysis classifies sites as follows:

<sup>•</sup> High risk sites have an Assessed Risk Level (ARL) rating of 1 or 2;

Medium risk sites have an ARL rating of 3 or 4; and

Low risk sites have either an ARL rating of 5, or are other natural batters or cut or fill slopes.

# 6.1 Proposal Objectives

The main objective of the Proposal is to remediate cut slopes to reduce the assessed risk level (ARL) of the cut slopes to 3 or better.

A secondary objective of the Proposal is to maintain road safety by maintaining the current speed limit of 40kph with 20kph advisory signs.

# 6.2 Options Considered

#### Option I - Do Nothing

This option was not considered suitable, as it would not address the RTA's responsibilities to maintain classified roads in accordance with the Proposal's objectives.

#### Option 2 - Major structural treatment

Major structural treatment would include a combination of rock fall shelters, retaining walls, gabion walls, pattern rock bolting, flexible meshing and shotcreting.

This option would address the RTA's responsibilities to maintain classified roads in accordance with the Proposal's objectives, but was considered not suitable, as the obtrusive appearance of a major structural treatment would detract from the attractive appearance of the natural bushland setting.

#### Option 3 - Major realignment

Major realignment would involve realignment of the road where the topography permits by constructing new cut slopes on the upslope side of the existing road.

This option would address the RTA's responsibilities to maintain classified roads in accordance with the Proposal's objectives, but was considered not suitable for the following reasons:

- Major realignment works would create new cut slopes that would have an obtrusive appearance for the short to medium term, which would detract from the attractive appearance of the natural bushland setting; and
- New cut slopes could have geotechnical stability problems, which cannot be predicted (ie. the new cut slopes could be less geotechnically stable than the existing cut slopes).

#### Option 4 - Local treatment (Preferred Option)

Option 4 would include the following works:

- Scaling of loose rocks;
- Crest treatment (ie. removal of unstable rock and soil), vegetation removal and slope regrading;
- Installation of metal rock bolts and face plates;
- Installation of metal rock catch fencing; and
- Application of shotcrete and/or mortar may be required at the cut slope sites (up to 10m<sup>2</sup> area in total).

This option was considered suitable, as it would address the RTA's responsibilities to maintain classified roads in accordance with the Proposal's objectives, and would not detract from the appearance of the attractive natural bushland setting in the medium to long term.

# 7 Background Investigations and Consultation

# 7.1 Background Investigations and Database Searches

The following results were obtained from desktop database searches conducted for the study area. The information below provides a summary of the search results. Copies of all the search results are provided in **Appendix E**.

#### Australian Heritage Database

The Australian Heritage Database was searched on 17 January 2005 for the Oberon LGA. The database returned 25 items, however only three are in close proximity to the Proposal site. 'The Greater Blue Mountains Area' is a declared place on the World Heritage List and covers the area surrounding the Proposal site including Kanangra Boyd National Park and the Jenolan Caves Reserve. 'Kanangra Boyd National Park' is a registered place on the Register of the National Estate (RNE). It is located to the immediate east of the existing stockpile/compound site, and approximately 700m east of the Proposal site (cut 3.64) at its closest point. 'Jenolan Caves and Reserve' is listed as a registered place on the RNE. The reserve is located adjacent to the Proposal site, on either side of the Jenolan Caves Road Reserve. The Jenolan Caves are located approximately 100m west of the Proposal site (cut 8.13). These items are not expected to be affected by the Proposal. Refer to Section 8.5 for further discussion.

# NSW Heritage Office State Heritage Register/Inventory

The NSW Heritage Office State Heritage Register/Inventory was searched for the Oberon LGA on 17 January 2005. Three items are State listed. One State listed item, Jenolan Caves Reserve, is located adjacent to the Proposal site, on either side of the Jenolan Caves Road Reserve.

Forty-two items are listed by Oberon Local Government/State Government Agencies. Five items listed by Oberon Local Government [Kanangra Boyd National Park, Jenolan Caves (listed twice), Jenolan Caves Reserve and the Six Foot Track] are located in the vicinity of the Proposal site. The Six Foot Track is located to the immediate east of the existing stockpile/compound site. (Refer to the section above on "Australian Heritage Database" for locations of the other listed items). Jenolan Caves House is listed on the Oberon LEP (but not on the NSW Heritage Office State Heritage Register/Inventory). Jenolan Caves House is located approximately 400m west of the Proposal site. These items are not expected to be affected by the Proposal. Refer to Section 8.5 for further discussion.

#### **National Native Title Tribunal**

The National Native Title Tribunal was searched for the Oberon LGA on 17 January 2005. Five Native Title applications have been lodged within the Oberon LGA. The Gundungurra Tribal Council Aboriginal Corporation #6 Native Title application (NC97/7) is active and applies to the entire Proposal site. There are no records of Indigenous Land Use Agreements within the Proposal site. Refer to Section 8.6 for further discussion.

#### NSW DEC Aboriginal Heritage Information Management System (AHIMS)

The DEC AHIMS was searched for the Proposal site (including a 1km buffer) on 30 April 2004. Eighteen Aboriginal objects and places were found. Only four of the Aboriginal objects and places were within 1km of the Proposal site. A burial site is located 350m west of the Proposal site (southern section), two open camp sites are located approximately 400m south of the existing stockpile/compound site and a burial site is located 500m northwest of Proposal site (southern section). These items are not expected to be affected by the Proposal.

Following undertaking the above search on 30 April 2004, the Pejar LALC and Gundungurra Tribal Council inspected the Proposal site on 21 May 2004 with the RTA Project Manager and the RTA's APC. The Pejar LALC and Gundungurra Tribal Council had no concerns regarding Aboriginal objects and/or places within or in the vicinity of the Proposal site. Refer to Section 8.6 for further discussion.

#### NSW DEC Atlas of NSW Wildlife - Threatened Flora and Fauna Records

The DEC Wildlife Atlas Flora and Fauna records were searched for the Proposal site (including a 2km buffer) on 29 April 2004. Three threatened flora species were recorded in the vicinity of the Proposal site. The closest, *Stemmacantha australis* was found 1.8km east of the Proposal site (southern section).

The DEC Wildlife Atlas recorded fourteen fauna sitings within the vicinity of the Proposal site. The closest siting to the Proposal site was a Brush-tailed rock wallaby (*Petrogale penicillata*) approximately 450m west of the Proposal site (southern section). There were several other fauna sitings located nearby the Brush-tailed rock wallaby siting. These items are not expected to be affected by the Proposal.

Following undertaking the above search on 29 April 2004, Lesryk Environmental Consultants have prepared an ecological assessment of this Proposal, including undertaking searches of the NSW DEC Atlas of NSW Wildlife - Threatened Flora and Fauna Records. For more discussion and information refer to Section 8.4 and **Appendix E**.

#### **DEH Protected Matters (EPBC Act) Database**

The Commonwealth Department of Environment and Heritage Database was searched for the Proposal site on 17 January 2005. A summary of the EPBC Act database search is provided below. The complete results of the search are provided in **Appendix E**. It should be noted that the species identified in this database search include all species whose habitat requirements may be found in the search area rather than known occurrences from the Proposal site.

None found

World Heritage Properties
National Heritage Places
Wetlands of International Significance

Commonwealth Marine Areas
Listed Marine Species
Threatened Ecological Communities
Threatened Species
Migratory Species
Commonwealth Lands
Commonwealth Reserves
Regional Forest Agreements

I found
None found
Within the same catchment as Macquarie
Marshes Nature Reserve
None found
I2 found
None found
I8 potentially occurring
8 potentially occurring
I found
None found

These listed items are not expected to be affected by the Proposal. Refer to Sections 8.4, 8.5 and 10.2, and **Appendix E** for further discussion and information.

#### NSW DPI FishFiles Database and Threatened Species List

The NSW Fisheries FISH FILE Database was searched on 17 January 2005 for the Hawkesbury-Nepean catchment. Silver perch (*Bidyanus bidyanus*) and Macquarie perch (*Macquaria australasica*) have been recorded in Hawkesbury-Nepean catchment. These species are not expected to be affected by the Proposal.

The NSW Fisheries Threatened Species website was consulted on 24 January 2005. The following matters have relevance to the proposed works:

- Key threatening processes the degradation of native riparian vegetation along New South Wales water courses, and
- Habitat protection plans Habitat Protection Plan No. 3: Hawkesbury-Nepean River System.

Refer to Section 8.4 for further discussion.

#### **NSW DPI Noxious Weeds List**

The NSW Department of Agriculture Noxious Weeds list was searched on 17 January 2005 for the Upper Macquarie County Council control area (including Oberon Council). Several weed species are declared noxious within this control area. Blackberry (*Rubus ulmifolius*), a Class 3 weed, is present within the Proposal site at cut slopes 4.22, 7.02, 7.58 and 8.13. Refer to Section 8.4 for further discussion.

#### **NSW DEC Contaminated Land Records**

The NSW DEC Contaminated Land Records were searched on 24 January 2005 for the Oberon Council area. No contaminated land is listed as present within the Oberon LGA. Oberon Council has advised that they are not aware of any contaminated sites located within the Proposal site. Refer to Section 8.4 and 8.11 for further discussion.

#### **NSW DEC Air Quality Information**

The NSW DEC Air Quality database was searched on 24 January 2005. The closest DEC Air quality monitoring site to the Proposal site is Bathurst. The two parameters measured here are ozone and number of particles less than 10 micrometers in diameter. Both the maximum one hour averages were well under the DEC goal measurements. These measurements are unlikely to be affected by the Proposal. Refer to Section 8.8 for further discussion.

#### The DEH National Pollutant Inventory

The National Pollutant Inventory was searched on 8 February 2005 for the Oberon LGA. Carter Holt Harvey Wood Products Australia Pty Limited (Carter Holt Harvey MDF) and Carter Holt Harvey Wood Products Australia Pty Limited (Structaflor Oberon) are the top two facilities for pollutant emissions for the Oberon LGA. Both facilities are located at Oberon, approximately 20km south east of Proposal site. The top pollutant sources within the Oberon LGA are: Other Wood Product Manufacturing; Basic Chemical Manufacturing; Cropping – Murray-Darling Basin; Unimproved Pasture - Murray-Darling Basin; and all others. The main substances emitted within the Oberon LGA include Formaldehyde (methyl

aldehyde), Polychlorinated dioxins and furans, Total Volatile Organic Compounds, Polycyclic aromatic hydrocarbons, and Particulate Matter (10.0 um) (DEH 2005). Refer to Section 8.8 for further discussion.

# 7.2 Government and Community Consultation and Involvement

#### 7.2.1 Government and stakeholder consultation

Relevant state government agencies and stakeholders were contacted and provided with the opportunity to comment on the Proposal. Table 7.2.1 lists the government agencies and stakeholders that were invited to comment on the Proposal for this REF. Responses received are summarised in column 1, while column 2 identifies the Section in the REF where addressed.

Table 7.2.1: Summary of issues raised by government agencies and stakeholders.

Summarised Issues	Section in REF Where Addressed
Department of Environment and Conservation (DEC)	
A response to the consultation letter dated 27 April 2004 was received in May 2004. DEC had the following comments to make with regard to the proposed works.	
DEC understands that the works would be fully contained within the existing road reserve and would not extend into the Kanangra Boyd National Park, nor into the Jenolan Caves Karst Conservation Area.	Sections 3.1 and 3.2
• DEC understand that the RTA will consider threatened species, and Aboriginal and Historic Cultural aspects.	Sections 8.4, 8.5 and 8.6
• DEC is aware that the RTA has made contact with the Jenolan Caves Trust Administrator and will make contact with the Sydney Catchment Authority.	Section 7.2.1
<ul> <li>The DEC contact officer will be the Kanangra Area Manager, Kim de Govrik (ph 6336 1972 or Kim.DeGovrik@npws.nsw.gov.au).</li> </ul>	Noted
Meeting with DEC	New York Control of the Control of t
A meeting was held with Geoff Luscombe (Regional Manager, Blue Mountains Region) on 3 May 2004. DEC had the following comments to make with regard to the proposed works.	
RTA Road reserve	
<ul> <li>Approval from the DEC under Part 5 of the EP&amp;A Act would not be required providing works are undertaken within the road reserve.</li> </ul>	Noted
<ul> <li>Environmental impacts of the Proposal under the EPBC Act would not need to be assessed, as the Proposal would be contained within the NSW RTA road reserve.</li> </ul>	Sections 8.4 and 10.2
<ul> <li>Stockpile site</li> <li>If the stockpile site is not located within the road reserve or on RTA owned land, the DEC recommended that the RTA obtain an agreement from the Jenolan Caves Reserve Trust to utilise the stockpile site at the top of Five Mile Hill.</li> </ul>	Section 3.2.7

Sydney Catchment Authority (SCA)	
A response to the consultation letter dated 19 April 2004 was received in	
May 2004. SCA had the following comments to make with regard to the proposed works.	
<ul> <li>The assessment must consider the matters contained in Clause 10 of SEPP 58 – Protecting Sydney's Water Supply.</li> </ul>	Section 4.3.2
• The REF should state that a Construction Environmental Management Plan would be prepared and that it would include a soil and water	Section 9.1
<ul> <li>management plan.</li> <li>Considerable care would be required to ensure excavated materials are not eroded from the site.</li> </ul>	Section 9.1
• The assessment should have regard for the draft Regional Plan – Sustaining the Catchments.	Section 4.2.1
Jenolan Caves Reserve Trust (JCRT)	
A response to the consultation letter dated 19 April 2004 was received in May 2004. JCRT had the following comments to make with regard to the proposed works.	
<ul> <li>The Trust is a statutory government body charged with the care, control and management of Abercrombie, Borenore, Jenolan and Wombeyan Karst Conservation Reserves.</li> </ul>	Noted
<ul> <li>The Trust would appreciate the additional opportunity to comment on the proposal when the relevant documentation (including the REF) becomes available.</li> </ul>	Noted
<ul> <li>Work sites are located in relative close proximity to the Jenolan River and subterranean wetlands, both of which are ecologically significant. The impact on water quality, flora and cave invertebrates warrants particular consideration due to their high susceptibility to environmental change.</li> </ul>	Section 8.3
<ul> <li>Consideration should be given to the installation of sediment traps and other forms of erosion control. A comprehensive survey of the proposed development site to "ascertain the presence or otherwise of threatened, rare or vulnerable flora and fauna communities is recommended.</li> </ul>	Sections 9.1 and 8.4
<ul> <li>Maintaining a clear thoroughfare for vehicular traffic during periods of peak visitation (i.e. 7:30am - 5:30pm daily) is important.</li> </ul>	Section 3.2
<ul> <li>Whilst it is accepted that proposed works will incur temporary impact on prevailing landscape values, the preparation of a site plan that gives consideration to parking requirements, plant storage etc. may help to reduce impacts in this regard.</li> <li>Site Compound and Stockpile</li> </ul>	Section 9.1
<ul> <li>The removal of native vegetation (including trees, shrubs and grasses), noise associated with the maintenance and use of plant, and the proximity of the proposed stockpile/compound site to accommodation facilities (i.e. Jenolan Caves Cottages) are issues of fundamental concern.</li> </ul>	Sections 8.4 and 8.10
From a practical perspective, the construction and operation of a stockpile/compound site in proximity to an established accommodation facility is less than desirable. The primary attractant for the majority of patrons is the peace and quite. Similarly, the frequent presence of native fauna (ie. wallaby and kangaroo) at and in proximity to the facility is a proven drawcard.	Sections 8.4 and 8.10
<ul> <li>The impact of the Proposal (i.e. noise and movement) on these attractants, and its potential ramifications with respect to Trust revenue streams, requires careful consideration.</li> </ul>	Sections 8.4 and 8.10

World Heritage Values	
The Jenolan Karst Conservation Reserve forms part of the Greater Blue Mountains World Heritage Area (GBMWHA). By definition, these areas require more stringent management practice then that generally applied to other parks and reserves.	Sections 8.5 and 10.2
<ul> <li>It can be expected that public scrutiny of the Proposal will be high and as such, it is recommended that a comprehensive and appropriately targeted program of community consultation public relations be developed.</li> </ul>	Noted
Karst Conservation Reserves	
<ul> <li>Karst Conservation Reserves contain natural features that are highly susceptible to disturbance. Legislation dictates that the management of these reserves should be such, that these features are protected. Any development should be of a type and design to avoid adverse impacts on these features.</li> </ul>	Sections 8.5 and 10.2
<ul> <li>Inappropriate disposal of wastes could cause damage to caves.</li> </ul>	Section 8.11
• Statutory/legislative responsibilities not being met could cause the Trust's reputation to be tarnished.	Section 1.5
<ul> <li>Inadequate site remediation could cause contamination of soil, visual amenity of Reserve to be compromised, and rockfalls and ongoing soil erosion.</li> </ul>	Section 9.1
Oberon Council	
No response was received from Oberon Council in response to the consultation letter sent 18 April 2004 at the time of publication.	NA
DIPNR	
No response was received from DIPNR in response to the consultation letter sent 18 April 2004 at the time of publication.	NA

# 7.2.2 Community Consultation and Involvement

The community would be informed of the proposed works on Jenolan Caves Road via local newspaper advertisements, community information sheets and road signage. Meetings have been held with the Jenolan Caves Reserve Trust (and lessees), and bus and coach operators to discuss completed, ongoing and future works on Jenolan Caves Road.

Community feedback (to date) regarding completed and ongoing works has been positive. The community generally understands the importance of undertaking the works to improve road safety along Jenolan Caves Road.

#### 8.1 General

This section of the REF provides a detailed description of the potential environmental impacts associated with the Proposal during both construction and operation, and provides site-specific safeguards to ameliorate the identified potential impacts.

The environmental safeguards predominately outline additional site-specific requirements which are not covered by the RTA's QA Specifications — Environmental Protection (Management System) G36, Soil and Water Management (Erosion and Sediment Control Plan) QA Specification G39, and Clearing and Grubbing QA Specification G40 for inclusion into the Contractors Environmental Management Plan (CEMP) and the Project Environmental Management Plan (PEMP). These safeguards would be implemented prior to construction, during construction and post construction. The CEMP and PEMP would be reviewed by the RTA's Regional Environmental Adviser Western Region prior to the commencement of work.

# 8.2 Landform, Geology and Soils

#### **Potential Impacts**

The Proposal would remove rock and soil material, vegetation growth at the cut slope sites, and may require minimal application of shotcrete and/or mortar. Up to 1479m³ of rock and soil material is expected to be removed by the Proposal. Due to the low density of vegetation growth present at the cut sites, only a small amount of vegetation is expected to be removed by the Proposal. Removal of the rock and soil material, and vegetation growth would create an erosion potential due to the disturbance of the cut slopes. Application of shotcrete and/or mortar would assist with stabilisation of the cut slopes. Loose soil material could be eroded from the cut slope sites by wind and water action. Natural regeneration of native ground covers and shrubs can be expected to assist with stabilising the cut slopes in the medium to long term.

Rock, soil material, and vegetation growth removed would be transported by truck to the existing stockpile/compound site. Truck movements has the potential to track mud and particles along the Jenolan Caves Road, particularly during wet weather. Erosion of rock and soil stockpiles also has the potential to occur as a result of wind and water action.

Following completion of the works, the existing potential for rock, soil and tree falls would be reduced (ie. the assessed risk level of the cut slopes would be 3 or better). The landform of the cut slopes would essentially remain the same, as only selective removal of rock, soil and vegetation would be required at each cut slope. Some parts of the majority of the cut slopes would be regraded to a flatter grade to reduce the potential for future geotechnical hazards.

#### Site Specific Safeguards

 An erosion and sedimentation control plan would be developed and incorporated into the CEMP. The plan would incorporate specifications outlined in the NSW Erosion and Sediment Control Handbook No. 2, identify areas requiring management controls,

- include inspections and checklist sheets and would be reviewed by the RTA's Regional Environmental Adviser, Western Region prior to the commencement of works.
- Temporary stormwater control devices or erosion and sedimentation controls would be implemented at stormwater drains to prevent sediment-laden runoff entering the local receiving waters. Temporary erosion control measures would be implemented at the source of disturbance to minimise any potential runoff of erodible material.
- Maintenance and checking of the erosion and sedimentation controls would be undertaken on a regular basis and records kept and provided at anytime upon request.
   Sediment would be cleared from behind barriers on a regular basis and all controls would be managed in order to work effectively at all times.
- All stockpiles would be designed, established, operated and decommissioned in accordance with the RTA's Stockpile Management Procedures 2001. In addition, all stockpiles would be located 50m away from the high bank of any rivers or drainage lines.
- Stockpiles would not be established on slopes greater than 2:1 (horizontal to vertical).
- All loose rock and soil material would be removed daily from the cut slope sites.
- Any material transported onto pavement surfaces would be swept and removed at the end of each working day.
- Hardstand material or rumble grids would be implemented at entry and exit points to minimise the tracking of soil and particulates onto pavement surfaces.
- Works would not be undertaken during periods of high rainfall.
- Site rehabilitation of disturbed areas would be undertaken progressively as works are completed at each cut slope site.
- Disturbed areas would be restored to their pre-works shape (where not regraded) at the completion of works.

# 8.3 Water Quality and Hydrology

#### Potential Impacts

The Proposal is not expected to impact on the water quality of the Jenolan River or the karst limestone caves. The Proposal would be limited to rock, soil and vegetation material removal (up to 1479m³), minimal application of shotcrete and/or mortar, and temporary storage of rock, soil, vegetation and waste material at the existing stockpile/compound site. Displaced groundwater from within drill holes, grout and epoxy resin spillage, shotcrete and/or mortar spillage, establishment of rock catch fence post holes, and drill cuttings/sludge removed from the drill holes would have a low potential to cause impacts on receiving waters. It is expected that the Proposal would only have a minor impact on erosion and sedimentation, and impacts on water quality are not expected providing the site specific safeguards below are implemented.

During drilling for rock bolts and piezometers/inclinometers, only small volumes of groundwater are expected to be encountered. No waterways or culverts would be altered by the Proposal, and no impact on hydrology and/or flooding is expected.

#### Site Specific Safeguards

An incident emergency spill plan would be developed and incorporated into the CEMP.
The plan would include measures to avoid spillages of fuels, chemicals, and fluids onto
any surfaces or into any adjacent/nearby waterways. An emergency spill kit would be
kept onsite at all times.

- All staff would be inducted to the incident emergency procedures and made aware of the location of where the emergency spill kit would be kept.
- Any accidental spills would be managed in accordance with the RTA *Emergency and Incident Response Procedure*.
- Should a spill occur during construction, the incident emergency spill plan would be implemented, and the Regional Environmental Adviser Western Region contacted.
- All fuels, chemicals, and liquids would be stored at least 50m away from any waterways
  or drainage lines and would be stored within an impervious bunded areas within the
  stockpile/compound site(s).
- The refuelling of plant and maintenance of machinery would be undertaken within impervious bunded areas within the stockpile/compound site(s).
- Vehicle wash downs and/or cement truck washouts would be undertaken within a designated bunded area of an impervious surface or undertaken offsite.
- All concrete works would be undertaken in accordance with DEC's *Environmental Best Management Practice Guideline for Concreting Contractors* (2002).
- To avoid contact with groundwater, no drill holes would be positioned at sites of known water seepage.
- Drop sheets would be used where appropriate during construction to prevent cement slurry and other materials (ie. grout and epoxy resin, shotcrete and/or mortar) from polluting any waterways.
- Excess concrete, shotcrete and/or mortar would be scraped off equipment prior to being washed. All remaining concrete, shotcrete and/or mortar residue would be collected and disposed of at a licenced landfill.
- All waste material (ie. grout, epoxy resin, shotcrete, mortar, workers refuse) would be collected and removed at the end of each working day.
- Wastewater generated from the construction process (ie. drill cuttings, sludge, displaced groundwater) would be collected, contained onsite, and treated (if necessary) in accordance with DEC specifications prior to its disposal. The release of dirty water into any waterways would be prohibited.
- Erosion and sediment control structures would be put in place to protect the water quality of the Jenolan River and the karst limestone caves.
- No polluted water generated by the Proposal would be permitted to be discharged to waterways.
- Sewage from portable toilets would be disposed of off-site at DEC approved locations.
- If any activities are likely to cause pollution of waterways, a licence would be obtained for the works under the POEO Act.

#### 8.4 Biodiversity

An ecological assessment of the Proposal was undertaken by Lesryk Environmental Consultants in February 2005 (Refer to **Appendix A** for the full report).

#### Potential Impacts

#### Flora

'The clearing of native vegetation' is a key threatening process under the TSC Act, and 'Land clearance' is a key threatening process under the EPBC Act. Impacts of the removal of the vegetation would be minor in comparison to the amount of the same vegetation types

occurring in the surrounding region (350,106ha). The Proposal would remove up to 6.15ha of native vegetation. Within the areas of likely disturbance, the vegetation communities present are considered to be of limited value for those species recorded or expected. The Proposal would not fragment, disturb or alter any movement, dispersal or pollination vectors corridors, or isolate any proximate areas of suitable habitat.

The Proposal would not cause compaction of root zones, ringbarking, or smothering or waterlogging of vegetation. Expansion of weed growth within and adjacent to the Proposal site is not expected to occur as a result of the Proposal. Operation of the stockpile/compound site (refer to Section 3.2.7) is not expected to impact on the surrounding bushland.

The Proposal would not affect any threatened species, ecological communities or populations listed on the Schedules to the TSC Act. As such, the preparation of a Species Impact Statement is not considered to be required as part of the Proposal.

The Proposal is not considered to affect, threaten or have an adverse impact on any of those plants listed under the *Commonwealth Environment Protection and Biodiversity Conservation Act 1999.* Therefore, the matter would not require referral to the Federal Minister for the Environment for further consideration or approval.

The Proposal has a minor potential to disturb Blackberry (a Class 3 weed), which is present within the Proposal site at cut slopes 4.22, 7.02, 7.58 and 8.13.

#### Fauna

The Proposal would not cause significant impacts on the following TSC Act listed species observed within the Proposal site: Powerful Owl, Sooty Owl, Yellow-bellied Glider, Large-eared Pied Bat, Large-footed Myotis, Eastern Bentwing Bat, and Eastern False Falsistrelle. The Proposal would not cause significant impacts on the Gang-gang Cockatoo (proposed TSC Act listing) observed within the Proposal site. Within the areas of likely disturbance, the habitats present are considered to be of limited value for those species recorded or expected. The Proposal sites are very small, none providing any important areas of foraging, sheltering, roosting or breeding habitat.

The Proposal would not cause significant impacts on the Large-eared Pied Bat or the Satin Flycatcher (both EPBC Act listed) observed within the Proposal site. Therefore, the matter would not require referral to the Federal Minister for the Environment for further consideration or approval.

Other native fauna species recorded within the Proposal site are protected, as defined under the NSW National Parks and Wildlife Act 1974, but considered to be common to abundant throughout their distribution ranges. These animals are regularly recorded in the surrounding region in association with their habitat types. The undertaking of the Proposal would not remove habitats important to any of these animals, such that the disturbance of these would affect the local status of any of these species. The Proposal would not present a barrier to the dispersal patterns of any of these species, nor would it isolate any proximate areas of their necessary habitats.

The Proposal is not expected to remove any hollow bearing trees, as they are located outside of the Proposal site. No critical habitat, important wildlife corridors or endangered ecological communities would be impacted, as none are present within the Proposal site. No endangered fauna populations would be impacted, as none are present within the Proposal site.

Given the limited extent of the works proposed, the known ability for Koalas to traverse open ground, combined with the amount of bushland present both adjacent to and beyond the limits of the Proposal site it is not considered that the Proposal would have a significant impact on any Koala individuals, their populations or habitat. Therefore a Plan of Management for the conservation and management of areas of Koala habitat is not required to be prepared as part of the Proposal.

# Aquatic

"The degradation of native riparian vegetation along New South Wales water courses" is a Key threatening process under the FM Act. The Proposal is not expected to cause degradation of native riparian vegetation present along the Jenolan River.

Habitat Protection Plan No. 3: Hawkesbury-Nepean River System has relevance to the Proposal site. The Proposal is not expected to cause impacts on the habitat of the Hawkesbury-Nepean River System.

Due to the minor nature of the proposed works, Silver perch and Macquarie perch (threatened FM Act listed species recorded in Hawkesbury-Nepean catchment) are not expected to be affected by the Proposal.

# Site Specific Safeguards

#### Flora

- All personnel taking part in construction activities would be instructed through regular toolbox talks in the importance of the conservation value of the surrounding World Heritage area, and the need to minimise disturbance to the area.
- The limit of disturbance would be clearly marked, and work practices, including vehicular movements, would take care to not cause any damage to any vegetation stands or potential habitat located outside construction areas.
- All earthmoving plant and equipment would be thoroughly washed down prior to arrival on site to remove all soil and weed seeds. Wash down certificates would be held on project environmental files.
- Prevention of spreading, and reduction of the quantity and distribution of Blackberry (*Rubus ulmifolius*), a Class 3 weed, at cut slopes 4.22, 7.02, 7.58 and 8.13 would be achieved by treatment of the noxious weed. Treatment of the noxious weed would be undertaken in consultation with Upper Macquarie County Council, and the CRC Weed Management Guide for Blackberry (http://www.weeds.crc.org.au/publications/weed\_man\_guides.html).
- Topsoil potentially containing weed propagules would be removed from the Proposal site and disposed of at a licenced landfill facility. Weed infested or contaminated topsoil would not be reused for revegetation works and would not be stockpiled adjacent to any areas of native vegetation.
- Weed growth present within the Proposal site (particularly at the stockpile/compound site) would be monitored weekly. Weed growth present would be removed/treated regularly to prevent the spread of weeds into adjacent bushland areas.
- If a chemical herbicide is used to suppress the growth of weed species, and/or to kill vegetation that presents a geotechnical hazard, a product would be selected that would readily break down and not impact on fauna species.
- The area of vegetation to be removed would be restricted to those areas specified in this REF. These areas would be clearly marked onsite, and on site plans prior to the commencement of works. Should additional clearing be required, the RTA's Regional

- Environmental Adviser, Western Region would be contacted and consulted to determine the need for further environmental impact assessment.
- All vegetation to be retained would be clearly highlighted on site and on site plans, and
  would be protected with fencing (or other suitable material). Protective fencing (or
  other suitable material) would be erected beyond the drip-line of trees and erected
  prior to the commencement of works. All staff would be informed and inducted of the
  limits of vegetation clearing and the areas of vegetation to be retained.
- Trees present within the cut slope sites would not be removed unless they present a geotechnical hazard (ie. causing root jacking of rock).
- All trimming of mature native trees would be undertaken by a qualified arborist.
- Vehicles and machinery would be parked in cleared areas and not under the drip-line of retained vegetation or trees. Retained vegetation or trees would not be smothered by stockpiles, sediment, or by the storage of materials and equipment.
- Construction stockpile/compound sites, stockpile sites and the storage of materials would be established within existing cleared areas.
- Cleared native vegetation would be mulched and used in site rehabilitation works (where practical).
- Cleared and disturbed areas within stockpile/compound sites would be stabilised with suitable native grasses and ground cover plants as soon as possible to prevent soil erosion.
- Work areas would be monitored regularly for up to 3 months following completion of
  construction works to identify any potential loss of topsoil and/or vegetation up-hill of
  the works due to unforeseen wash-outs or soil slippage. The need for planting mitigation
  would be re-assessed.

#### Fauna

- Any fauna species found inhibiting works within Proposal site areas to be disturbed, would be removed by licenced persons under the NPW Act 1974.
- During vegetation clearing, woody debris suitable for fauna habitat would be retained and replaced on site outside of clear zones, as the removal of any dead wood, trees and logs is a Key Threatening Process under the TSC Act.

# Aquatic

- The Proposal would not cause degradation of native riparian vegetation present along the Jenolan River.
- The Proposal would be undertaken in accordance with the Habitat Protection Plan No. 3: Hawkesbury-Nepean River System.

# 8.5 Non-Indigenous Heritage

#### Potential Impacts

Providing the site specific safeguards below (and in Sections 8.2 and 8.3) are implemented, the proposed works are not expected to cause any impact on the following heritage items:

- Dry stone walls (relics);
- Jenolan Caves, Kanangra Boyd National Park, Jenolan Caves Reserve, The Six Foot Track (LEP listed heritage items); and
- The Greater Blue Mountains Area which includes the Kanangra Boyd National Park and Jenolan Caves Reserve (World Heritage listed).

### Site Specific Safeguards

- Should archaeological remains be uncovered during construction, all works would cease within the vicinity of the material/find and the RTA's Regional Environmental Adviser Western Region contacted.
- Machinery and trucks would be parked away from the downslope side of the road to avoid heavy loads being placed on the dry stone walls.
- Adverse affect on the heritage significance of the Six Foot Track would be avoided by maintaining foot access along the Six Foot Track (including installation of track markers) in the vicinity of the stockpile/compound site.

# 8.6 Indigenous Heritage

#### **Potential Impacts**

The Pejar LALC and Gundungurra Tribal Council inspected the Proposal site on 21 May 2004 with the RTA Project Manager and the RTA's APC. The Pejar LALC and Gundungurra Tribal Council had no concerns regarding Aboriginal objects and/or places within or in the vicinity of the Proposal site (refer to **Appendix F**).

The Proposal site has been previously disturbed by road construction works. The Proposal would cause moderate soil and rock disturbance and removal of a small amount of native vegetation. Taking into account advice received from The Pejar LALC and Gundungurra Tribal Council (see above), the works would only have a minor potential to impact on archaeological items.

The Gundungurra Tribal Council Aboriginal Corporation #6 Native Title application (NC97/7) is active and applies to the entire Proposal site. The Proposal subsequently has a potential to impact on the Native Title application.

#### Site Specific Mitigation Safeguards

- All personnel working on site would receive training in their responsibilities under the National Parks and Wildlife Act 1974.
- Should Indigenous heritage items be uncovered during works, all works in the vicinity of
  the find would cease and the RTA's Aboriginal Programs Consultant, Regional
  Environmental Adviser Western Region, DEC representative and relevant LALC
  representatives would be contacted. Works would not re-commence until appropriate
  clearance has been received.
- The RTA's Property section would deal with the matter relating to the Gundungurra Tribal Council Aboriginal Corporation #6 Native Title application (NC97/7).

#### 8.7 Noise and Vibration

## **Operational Noise**

The Proposal would not increase the capacity or the operational noise of the road.

#### **Construction Noise**

Construction equipment likely to be used during construction would include: scaling bars; excavators; cherry pickers; air track; small trucks; chainsaws; bobcats; and augers. The works would be undertaken from 4pm to 10am, from Sunday nights to Thursday nights inclusive, which would include the following non-standard working hours:

Sunday
 4pm to midnight; and

Monday to Thursday 6pm to 7am.

Jenolan Caves Reserve Trust accommodation (Caves House, Jenolan Caves Cottages, Bellbird cottage) may be occupied during the works. The Proposal may cause noise impacts during the construction period, particularly at Bellbird cottage, which is located approximately I00m from the south end of the Proposal site. Noise impacts on visitors to Caves House and Jenolan Caves Cottages are not expected due to ample separation distances between the Proposal site and these accommodation houses.

The Jenolan Caves Camping ground can expected to be only lightly to moderately patronized at night during the April to September works period. Due to the ample separation distance between the Proposal site and camping ground of approximately 600m, the Proposal is not expected to impact on campers at the camping ground.

The RTA adopts the construction noise control criteria of the NSW DEC and EPA *Environmental Noise Control Manual (1999)*. In accordance with the DEC guidelines, target noise levels for the Proposal (5 months duration) would be 'background' +10dBA. The criteria recognises that moderate to high construction noise levels are likely to be accepted by local residents and workers due to the short-term duration activities such as those proposed. Short-term noise is also more likely to be accepted if the work is part of essential safety works such as those being undertaken for this Proposal.

Noise from night time construction activities are expected to exceed the current DEC Criteria, and the works may be expected to cause noise levels that can potentially cause adverse comment.

"Out of standard working hours" work would be undertaken to minimise impacts on traffic flow. The majority of the night work would be classified as being outside normal working hours and consequently *Practice Note vii* of the *RTA Environmental Noise Management Manual* would be adhered to at all times.

#### Vibration

No buildings are located within 30m of the Proposal site, and no blasting would be undertaken. No vibration impacts are therefore expected.

- The procedures contained in the RTA's Environmental Noise Management Manual, 2001 "Practice Notes vii Roadworks Outside of Normal Working Hours" would be followed for works undertaken outside standard hours.
- Prior to the commencement of works, the Jenolan Caves Reserve Trust would be notified of the Proposal details, including the potential for noise impacts to occur.
- Background noise levels at the Proposal site would be recorded prior to the commencement of works. Construction noise monitoring would be undertaken during the works, if it is deemed necessary by the RTA Project Manager and/or RTA Regional Environmental Advisor, Western Region.

- If accommodation cabins are occupied by Trust guests during the works, it may be necessary to vacate them (particularly Bellbird cottage) if unacceptable noise levels occur during the Proposal. The RTA Project Manager would maintain close liaison with the Jenolan Caves Reserve Trust during the works.
- The idling of machinery and equipment when not in use, and for prolonged periods of time would be prohibited.
- Best management practices would be adopted that are consistent with the RTA's Environmental Noise Management Manual, 2001.
- Noise from reverse alarms would be limited to the lowest possible levels consistent with safety or, during the night, replaced with flashing lights, or other warning devices.
   Machines with excessively noisy alarms would be modified or removed from the site.
- All machines would be in good working condition, with particular attention to exhaust silencers, engine covers and other noise reduction devices.
- Short, sharp sounds primarily caused by physical impacts, would be avoided where possible to minimise sleep disturbance to Trust guests.

# 8.8 Air Quality

#### Potential Impacts

The Proposal has a minor potential to deteriorate the local air quality as a result of vehicle emissions, and from dust from earthworks/vegetation removal and stockpile erosion generated during construction.

No change in the operational vehicle emissions is expected, as the Jenolan Caves Road speed limits would remain unchanged. In order to ameliorate the potential impacts of the Proposal on local air quality, the following mitigation measures would be incorporated.

- Construction activities that generate high dust levels would be avoided during high wind periods.
- Where dust generated by the proposed works is visible, dust suppression measures would be implemented.
- If winds are high and works are creating high levels of dust that are likely to cause
  discomfort to local residents or a safety hazard to traffic or work personnel, the works
  would be modified or stopped until the dust hazard is eliminated or has been reduced to
  an acceptable level.
- Any stockpiles and general works areas with the capacity to cause dust would be dampened or covered to suppress dust emissions.
- Long term stockpiles would be sprayed with a sterile grass mix to suppress dust generation.
- All stockpiles would be fenced with sediment control fencing.
- Truck movements would be controlled on site and restricted to designated roadways.
- To minimise exhaust emissions, vehicles and operating equipment used on-site would be switched off when not operating.
- Any materials transported in trucks would be appropriately covered to reduce dust generation.
- Tailgates would be secured during operation of trucks.

Rehabilitation of disturbed surfaces would be undertaken as soon as practicable.

# 8.9 Visual Amenity / Landscape

A landscape and visual assessment of the Proposal was undertaken by Urban Design Office in February 2005 (Refer to **Appendix B** for the full report).

# **Potential Impacts**

Visual impacts of the Proposal have been assessed in accordance with the RTA's Environmental Impact Assessment Policy Guidelines Procedures (Version 4).

# Construction Phase

The necessary presence of night lighting, warning signs, temporary safety fencing and construction equipment would have a negative impact upon the road corridor for the duration of the works. Taking into account the small scale of the proposed works, and that the proposed works would generally be executed above eye level, the overall visual impact is expected to be Moderate to Low.

Works at the stockpile/compound site are not expected to be visible to surrounding land users, as the site is surrounded by dense native vegetation.

#### Operational Phase

The rock scaling works would be limited to small well defined areas. The nature of the scaling work is such that within a short timeframe, the freshly exposed cut slope faces would weather to match the existing appearance of the cut slopes. The scaling work is generally considered to be of Low visual impact.

The crest treatment and regrading works would be similar in extent at each of the cut slopes. The zone of crest treatment and regrading works would be limited to 5m from the existing crest. The minor scale of the work against the scale and density of the existing vegetation is comparatively small. The crest treatment and regrading works is considered to be of Moderate to Low visual impact.

The size of the rock bolts/face plates (grey colour) would be limited to 150mm x 150mm, and would be constructed of ferrous iron which would quickly weather and take on an organic appearance. Against the scale of the height of the cut slopes (5-10m range) the rock bolt faces/plates would be generally considered to be of Low visual impact.

The shotcrete and/or mortar application would be limited to small areas, and is generally considered to be of Low visual impact.

The rock catch fences would not exceed 1500mm in height, 15m in length, and would only be present at up to three locations (ie. at cuts 5.29 and 8.13). The rock catch fences would be considered to be of Moderate to Low visual impact.

- The Proposal would be undertaken with the intent to only remove amounts of soil, rock and vegetation necessary to achieve the project objectives.
- The colour of the metal rock catch fencing would be chosen to blend in with the cut slope faces.

- Application of shotcrete and/or mortar would be undertaken in accordance with RTA's QA Specification B82 Shotcrete Work.
- The colour of the shotcrete and/or mortar would be chosen to match (as close as possible) the colour of the surrounding weathered rock at each cut slope site.
- The application of shotcrete and/or mortar would be minimised to that necessary to achieve stabilisation of the cut slope sites.
- Lights would be positioned to avoid light impacting on areas located beyond the Proposal site.
- The construction site would be kept tidy and rubbish free.

#### 8.10 Socio-economic Considerations

# **Potential Impacts**

Jenolan Caves Road would be closed during work periods from Sunday nights to Thursday nights (4pm to 10am) from 26 April 2005 to 23 September 2005. The timing of the works has been planned to occur outside peak periods for cave visitation (ie. summer, autumn and spring school holidays).

The Proposal would impact on visitors who would normally use Jenolan Caves Road to access Kanangra Walls and/or Jenolan Caves, including accommodation at Jenolan Caves House, Bellbird Cottage and Jenolan Caves Camping ground. Access to these destinations during the proposed work periods (Sunday to Thursday 4pm to 10am) would be possible via Oberon Road or Two-Mile Hill Road. The alternative routes are longer than the Jenolan Caves Road route, and are not suitable for tourist buses and/or coaches. Private bus companies would not be able to access Jenolan Caves via Jenolan Caves Road during work hours. During the works, buses would have to travel via Two-Mile Hill. A mini-bus shuttle service would transport passengers between Two-Mile Hill and the Jenolan Caves.

Due to sufficient separation distances between places of accommodation and the Proposal site, impacts from lighting, noise and dust are not expected.

Impacts on visitor numbers to Kanangra Walls and/or Jenolan Caves, and a subsequent reduction in tourism income is expected to be minor given that the Proposal would be undertaken during an off-peak period.

No post-construction community impacts are expected as a result of the Proposal.

- A pre-construction audit of the local network condition, with particular focus on Jenolan Caves Road would be conducted to monitor whether additional truck movements result in the deterioration of the road surface.
- A Traffic Control Plan would be prepared in accordance with the RTA's *Traffic Control at Work Sites Manual 2003*, and approved by the RTA prior to implementation. The Traffic Control Plan would include the notification of any traffic alterations or closures.
- Telstra mobile network coverage would be available at Jenolan Caves for visitors to the Jenolan Caves area.
- Access along Jenolan Caves Road would be available during the winter school holiday period from 2-17 July 2005.

- Alternate access to Kanangra Walls, Jenolan Caves and accommodation (Jenolan Caves House, Bellbird cottage, Jenolan Caves Camping ground) would be available via Oberon or Two-Mile Hill Road.
- A mini-bus shuttle service between Two-Mile Hill and the Jenolan Caves would be provided as needed.
- All construction work areas on Jenolan Caves Road would be made trafficable at the end
  of each working day.
- Jenolan Caves Road would be accessible between 10am and 4pm Monday to Thursday, and all day Friday and Saturday.
- Signs would be used to advise drivers to use alternate access routes into Jenolan Caves via Oberon Road and Two-Mile Hill Road. The signs would be located at Hartley, Hampton, Top of Five Mile Hill, Top of Two Mile Hill, Lithgow and Bathurst, and traffic access advice would be provided through the media.
- A Community Liaison Group would be established to advise stakeholders and local road users of the progress of the works, and to seek input and feedback regarding the works.
   The Community Liaison Group would consist of Jenolan Caves Trust and staff, Caves House and staff, and local business owners.
- If accommodation cabins are occupied during the works, it may be necessary to vacate them (particularly Bellbird cottage) if unacceptable noise levels occur during the Proposal. The RTA Project Manager would maintain close liaison with the Jenolan Caves Reserve Trust during the works.
- In accordance with the RTA's Community Involvement Practice Notes and Resource Manual (1988), members of the affected community (including local residents, bus companies and emergency services) would be notified of the proposed works at least two (2) weeks prior to their commencement. The notification would identify the nature of the works, give an estimated duration, advise of anticipated delays and identify any changes to traffic, wide load restrictions, or access during the works.
- All booked visitors to Jenolan Caves would be advised of traffic management arrangements prior to their visit.
- All tourist bus and coach operators travelling to Jenolan Caves would be advised of traffic management arrangements prior to travelling to Jenolan Caves.

# 8.11 Waste Minimisation and Management

#### **Potential Impacts**

The Proposal would generate the following waste streams:

- Rock, soil and vegetation material;
- Metal rockbolts and face plates off-cuts;
- Drill cuttings and sludge;
- Grout and epoxy resin;
- Concrete;
- Shotcrete and/or mortar;
- Sewage;
- Workers refuse (eg. food waste).

The principles of waste management are to minimise the amount of waste generated, recycle waste wherever possible and dispose of the remainder in a responsible manner in accordance with appropriate RTA policy. The RTA adopts the Resource Management

Hierarchy principles embodied in the *Waste Avoidance & Resource Recovery Act 2001* (WARR Act).

# Site Specific Safeguards

- A Waste Management Plan would be prepared in accordance with RTA's QA Specifications and in accordance with RTA's Waste Minimisation & Management Guidelines, 1998 and the principles of the WARR Act.
- Trees to be removed would be assessed for their value as millable timber.
- Leaf material and small branches of native vegetation would be chipped and used as mulch in revegetation works.
- There would be no burning of waste.
- All exotic plant species removed would be bagged and disposed of at a licenced landfill facility.
- All construction materials, surplus soils and wastes generated from the Proposal would be stockpiled and stored at the stockpile/compound site prior to reuse, recycling or disposal.
- All working areas would be maintained, kept free of rubbish and cleaned up at the end of each working day.
- Wastes would not be stored for long periods during construction of the Proposal.
   Empty drums of fuels, oils or chemicals and fluids would not be stored on site during construction.
- Any contaminated waste found would be identified and classified by a suitably qualified consultant
- Any contaminated waste identified or generated during the Proposal would be disposed in accordance with DEC guidelines.

In addition, the Resource Management Hierarchy principles of the WARR Act would be adopted as follows:

- 1. Avoid unnecessary resource consumption as a priority;
- 2. Avoidance is followed by resource recovery (including reuse of materials, reprocessing recycling, and energy recovery; and
- 3. Disposal is undertaken as a last resort.

# 8.12 Summary of Beneficial Effects

The Proposal has the following beneficial effects:

 The remediation of Jenolan Caves Road cut slopes would reduce the assessed risk level (ARL) of the cut slopes to 3 or better, and accordingly would improve road safety in accordance with objectives set out in Road Safety 2010.

### 8.13 Summary of Adverse Effects

The Proposal would result in some adverse effects that would include:

- Night closures of Jenolan Caves Road.
- Removal of a small amount of native vegetation.
- Potential for minor erosion and sedimentation.

- Potential for minor noise impacts.
- Potential for minor night lighting impacts.
- Potential for a minor temporary reduction in tourism income.
- A low operational impact on the high visual amenity of the Proposal site.

# 9.1 Summary of Proposed Environmental Safeguards

Environmental safeguards outlined in this document would be incorporated into the detailed design phase of the Proposal and during construction and operation of the Proposal. These safeguards would minimise any potential adverse impacts arising from the proposed works on the surrounding environment. All safeguards described in this REF and the Decision Report/ Conditions of Approval would be incorporated into the Contractor's Environmental Management Plan (CEMP) and the Project Environmental Management Plan (PEMP).

The CEMP and PEMP (if required) would be developed in accordance with the specifications set out in the RTA's Environmental Protection (Management System) – QA Specification G36, and/or G39 and G40.

 Table 9.1: Site Specific Environmental Safeguards.

<ul> <li>An erosion and sedimentation control plan would be develope and incorporated into the CEMP. The plan would incorporate specifications outlined in the NSW Erosion and Sedimental</li> </ul>
Control Handbook No. 2, identify areas requiring management controls, include inspections and checklist sheets and would be reviewed by the RTA's Regional Environmental Advises Western Region prior to the commencement of works.
<ul> <li>Temporary stormwater control devices or erosion an sedimentation controls would be implemented at stormwater drains to prevent sediment-laden runoff entering the local receiving waters. Temporary erosion control measures would be implemented at the source of disturbance to minimise an potential runoff of erodible material.</li> </ul>
<ul> <li>Maintenance and checking of the erosion and sedimentation controls would be undertaken on a regular basis and record kept and provided at anytime upon request. Sediment would be cleared from behind barriers on a regular basis and all control would be managed in order to work effectively at all times.</li> </ul>
<ul> <li>All stockpiles would be designed, established, operated an decommissioned in accordance with the RTA's Stockpile Management Procedures 2001. In addition, all stockpiles would be located 50m away from the high bank of any rivers of drainage lines.</li> </ul>
• Stockpiles would not be established on slopes greater than 2: (horizontal to vertical).
<ul> <li>All loose rock and soil material would be removed daily from th cut slope sites.</li> </ul>
<ul> <li>Any material transported onto pavement surfaces would be swept and removed at the end of each working day.</li> </ul>

Impact	Environmental Safeguards
	<ul> <li>Hardstand material or rumble grids would be implemented at entry and exit points to minimise the tracking of soil and particulates onto pavement surfaces.</li> </ul>
	Works would not be undertaken during periods of high rainfall.
	Site rehabilitation of disturbed areas would be undertaken progressively as works are completed at each cut slope site.
	<ul> <li>Disturbed areas would be restored to their pre-works shape (where not regraded) at the completion of works.</li> </ul>
Water Quality & Hydrology	<ul> <li>An incident emergency spill plan would be developed and incorporated into the CEMP. The plan would include measures to avoid spillages of fuels, chemicals, and fluids onto any surfaces or into any adjacent/nearby waterways. An emergency spill kit would be kept onsite at all times.</li> </ul>
	<ul> <li>All staff would be inducted to the incident emergency procedures and made aware of the location of where the emergency spill kit would be kept.</li> </ul>
	<ul> <li>Any accidental spills would be managed in accordance with the RTA Emergency and Incident Response Procedure.</li> </ul>
	<ul> <li>Should a spill occur during construction, the incident emergency spill plan would be implemented, and the Regional Environmental Adviser Western Region contacted.</li> </ul>
	<ul> <li>All fuels, chemicals, and liquids would be stored at least 50m away from any waterways or drainage lines and would be stored within an impervious bunded areas within the stockpile/compound site(s).</li> </ul>
	• The refuelling of plant and maintenance of machinery would be undertaken within impervious bunded areas within the stockpile/compound site(s).
	<ul> <li>Vehicle wash downs and/or cement truck washouts would be undertaken within a designated bunded area of an impervious surface or undertaken offsite.</li> </ul>
	• All concrete works would be undertaken in accordance with DEC's <i>Environmental Best Management Practice Guideline for Concreting Contractors</i> (2002).
	<ul> <li>To avoid contact with groundwater, no drill holes would be positioned at sites of known water seepage.</li> </ul>
	<ul> <li>Drop sheets would be used where appropriate during construction to prevent cement slurry and other materials (ie. grout and epoxy resin, shotcrete and/or mortar) from polluting any waterways.</li> </ul>
	<ul> <li>Excess concrete, shotcrete and/or mortar would be scraped off equipment prior to being washed. All remaining concrete, shotcrete and/or mortar residue would be collected and disposed of at a licenced landfill.</li> </ul>
	<ul> <li>All waste material (ie. grout, epoxy resin, shotcrete, mortar, workers refuse) would be collected and removed at the end of each working day.</li> </ul>

Impact	Environmental Safeguards
	<ul> <li>Wastewater generated from the construction process (ie. drill cuttings, sludge, displaced groundwater) would be collected, contained onsite, and treated (if necessary) in accordance with DEC specifications prior to its disposal. The release of dirty water into any waterways would be prohibited.</li> </ul>
	<ul> <li>Erosion and sediment control structures would be put in place to protect the water quality of the Jenolan River and the karst limestone caves.</li> </ul>
	<ul> <li>No polluted water generated by the Proposal would be permitted to be discharged to waterways.</li> </ul>
	<ul> <li>Sewage from portable toilets would be disposed of off-site at DEC approved locations.</li> </ul>
	If any activities are likely to cause pollution of waterways, a licence would be obtained for the works under the POEO Act.
Biodiversity	Flora
	<ul> <li>All personnel taking part in construction activities would be instructed through regular toolbox talks in the importance of the conservation value of the surrounding World Heritage area, and the need to minimise disturbance to the area.</li> </ul>
	<ul> <li>The limit of disturbance would be clearly marked, and work practices, including vehicular movements, would take care to not cause any damage to any vegetation stands or potential habitat located outside construction areas.</li> </ul>
	<ul> <li>All earthmoving plant and equipment would be thoroughly washed down prior to arrival on site to remove all soil and weed seeds. Wash down certificates would be held on project environmental files.</li> </ul>
	<ul> <li>Prevention of spreading, and reduction of the quantity and distribution of Blackberry (<i>Rubus ulmifolius</i>), a Class 3 weed, at cut slopes 4.22, 7.02, 7.58 and 8.13 would be achieved by treatment of the noxious weed. Treatment of the noxious weed would be undertaken in consultation with Upper Macquarie County Council, and the CRC Weed Management Guide for Blackberry (http://www.weeds.crc.org.au/publications/weed_man_guides.ht ml).</li> </ul>
	Topsoil potentially containing weed propagules would be removed from the Proposal site and disposed of at a licenced landfill facility. Weed infested or contaminated topsoil would not be reused for revegetation works and would not be stockpiled adjacent to any areas of native vegetation.
	<ul> <li>Weed growth present within the Proposal site (particularly at the stockpile/compound site) would be monitored weekly.</li> <li>Weed growth present would be removed/treated regularly to prevent the spread of weeds into adjacent bushland areas.</li> </ul>
	<ul> <li>If a chemical herbicide is used to suppress the growth of weed species, and/or to kill vegetation that presents a geotechnical hazard, a product would be selected that would readily break down and not impact on fauna species.</li> </ul>

#### **Impact**

# **Environmental Safeguards**

- The area of vegetation to be removed would be restricted to those areas specified in this REF. These areas would be clearly marked onsite, and on site plans prior to the commencement of works. Should additional clearing be required, the RTA's Regional Environmental Adviser, Western Region would be contacted and consulted to determine the need for further environmental impact assessment.
- All vegetation to be retained would be clearly highlighted on site and on site plans, and would be protected with fencing (or other suitable material). Protective fencing (or other suitable material) would be erected beyond the drip-line of trees and erected prior to the commencement of works. All staff would be informed and inducted of the limits of vegetation clearing and the areas of vegetation to be retained.
- Trees present within the cut slope sites would not be removed unless they present a geotechnical hazard (ie. causing root jacking of rock).
- All trimming of mature native trees would be undertaken by a qualified arborist.
- Vehicles and machinery would be parked in cleared areas and not under the drip-line of retained vegetation or trees. Retained vegetation or trees would not be smothered by stockpiles, sediment, or by the storage of materials and equipment.
- Construction stockpile/compound sites, stockpile sites and the storage of materials would be established within existing cleared areas
- Cleared native vegetation would be mulched and used in site rehabilitation works (where practical).
- Cleared and disturbed areas within stockpile/compound sites would be stabilised with suitable native grasses and ground cover plants as soon as possible to prevent soil erosion.
- Work areas would be monitored regularly for up to 3 months following completion of construction works to identify any potential loss of topsoil and/or vegetation up-hill of the works due to unforeseen wash-outs or soil slippage. The need for planting mitigation would be re-assessed.

#### Fauna

- Any fauna species found inhibiting works within Proposal site areas to be disturbed, would be removed by licenced persons under the NPW Act 1974.
- During vegetation clearing, woody debris suitable for fauna habitat would be retained and replaced on site outside of clear zones, as the removal of any dead wood, trees and logs is a Key Threatening Process under the TSC Act.

#### Aquatic

 The Proposal would not cause degradation of native riparian vegetation present along the Jenolan River.

Impact	Environmental Safaguards
Impact	<ul> <li>Environmental Safeguards</li> <li>The Proposal would be undertaken in accordance with the Habitat Protection Plan No. 3: Hawkesbury-Nepean River System.</li> </ul>
Non-Indigenous Heritage	<ul> <li>Should archaeological remains be uncovered during construction, all works would cease within the vicinity of the material/find and the RTA's Regional Environmental Adviser Western Region contacted.</li> </ul>
	<ul> <li>Machinery and trucks would be parked away from the downslope side of the road to avoid heavy loads being placed on the dry stone walls.</li> </ul>
	<ul> <li>Adverse affect on the heritage significance of the Six Foot Track would be avoided by maintaining foot access along the Six Foot Track (including installation of track markers) in the vicinity of the stockpile/compound site.</li> </ul>
Indigenous Heritage	<ul> <li>All personnel working on site would receive training in their responsibilities under the National Parks and Wildlife Act 1974.</li> </ul>
	<ul> <li>Should Indigenous heritage items be uncovered during works, all works in the vicinity of the find would cease and the RTA's Aboriginal Programs Consultant, Regional Environmental Adviser Western Region, DEC representative and relevant LALC representatives would be contacted. Works would not re- commence until appropriate clearance has been received.</li> </ul>
	<ul> <li>The RTA's Property section would deal with the matter relating to the Gundungurra Tribal Council Aboriginal Corporation #6 Native Title application (NC97/7).</li> </ul>
Noise and Vibration	• The procedures contained in the RTA's Environmental Noise Management Manual, 2001 "Practice Notes vii – Roadworks Outside of Normal Working Hours" would be followed for works undertaken outside standard hours.
	<ul> <li>Prior to the commencement of works, the Jenolan Caves Reserve Trust would be notified of the Proposal details, including the potential for noise impacts to occur.</li> </ul>
	<ul> <li>Background noise levels at the Proposal site would be recorded prior to the commencement of works. Construction noise monitoring would be undertaken during the works, if it is deemed necessary by the RTA Project Manager and/or RTA Regional Environmental Advisor, Western Region.</li> </ul>
	• If accommodation cabins are occupied by Trust guests during the works, it may be necessary to vacate them (particularly Bellbird cottage) if unacceptable noise levels occur during the Proposal. The RTA Project Manager would maintain close liaison with the Jenolan Caves Reserve Trust during the works.
	<ul> <li>The idling of machinery and equipment when not in use, and for prolonged periods of time would be prohibited.</li> </ul>
	<ul> <li>Best management practices would be adopted that are consistent with the RTA's Environmental Noise Management Manual, 2001.</li> </ul>
	<ul> <li>Noise from reverse alarms would be limited to the lowest possible levels consistent with safety or, during the night,</li> </ul>

Impact	Environmental Safeguards
	replaced with flashing lights, or other warning devices. Machines with excessively noisy alarms would be modified or removed from the site.
	<ul> <li>All machines would be in good working condition, with particular attention to exhaust silencers, engine covers and other noise reduction devices.</li> </ul>
	<ul> <li>Short, sharp sounds primarily caused by physical impacts, would be avoided where possible to minimise sleep disturbance to Trust guests.</li> </ul>
Air Quality	<ul> <li>Construction activities that generate high dust levels would be avoided during high wind periods.</li> </ul>
	<ul> <li>Where dust generated by the proposed works is visible, dust suppression measures would be implemented.</li> </ul>
	<ul> <li>If winds are high and works are creating high levels of dust that are likely to cause discomfort to local residents or a safety hazard to traffic or work personnel, the works would be modified or stopped until the dust hazard is eliminated or has been reduced to an acceptable level.</li> </ul>
	• Any stockpiles and general works areas with the capacity to cause dust would be dampened or covered to suppress dust emissions.
	<ul> <li>Long term stockpiles would be sprayed with a sterile grass mix to suppress dust generation.</li> </ul>
	<ul> <li>All stockpiles would be fenced with sediment control fencing.</li> </ul>
	<ul> <li>Truck movements would be controlled on site and restricted to designated roadways.</li> </ul>
	<ul> <li>To minimise exhaust emissions, vehicles and operating equipment used on-site would be switched off when not operating.</li> </ul>
	<ul> <li>Any materials transported in trucks would be appropriately covered to reduce dust generation.</li> </ul>
	<ul> <li>Tailgates would be secured during operation of trucks.</li> </ul>
	<ul> <li>Rehabilitation of disturbed surfaces would be undertaken as soon as practicable.</li> </ul>
Visual Amenity / Landscape	<ul> <li>The Proposal would be undertaken with the intent to only remove amounts of soil, rock and vegetation necessary to achieve the project objectives.</li> </ul>
	• The colour of the metal rock catch fencing would be chosen to blend in with the cut slope faces.
	<ul> <li>Application of shotcrete and/or mortar would be undertaken in accordance with RTA's QA Specification B82 Shotcrete Work.</li> </ul>
	<ul> <li>The colour of the shotcrete and/or mortar would be chosen to match (as close as possible) the colour of the surrounding weathered rock at each cut slope site.</li> </ul>
	<ul> <li>The application of shotcrete and/or mortar would be minimised to that necessary to achieve stabilisation of the cut slope sites.</li> </ul>
	<ul> <li>Lights would be positioned to avoid light impacting on areas located beyond the Proposal site.</li> </ul>

# **Impact**

# **Environmental Safeguards**

# Socio-Economic Considerations

- The construction site would be kept tidy and rubbish free.
- A pre-construction audit of the local network condition, with particular focus on Jenolan Caves Road would be conducted to monitor whether additional truck movements result in the deterioration of the road surface.
- A Traffic Control Plan would be prepared in accordance with the RTA's Traffic Control at Work Sites Manual 2003, and approved by the RTA prior to implementation. The Traffic Control Plan would include the notification of any traffic alterations or closures.
- Telstra mobile network coverage would be available at Jenolan Caves for visitors to the Jenolan Caves area.
- Access along Jenolan Caves Road would be available during the winter school holiday period from 2-17 July 2005.
- Alternate access to Kanangra Walls, Jenolan Caves and accommodation (Jenolan Caves House, Bellbird cottage, Jenolan Caves Camping ground) would be available via Oberon or Two-Mile Hill Road.
- A mini-bus shuttle service between Two-Mile Hill and the Jenolan Caves would be provided as needed.
- All construction work areas on Jenolan Caves Road would be made trafficable at the end of each working day.
- Jenolan Caves Road would be accessible between 10am and 4pm Monday to Thursday, and all day Friday and Saturday.
- Signs would be used to advise drivers to use alternate access routes into Jenolan Caves via Oberon Road and Two-Mile Hill Road. The signs would be located at Hartley, Hampton, Top of Five Mile Hill, Top of Two Mile Hill, Lithgow and Bathurst, and traffic access advice would be provided through the media.
- A Community Liaison Group would be established to advise stakeholders and local road users of the progress of the works, and to seek input and feedback regarding the works. The Community Liaison Group would consist of Jenolan Caves Trust and staff, Caves House and staff, and local business owners.
- If accommodation cabins are occupied during the works, it may
  be necessary to vacate them (particularly Bellbird cottage) if
  unacceptable noise levels occur during the Proposal. The RTA
  Project Manager would maintain close liaison with the Jenolan
  Caves Reserve Trust during the works.
- In accordance with the RTA's Community Involvement Practice Notes and Resource Manual (1988), members of the affected community (including local residents, bus companies and emergency services) would be notified of the proposed works at least two (2) weeks prior to their commencement. The notification would identify the nature of the works, give an estimated duration, advise of anticipated delays and identify any changes to traffic, wide load restrictions, or access during the works.

Impact	Environmental Safeguards
	<ul> <li>All booked visitors to Jenolan Caves would be advised of traffic management arrangements prior to their visit.</li> </ul>
	<ul> <li>All tourist bus and coach operators travelling to Jenolan Caves would be advised of traffic management arrangements prior to travelling to Jenolan Caves.</li> </ul>
Waste Minimisation & Management	<ul> <li>A Waste Management Plan would be prepared in accordance with RTA's QA Specifications and in accordance with RTA's Waste Minimisation &amp; Management Guidelines, 1998 and the principles of the WARR Act.</li> </ul>
	<ul> <li>Trees to be removed would be assessed for their value as millable timber.</li> </ul>
	<ul> <li>Leaf material and small branches of native vegetation would be chipped and used as mulch in revegetation works.</li> </ul>
XIII AND AND A SECOND	There would be no burning of waste.
	<ul> <li>All exotic plant species removed would be bagged and disposed of at a licenced landfill facility.</li> </ul>
	<ul> <li>All construction materials, surplus soils and wastes generated from the Proposal would be stockpiled and stored at the stockpile/compound site prior to reuse, recycling or disposal.</li> </ul>
	All working areas would be maintained, kept free of rubbish and cleaned up at the end of each working day.
	<ul> <li>Wastes would not be stored for long periods during construction of the Proposal. Empty drums of fuels, oils or chemicals and fluids would not be stored on site during construction.</li> </ul>
	<ul> <li>Any contaminated waste found would be identified and classified by a suitably qualified consultant.</li> <li>Any contaminated waste identified or generated during the Proposal would be disposed in accordance with DEC guidelines.</li> </ul>
	In addition, the Resource Management Hierarchy principles of the WARR Act would be adopted as follows:
	I. Avoid unnecessary resource consumption as a priority;
	2. Avoidance is followed by resource recovery (including reuse of materials, reprocessing recycling, and energy recovery; and
	3. Disposal is undertaken as a last resort.

# 9.2 Licences and Approvals

# Protection of the Environment Operations Act, 1997

The Proposal is not expected to cause pollution of water (ie. any chemical, biological, physical change to existing water quality). An Environment Protection Licence (EPL) would therefore not be expected to be required under the POEO Act, 1997.

The Contractor and the RTA would notify the DEC if a "pollution incident" occurs that causes or threatens "material harm" to the environment.

# 10 Consideration of State and Commonwealth Environmental Factors

# 10.1 Clause 228(2) Factors (NSW Legislation)

The factors which need to be taken into account when considering the environmental impact of an activity are listed in Clause 228(2) of the *Environmental Planning and Assessment Regulation, 2000.* Those factors have been addressed in Table 10.1 below to ensure that the likely impacts of the proposed activities on the natural and built environment are fully considered.

Table 10.1: Compliance with Clause 228(2) of the EP&A Regulation 2000.

	Clause 228(2) Factors	Impact
a)	Any environmental impact on a community?	
	Short term negative impacts include night closures of Jenolan Caves Road, and could potentially include noise impacts (particularly at Bellbird cottage), adverse light impacts and temporary minor reduction in tourism income. These impacts would be limited to the construction period, and would be eliminated or minimised through the implementation of safeguards described in Section 9 of this report. In the long term, the community would be provided with a safer roadway. Refer to Section 8.10.	Short term - ve  Long term + ve
b)	Any transformation of a locality?	
	In the short term, the freshly cut rock/soil surface, and possibly the absence of vegetation, would be visible along Jenolan Caves Road during daylight hours. In the long term, the locality is not expected to be transformed. The introduction of rock bolts/face plates, shotcrete and/or mortar, and rock catch fencing can be expected to be noticeable to road users, but would not be noticeable to surrounding land users. Vegetation growth adjacent to the roadway would assist to screen the rock bolts/face plates, shotcrete and/or mortar, and rock catch fencing from the view of surrounding land users. Refer to Section 8.10.	Short term - ve  Long term Minor -ve
c)	Any environmental impact on the ecosystem of the locality?	
	The areas likely to be directly and indirectly impacted by the Proposal are not considered to be important for either the integrity or life cycle requirements of endangered ecological communities and/or threatened species. The Proposal would not disturb, remove, modify or fragment any habitats critical to the life cycle requirements of the Powerful Owl, Sooty Owl, Yellow-bellied Glider, Large-eared Pied Bat, Large-footed Myotis, Eastern Bentwing Bat, and Eastern False Falsistrelle, Gang-gang Cockatoo or Satin Flycatcher. Refer to Section 8.4.	Nil
d)	Any reduction of the aesthetics, recreational, scientific or other environmental quality or value of a locality?	
	The Proposal is not expected to reduce the aesthetic, recreational, scientific or other environmental quality or value of the locality. In the medium to long-term, the cut slope sites can be expected to regenerate	Short term ve
	with vegetation growth. The rock bolts/face plates would weather in the medium to long-term, and the colour of the shotcrete and/or mortar, and rock catch fencing would be a chosen to blend in with the cut slope faces.	Long term Nil

	Clause 228(2) Factors	Impact
	The aesthetically attractive travel route would be maintained in the medium to long-term. Refer to Section 8.10.	
e)	Any effect on a locality, place or building having aesthetic, anthropological, archaeological, architectural, cultural, historical, scientific or social significance or other special value for present generations?  The Proposal would not remove any locality, place or building having aesthetic, anthropological, archaeological, architectural, cultural, historical, scientific or social significance or other special value for present generations. Refer to Sections 8.5, 8.6, 8.10.	Nil
f)	Any impact on habitat of any protected fauna (within the meaning of the <i>National Parks and Wildlife Act 1974</i> )?  The Proposal would not disturb, remove, modify or fragment any habitats critical to the life cycle requirements of any protected fauna. Refer to Section 8.4.	Nil
g)	Any endangering of any species of animal, plant or other form of life, whether living on land, in water or in the air?	1
	It is not anticipated that the Proposal would result in the endangering of any species of animal, plant or other form of life, whether living on land, in water or in the air. Refer to Section 8.4.	Nil
h)	Any long-term effects on the environment?	9
	The Proposal is not expected to cause long term negative impacts on the environment. Refer to Section 8.	Nil
i)	Any degradation of the quality of the environment?	
	In the medium to long-term, the Proposal is not expected to degrade the quality of the environment. The cut slope sites can be expected to regenerate with vegetation growth. Introduction of rock bolts/face plates, shotcrete and/or mortar, and rock catch fencing is not expected to degrade the quality of the environment. The appearance of the cut slope sites would only appear slightly different to their existing appearance following completion of the works. There may be some minor short term impacts during construction, however these would be managed via the safeguards listed in Section 9. Refer to Section 8.4, 8.9.	Short term- ve Long term Nil
j)	Any risk to the safety of the environment?	
	In the long term there would be positive impacts as the Proposal would improve the level of safety for road users. Refer to Sections 8.3 and 8.12.	Long term + ve
k)	Any reduction in the range of beneficial uses of the environment?	
	Jenolan Caves Road would be closed during work periods from Sunday nights to Thursday nights (4pm to 10am) from 26 April 2005 to 23 September 2005. Access to Kanangra Walls and/or Jenolan Caves, including accommodation during the proposed work periods would be possible via Oberon Road or Two-Mile Hill Road. The alternative routes are longer than the Jenolan Caves Road route, and are not suitable for tourist buses and/or coaches. Impacts on visitor numbers to Kanangra Walls and/or Jenolan Caves, and a subsequent reduction in tourism income is expected to be minor taking into account the Proposal would be undertaken during an off-peak period. No post-construction community impacts are expected as a result of the Proposal. Refer to Section 8.3.	Short term- ve Long term Nil

I)	Any pollution of the environment?	
	It is expected that the Proposal would not pollute the environment, providing that the safeguards in Section 9 are implemented. Refer to Section 8.3.	Long term Nil
m)	Any environmental problems associated with the disposal of waste?	
	Minimal waste would be generated as a result of the Proposal. Waste material would be disposed of at approved waste disposal sites and managed in accordance with the Resource Management Hierarchy of the WARR Act. Refer to Section 8.11.	Nil
n)	Any increased demands on resources, natural or otherwise which are, or are likely to become, in short supply?	
	There would not be any increased demand on resources, natural or otherwise which are, or are likely to become in short supply. Refer to Sections 3.1 and 8.11.	Nil
o)	Any cumulative environmental effect with other existing or likely future activities?	
	The proposed works would have a positive cumulative effect on the safety of the current use of Jenolan Caves Road in conjunction with other proposed works on this road (ie. installation of cantilever structures and	Short term -ve
	Thriebeam guardrail at three sites). During construction, installation of cantilever structures and Thriebeam guardrail on Jenolan Caves Road have a potential to cause negative cumulative impacts during construction (ie. water quality, noise, visual) in association with the proposed cut slopes remediation. During operation, the cantilevers/Thriebeam guardrail on	Long term +ve and - ve
	Jenolan Caves also have a minor potential to cause negative visual cumulative impacts in association with the proposed cut slopes remediation. Refer to Section 1.5.	

# 10.2 EPBC Act 1999 Factors (Commonwealth Legislation)

The EPBC Act requires that the following matters of National Environmental Significance (NES) be considered.

Table 10.2: Compliance with Commonwealth EPBC Act requirements.

	EPBC Act Factors	Impact
a)	Any environmental impact on World Heritage property?  The Proposal is not expected to impact on the Greater Blue Mountains World Heritage Area.	Nil
b)	Any environmental impact on National Heritage places?  The Proposal would not impact any National Heritage places, as there are no National Heritage places present within 10km of the Proposal site.	Nil
c)	Any environmental impact on wetlands of international importance?  The Proposal is not located within the catchment of the Macquarie Marshes, which is located 340km north west of the Proposal site. The Proposal would not impact on any wetland of international importance.	Nil
d)	Any environmental impact on Commonwealth listed threatened species or ecological communities?  There are 18 threatened species and no ecological communities recorded as potentially occurring within a 10km search area around the locality. The Proposal would not have a significant impact on any of these species.	Nil
e)	Any environmental impact on Commonwealth listed migratory species?  There have been 8 migratory species recorded within a 10km search area around the locality. The Satin Flycatcher was observed within the Proposal site. No habitat for any of these species would be affected by the Proposal, and a significant impact on the Satin Flycatcher is not expected. The Proposal would therefore not have any impact on Commonwealth listed migratory species.	Nil
f)	Does any part of the Proposal involve nuclear action?  The Proposal would not involve a nuclear action.	Nil
g)	Any environmental impact on a Commonwealth Marine area? The Proposal would not impact on a Commonwealth marine area.	Nil
In	addition: Any impact on Commonwealth Land?  Commonwealth land would not be affected, directly or indirectly, as part of this Proposal.	Nil

# **II** Certification

This Review of Environmental Factors provides a true and fair review of the Proposal in relation to its potential effects on the environment. It addresses to the fullest extent possible all matters affecting or likely to affect the environment as a result of the Proposal.

P. Rya

Peter Ryan

Environmental Officer Date: 11-3-2004

I have examined this Review of Environmental Factors and the certification by Peter Ryan and accept the Review of Environmental Factors on behalf of the RTA.

Chris Barnett Project Manager Date:

# 12 References

Australian Heritage Database, 2005, (http://www.ahc.gov.au/register/easydatabase/database.html).

Bureau of Meteorology 2004. Climate data obtained from www.bom.gov.au. May 2004

CALM 1994. Soil Landscapes of the Katoomba 1:100,000 Sheet (Mount Tomah, Woodford, Jenolan Caves, Hampton). D.P King.

DEC website (http://www.dec.nsw.gov.au)

DEC Contaminated Land Register, 2005, (http://www2.epa.nsw.gov.au/prpoeo/LicenceN.asp)

Department of Environment and Heritage, Protected Matters Search Tool, 2005 (http://www.deh.gov.au/erin/ert/epbc/index.html)

Department of Environment and Heritage 2005. *National Pollutant Inventory* (http://www.npi.gov.au/index.html)

EPA 1999. Environmental Noise Control Manual.

EPA 2002. Environmental Best Management Practice Guideline for Concreting Contractors.

JCRT 2004. The Jenolan Karst Conservation Reserve Draft Plan of Management. Manides Roberts.

|CRT 2005. Jenolan Caves Reserve Trust web site. 2005

NSW Heritage Office State Heritage Inventory 2005, (http://www.heritage.nsw.gov.au/07\_subnav\_01.cfm)

Oberon Council 2003. State of the Environment Report (1/7/02 to 30/6/03).

RTA 1998. Waste Minimisation & Management Guidelines. RTA, NSW.

RTA 1999. RTA Statutory Planning Guidelines. RTA, NSW.

RTA 2001a. Environmental Impact Assessment Policy, Guidelines and Procedures, Version 4.

RTA 2001b. Stockpile Management Procedures. RTA, NSW.

RTA 2002. Aboriginal Heritage Guidelines. RTA, NSW.

RTA 2003a. Preliminary Draft Report on Concept Design Remediation Work for Rock Cuts MR 253 Jenolan Caves Road. Golder Associates, December 2003.

RTA 2003b. Traffic Control at Work Sites Manual. RTA, NSW.

RTA 2005. Ecological Assessment of Proposed Cut Slopes Remediation on Jenolan Caves Road, Jenolan Caves. Lesryk Environmental Consultants.

RTA Heritage and Conservation Register 2005, (http://www.rta.nsw.gov.au/environment/heritage/heritageconservreg/hunter/index.html)

# Appendix A Ecology Study

# Ecological assessment of proposed cutslope remediation works.



Jenolan Caves Road, Jenolan Caves

February 2005





Report prepared on behalf of:

The NSW Roads and Traffic Authority by

LesryK Environmental Consultants PO BOX 3001 BUNDEENA NSW 2230

> Telephone: (02) 9523 2016 Mobile: 0408 25 8129 Facsimile: (02) 9544 1835

Email: admin@lesryk.com.au www.lesryk.com.au

Please note that, given the dynamic nature of the relevant pieces of environmental legislation considered in this report, the authors consider that this report only has a 'shelf life' of six months. If a development application, review of environmental factors or statement of environmental effect is not submitted to a determining authority for consideration within this time frame, it is recommended that this report be reviewed and revised where required in light of any relevant legislative listings or changes.

## **EXECUTIVE SUMMARY**

At the request of the New South Wales Roads and Traffic Authority (RTA), a flora and fauna assessment was undertaken of the lands that occur within, and adjacent to, Jenolan Caves Road, Jenolan Caves, New South Wales. The survey has been carried out as the RTA is proposing to conduct remedial works at several sites, thereby improving the safety of Jenolan Caves Road to road users. The survey was conducted to identify the presence of any species, populations or communities listed under the Commonwealth Environment Protection and Biodiversity Conservation Act 1999 and/or NSW Threatened Species Conservation Act 1995, thereby assessing their reliance on the proposed works sites and determining the extent of any likely impacts on the viability of these as a result of the undertaking of the Proposal.

By the completion of the field surveys, no state or nationally listed threatened plants or Endangered Ecological Communities had been recorded within the study area. Similarly no plants or vegetation communities of regional conservation concern had been detected. As such, no locally or regionally significant populations of any plants or vegetation communities of conservation significance would be adversely affected as a result of the undertaking of the Proposal.

Seven state listed threatened animals were recorded during the fauna surveys undertaken as part of the investigation, these being the Powerful Owl Ninox strenua, Sooty Owl Tyto tenebricosa, Yellowbellied Glider Petaurus australis, Large-eared Pied Bat Chalinolobus dwyeri, Eastern False Pipistrelle Falsistrellus tasmaniensis, Large-footed Myotis Myotis adversus and Eastern Bentwing Bat Miniopterus schreibersii. In addition to these, the Gang-gang Cockatoo Callocephalon fimbriatum was detected, this bird being preliminary listed for inclusion under Schedule 2 of the Threatened Species Conservation Act 1995. Two nationally listed animals were also recorded, these being the Satin Flycatcher Myiagra cyanoleuca (a migratory bird) and Large-eared Pied Bat Chalinolobus dwyeri (a vulnerable species). Giving consideration to the scale of works proposed, the structure and quality of the habitats present at each site, and the presence of large conservation reserves adjacent to the study area, it was not considered that any individuals or populations of any of these fauna species of state and/or national conservation concern would be significantly impacted upon, such that the extinction or displacement of these animals would arise. Giving consideration to the assessment criteria provided in association with the Commonwealth Environment Protection and Biodiversity Conservation Act's Administrative Guidelines on Significance and Section 5A of the NSW Environmental Planning and Assessment Act 1979 it is not considered that the Proposal would have an adverse impact on any state or nationally listed threatened species, their populations, ecological communities or habitats. As such, it is not considered necessary that a referral to Environment Australia be made, or a Species Impact Statement prepared, as part of the Proposal.

By the completion of the field surveys, no ecological constraints were identified that would impede the Proposal proceeding as planned. The Proposal could be undertaken without requiring the preparation of any further terrestrial ecological studies.

Recommendations are presented to ensure that the activities associated with the Proposal are undertaken in an ecologically sustainable manner, thereby minimising the indirect impact of the works on adjacent features of state and/or national conservation value.

# TABLE OF CONTENTS

1.	Introd	uction	4
2.	Enviro	nmental setting.	6
3.	Field s	urvey methods	10
	2   Flora o	ırvey	10
		survey	
	3.2 rauna :	sur yey	10
4.	Literat	ure review and field guides.	13
5.	Flora r	esults	14
	5.1.Plant st	pecies	14
		tion communities	
		scussion.	
6.	Fauna	results.	22
			22
		types	
		species recorded	
	6.2.1.	Powerful Owl (Ninox strenua)	
	6.2.2.	Sooty Owl (Tyto tenebricosa).	
	6.2.3.	Satin Flycatcher (Myiagra cyanoleuca)	
	6.2.4.	Yellow-bellied Glider (Petaurus australis)	
	6.2.5.	Large-eared Pied Bat (Chalinolobus dwyeri)	
	6.2.6.	Eastern False Pipistrelle (Falsistrellus tasmaniensis)	
	6.2.7.	Large-footed Myotis (Myotis adversus)	
	6.2.8.	Eastern Bentwing Bat (Miniopterus schreibersii)	
	6.2.9.	Gang-gang Cockatoo (Callocephalon fimbriatum)	
	6.3. Fauna s	species of conservation significance previously recorded in the study region	29
7.	Ecolog	ical assessments	29
	7.1 Commo	nwealth Environment Protection and Biodiversity Conservation Act 1999	29
	7.1.1	Flora considerations	
	7.1.2	Fauna considerations.	
	7.7 State F	nvironmental Planning and Assessment Act 1979	
	7.2.1	Flora assessment	
	7.2.2	Eight part test – Flora	
	7.2.3.	Flora conclusion.	
	7.2.4.	Fauna assessment	
	7.2.5. (a)	Eight part test – Powerful Owl.	
	7.2.5. (b)	Expected impact on the Powerful Owl	
	7.2.6. (a)	Eight part test — Sooty Owl	
	7.2.6. (b)	Expected impact on the Sooty Owl	
	7.2.7. (a)	Eight part test — Yellow-bellied Glider	
	7.2.7. (b)	Expected impact on the Yellow-bellied Glider	
	7.2.8. (a)	Eight-part test — Cave dependant microchiropterans (Large-eared Pied Bat and	
	7.2.0. (d)	Eastern Bentwing Bat)	37
	7.2.8. (b)	Expected impact on cave dependant microchiropterans	
	7.2.9. (a)	Eight-part test – Eastern False Pipistrelle	
	7.2.9. (a) 7.2.9. (b)	Expected impact on the Eastern False Pipistrelle	
		Eight part test – Large-footed Myotis.	
	7.2.10. (a)		
	7.2.10. (b)	Expected impact on the Large-footed Myotis	
	7.2.11. (a)	Eight part test – Gang-gang Cockatoo.	42

7.	2.11. (b) Expected impact on the Gang-gang Cockatoo	43
/.	.3 State - State Environmental Flatining Folicy No. 44 (SEFF 44) - Rodia Habitat Protection	43
8.	Conclusions.	43
9.	Recommendations.	44
10.	Bibliography	46

#### List of Figures.

Figure 1: Study location and area. Figure 2: Location of fauna survey sites.

# Photographic record of study area.

#### List of Tables.

Table I: Fauna survey locations.

Table 2: Plant species of conservation significance previously recorded in the Oberon Local

Government Area.

Table 3: Results of bat call analysis.

## List of Appendices.

Appendix 1: Plant species list.

Appendix 2: Fauna species recorded or previously detected within the study region.

Appendix 3: Fauna species of conservation significance previously recorded in the study region.

Appendix 4: Results of targeted survey undertaken to determine the presence of the Purple Copper Butterfly (*Paralucia spinifera*).

#### I. Introduction.

This report presents the findings of a flora and fauna survey of the lands that occur within, and inclose proximity to, ten sites that occur adjacent to Jenolan Caves Road, Jenolan Caves, New South Wales (NSW). The survey has been carried out as the NSW Roads and Traffic Authority (RTA) is proposing to conduct remedial work at each of the ten sites.

The ten sites being investigated are:

- Cut slope C1.74 (approximate length 150 metres [m]);
- Cut slope 2.63 (100m);
- Cut slope 3.64 (200m);
- Cut slope 4.22 (150m);
- Cut slopes 5.08 and 5.29 (300m);
- Cut slope 7.02 (75m);
- Cut slope 7.58 (150m);
- Cut slope 8.13 (100m); and
- Walls 40 and 41 (115m).

In addition to these, the existing compound site was also investigated, as was an access track and proposed works area that would be established above cut slope 3.64.

For reference, each of the sites surveyed are highlighted on Figure 1.

The remediation works proposed to be undertaken at each of the cut slopes would include the scaling of loose rock, the installation of rock bolts, steel meshing and barrier fencing and the repair / replacement of drainage structures. The proposed works would be undertaken at night, generally between the hours of 4pm and 10am, from the 26<sup>th</sup> of April to the 23<sup>rd</sup> of September 2005.


At cut slope 3.64, an access track and works compound may be required. The access track and works compound would be established above the cut slope, the track being approximately 500m long and 5m wide. To establish both the access track and works compound, some native vegetation would require removal.

Based on a worst case scenario (this assuming a clearing width of 10m for the cut slopes), it is assumed that a total of 6.15 hectares (ha) of native vegetation would be cleared to permit the undertaking of the proposed works, this including the remediation of the cut slopes, and the establishment of both the access track ( $50 \times 500m$  in size) and works site ( $80 \times 300m$  in size). Whilst this is the case, it is noted that several of the cut slopes are currently cleared or sparsely vegetated, these being slopes composed mainly of exposed rock (e.g. refer to photographs 4 and 6). These cleared slopes were included in the estimates made for total vegetation removal.

It is noted that some works have already been completed at Walls 40 and 41, the cut slopes at these locations having been cleared and scaled of loose rock (refer to photograph 1). The works compound is also an existing facility, this area supporting a series of demountables, stockpiles and fenced enclosures (refer to photograph 2).

Where required, more detailed information on the scope of the project is provided in the project's Review of Environmental Factors (REF).

For ease of reference, unless a specific site or component of the investigation area is referred to, the entire area surveyed (that being the nine cut slopes, Walls 40/41, the existing compound site, the proposed access track, works site and their adjacent habitats) will hereafter be referred to as the 'study area', whilst the surrounding lands will be referred to as the 'study region'.



For the purpose of the current investigation, where access was physically possible and safe, the area surveyed encompassed all the lands that occur within the study area and for a distance of 30 metres (m) either side of Jenolan Caves Road.

The assessment of possible impacts associated with the Proposal is based on a field survey of the study area, a literature review of previous studies undertaken in both the region and the Oberon Local Government Area, the consultation of standard databases and the consideration of the objectives of the Commonwealth Environment Protection and Biodiversity Conservation (EPBC) Act 1999, the NSW Environmental Planning and Assessment Act (EPA) 1979, NSW National Parks and Wildlife (NPW) Act 1974, NSW Threatened Species Conservation (TSC) Act 1995, and any relevant State Environmental Planning Policies (SEPP) (e.g. SEPP 44 – Koala habitat protection).

#### 2. Environmental setting.

The study area is located within the Oberon Local Government Area. The ten survey sites all occur adjacent to Jenolan Caves Road, northeast of Jenolan Caves. Jenolan Caves Road is situated within Kanangra Gorge, on the eastern slopes of Binoomea Ridge. The proposed works are located within an 8km section of Jenolan Caves Road, commencing near the Grand Arch and finishing near Kiaora Hill (Figure 1).

For reference, a photographic record of several portions of the study area has been provided.

It is noted that cut slopes C1.74, 2.62, 3.64, 4.22. 5.08 7.02 and Walls 40/41 all have an easterly aspect, whilst cut slopes 5.29, 7.58 and 8.13 are all generally south to south west facing. All cut slopes and walls have a slope of between 60 and 80 degrees.

Jenolan Caves Road is located within a landscape that is characterised by steep to very steep valleys. The dominant soils of the study area are derived from Devonian and Silurian metasediments and volcanics (King 1994). These consist generally of structured Loams / Lithosoils (on rocky steep slopes and crests), Brown, Red and Yellow Podzolic Soils (on the lower slopes) and alluvial soils along drainage lines (King 1994). These soils have low fertility, and are susceptible to severe water erosion, mass movement, localised rock falls and foundation hazards (King 1994).

Natural elevations within the study area are between 750 and 1000m above sea level. The annual average rainfall in the region is 966.2 millimetres with the greatest falls being experienced during the summer months (Bureau of Meteorology Jenolan Caves 2005). Average temperatures range between a winter low of  $0.2^{\circ}$ C to a summer high of  $25.6^{\circ}$ C (Bureau of Meteorology Jenolan Caves 2005). Frosts are also common during the winter months (Oberon Council 2004).

Drainage lines that occur down slope of the study area include Jenolan River, Pheasants Nest and Bulls Creeks, Cookes Gully and several unnamed drainage channels (Figure 1). The smaller drainage lines feed into the Jenolan River, this river eventually flowing into the Coxs River 13km east of the study area. The unnamed drainage channels are all considered to be ephemeral, whilst the major rivers and creeks are permanent water bodies. Each of the drainage lines occurs within a catchment that is dominated by relatively pristine natural bushland.

Whilst drainage lines traverse under, and occur adjacent to Jenolan Caves Road, it is noted that none are located within any of the proposed remediation sites.

Jenolan Caves Road is surrounded by a network of large conservation reserves. These reserves, or other protected lands, include the Jenolan Caves Reserve Conservation Area, Blue Mountains and Kanangra-Boyd National Parks and both Jenolan and Hampton State Forests. These reserves cover areas of 2260, 264848, 68661, 9607 and 4771ha respectively (National Parks and Wildlife Service [NPWS] 1998, Oberon Council 2004). In relation to the Jenolan Caves Reserve Conservation Area, Blue Mountains and Kanangra-Boyd National Parks, these are part of a group of reserves that contribute to the largest conservation area in NSW (this being the Greater Blue Mountains Area which was inscribed on the World Heritage List during the 24th Session of the World Heritage Committee) (Oberon Council 2004, Department of Environment and Heritage [DEH] 2005a).

# PHOTOGRAPHIC RECORD OF STUDY AREA




Photo I: Extent of completed works at Walls 40/41.




Photo 2: Existing character of the works compound. Photograph taken looking west through site.

# PHOTOGRAPHIC RECORD OF STUDY AREA




Photo 3: Structure of woodland on top of cut slope 3.64, within the alignment of the proposed access track.




Photo 4: Cut slope 3.64.

# PHOTOGRAPHIC RECORD OF STUDY AREA



Photo 5: Cut slope 2.63.




Photo 6: Cut slope 5.08/5.29.

The Greater Blue Mountains World Heritage Area is approximately 1.03 million hectares in size (DEH 2005a).

Jenolan Caves Road traverses through an area that is dominated by eucalypt woodlands. As such, the majority of the proposed cut slopes support a suite of native plants, though the species diversity of these is dependant upon the impacts associated with the previous road works activities, and any ongoing vegetation maintenance / hazard reduction schemes. In relation to this it is noted that on going maintenance has resulted in a number of trees and shrubs being prunes and/or removed from the cut slopes themselves.

Through consultation of the Australian Heritage Council and Australian Heritage Database, it was identified that the following "ecological features" were listed as state heritage items:

- Jenolan Caves (Type of Item: Archaeological Terrestrial; Category: Cave);
- Jenolan Caves Reserve Conservation Area (Type of Item: Archaeological Terrestrial; Category: Cave);
- Kanangra-Boyd National Park (Type of Item: Archaeological Terrestrial; Category: Reserve);
   and
- The Oberon Area (Type of Item: Area/Complex/Group; Category: Geological site or area) (NSW Heritage Office 2005).

Given the scale of the works associated with the Proposal, none of these state listed heritage items would be significantly affected.

# 3. Field survey methods.

# 3.1 Flora survey.

A botanical investigation of the study area was undertaken by John Speight (B.Sc.) on the 11th and 12th of January 2005. The methods employed during this investigation were:

- The identification of all plants within the areas of likely disturbance, including both direct and indirect impacts; and
- The identification of the structure of those vegetation communities and fauna habitats present.

The botanical survey identified the diversity of plants present within, and adjacent to each of the Proposal areas, as well as the structure and nature of the vegetation communities. To survey each of the likely disturbance sites, foot traverses were undertaken where possible. During the field surveys the area down slope of the existing road was surveyed where appropriate but the steep to very steep slopes and loose rubble was considered to be generally unsafe to access most of these down slope sites.

The investigation considered each of the likely works sites, and a distance of up to 30m either side of the existing road.

# 3.2 Fauna survey.

A survey of the study area was undertaken by Deryk Engel (B.Env.Sc.HONS) between the 6<sup>th</sup> and 8<sup>th</sup> of January 2005. To survey each of the cut slopes, the proposed access track and works site, foot traverses were undertaken within and adjacent to the likely disturbance areas. During the field investigations, the diversity of animals present within, and adjacent to, the nine cut slopes, Walls 40/41, the access track, works site and existing compound, were recorded. For the purposes of the field investigations, to consider the likely direct and indirect impacts of the works, where possible and safe, the survey of each of the study areas incorporated the proposed remediation sites themselves, and a distance of up to 30m either side of the existing road.

The fauna survey methods employed during the field investigations were:

- The direct observation of any species within, or adjacent to, the study area;
- The identification of any indirect evidence that would suggest the presence of any fauna species;
- Litter and ground debris searches for reptiles and frogs;
- Diurnal and nocturnal call identifications with all calls being identified in the field;
- Call determinations undertaken on dusk;
- Spotlighting;
- Echolocation targeting microchiropterans (insectivorous bats);
- · Call playbacks targeting threatened owls and mammals; and
- Targeted searches for those species of state and national conservation concern, or their likely habitat areas, that were identified during the literature review stage of the project.

Where required, greater detail on several of the fauna survey methods employed are provided below.

The nocturnal surveys were undertaken on the 6<sup>th</sup> and 7<sup>th</sup> of January 2005 these lasting for around 3 hours per night. The weather conditions experienced during the nocturnal surveys were clear skies, warm temperatures (19.7°C) and slight breezes and, partial cloud cover [3/8], slight breezes and cool temperatures (14.3°C) respectively. During these surveys, a variety of fauna identification techniques were employed.

During each of the nocturnal sessions, call identifications were undertaken on dusk. The call identifications involved a researcher being located within a portion of study area, the researcher listening for any territorial calls that were broadcast by native species as they left, or entered, their roosting sites. The dusk call identifications were undertaken on top of cut slope 3.64 (6/01/05) (Easting 225761, Northing 6255358 – in the vicinity of Bat 2 [Figure 2]) and at the base of cut slope 1.74 (7/01/04) (Easting 224833, Northing 6256491– in the vicinity of Bat 4 [Figure 2]), the researcher being on site at approximately 19.30hours. At the completion of this survey method, which lasted for approximately 30 minutes after dark, no territorial owl or mammal calls had been detected.

Whilst conducting the nocturnal surveys, spotlighting (using 100 watt hand held spotlights) was undertaken. The spotlighting transects were either conducted on foot, or via motor vehicle at a rate of 5km/h. The spotlighting sessions commenced 30 minutes after dark and lasted for approximately 2 hours. During the spotlighting sessions, efforts were made to target those habitats considered suitable for nocturnal animals, particularly those species of conservation significance identified during the literature review process as having been previously recorded in the study region. Site sampled during the spotlighting sessions are identified on Figure 2.

During the nocturnal surveys, the identification of microchiropterans, using Anabat II echolocation detectors, was undertaken. The detectors used to identify the presence of these species were placed at a variety of locations (Figure 2, Table I), these sites being selected as they corresponded to those habitats likely to be used by microchiropterans as roosting sites (i.e. woodland stands), or during their foraging and dispersal periods (i.e. woodlands and habitat ecotones). The echolocation detectors were generally turned on fifteen minutes prior to dusk (thereby endeavouring to detect any microbats that were leaving those likely roosting sites targeted) and were left in place all night (the tape recorders being set for voice activation with sun set being approximately 20.30 hours and sun rise 6.00 am). Any calls recorded were analysed using Anabat 6.3 computer software. The survey locations and effort obtained through use of this method are provided in Table 1.

Based on the results of the literature review, call playbacks targeting the presence of the Powerful Owl (Ninox strenua), Barking Owl (Ninox connivens), Sooty Owl (Tyto tenebricosa), Yellow-bellied Glider (Petaurus australis) and Koala (Phascolarctos cinereus) were undertaken during the spotlighting sessions. During these sessions, the calls (which were taken from Buckingham and Jackson 1990 and Stewart 1999 and lasted for five minutes per species) of these threatened species were broadcast through a megaphone connected to a compact disc player. The sites chosen for the call playbacks are identified in Table I and mapped on Figure 2.




Figure 2. Locations of fauna survey sites.

Table I. Fauna survey locations.

Site	Date	Location	Easting	Northing	Survey effort
Bat I	6/1/05	Inspiration lookout.	225738	6254911	9.75 hours
Bat 2	6/1/05	Access track atop of cut slope 3.64.	225715	6255370	9.75 hours
Bat 3	7/1/05	Cut slope 7.02	225150	6254044	9.75 hours
Bat 4	7/1/05	Cut slope 1.75	224833	6256491	9.75 hours
Playback	6/1/05	Cut slope 3.64	225815	6255392	45 mins
Playback 2	6/1/05	200m north of cut slope 7.02	225278	6254478	45 mins
Playback 3	7/1/05	Cut slope 1.75	224827	6256473	45 mins
Playback 4	7/1/05	Cut slope 5.08 / 5.29	225251	6254950	45 mins
				TOTAL	42 hours

To detect any calls or responses made by the threatened species targeted during the call playbacks, prior to, and after, the call playbacks, a ten minute listening period was undertaken. After the call playbacks and subsequent listening periods, spotlighting of the area was also undertaken to detect any species that may have been attracted to the calls, but which did not respond vocally. By the completion of this component of the field investigation, a total survey effort of approximately 3 hours had been accumulated.

The purpose of the field investigations was to locate within the areas surveyed any plants, animals or vegetation communities that are of regional, state and/or national conservation significance. When conducting the field investigations, the 'Random Meander Method' (as per Cropper 1993) (or an adaptation of this) was employed. This method is suitable for covering large areas and for locating any rare species (and their associated vegetation communities / habitat types) that may occur within a survey site. The method involves walking randomly across the survey area while sampling all of the various habitat types and vegetation communities until no new species have been recorded for at least thirty minutes.

By the completion of the field surveys, approximately 28 person hours of active investigation had been accumulated. Given the relatively small size of the study area, combined with its open nature, no limitations to the success of the field investigations were encountered. Similarly, for those threatened species targeted as potentially occurring, based on their previous recording within this portion of the Oberon Local Government Area, no limitations based on seasonal conditions and survey timings were encountered.

In addition to the field surveys methods employed, a targeted survey was undertaken by Mjadwesch Environmental Service Support to determine the presence of the Purple Copper Butterfly (*Paralucia spinifera*) (refer to attached report, Appendix 4)

## Literature review and field guides.

Prior to the undertaking of any field work, previous studies conducted in the region and known databases were consulted to identify the diversity of species known for, or potentially occurring in, the study region. These species could potentially utilise or occupy the study area on occasion but were not observed, recorded or indicated during the current field investigation. The literature search also ensures that the results from surveys conducted during different climatic, seasonal and date periods are considered. This approach increases the probability of considering the presence of, and possible impacts on, all known and likely native species, particularly those of conservation concern.

The identification of known, or potentially occurring, native species within the region, particularly those listed under the EPBC and TSC Acts, also permits the tailoring of the field survey strategies to the detection of these animals and plants, or their necessary habitats and vegetation associations.

The studies, reports and databases referred to include:

- The natural vegetation of the Katoomba 1:100,000 map sheet (Keith and Benson 1988);
- The Jenolan Caves Reserve Draft Plan of Management (Mt King Ecological Surveys 1989);
- A flora and fauna assessment undertaken in relation to the proposed widening of Jenolan Caves Road between Lithgow Road and Hampton Halfway House, and Duckmaloi Road between Oberon and Jenolan Caves Road (LandScope Environmental Consultants 1996);
- A Review of Environmental Factors for the maintenance of a culvert under the Grand Arch at Jenolan Caves (LandScope Environmental Consultants 1997);
- A flora and fauna assessment of five rock cuttings that occur adjacent to Jenolan Caves Road (LesryK Environmental Consultants 2004);
- A Review of Environmental Factors for the removal of weeds and the regeneration of bushland within the Jenolan Karst Conservation Reserve (Woodlots and Wetlands Pty. Ltd. and Urban Bushland Management Consultants 2004);
- The Jenolan Karst Conservation Reserve Draft Plan of Management (Manidis Roberts 2004);
- Oberon Council's State of the Environment Report (Oberon Council 2004);
- The DEH online database (DEH 2005b); and
- The Department of Environment and Conservation's (DEC) Atlas of NSW Wildlife Database (DEC 2005).

When accessing the DEC and DEH databases, the search area specified was 10 square kilometres  $(km^2)$  centred on the study area. Other reports and documents referred to are provided within the bibliography section of this report.

Field guides and standard texts used were:

- Harden (1992, 1993, 2000 and 2002) (for the identification of plants);
- Cogger (1992) (reptiles and frogs);
- Simpson and Day (1999) (birds);
- Strahan (1995) (mammals);
- · Churchill (1998) (bats); and
- Triggs (1996) (identification of scats, tracks and markings).

The naming of those species recorded or known for the region follows the nomenclature presented in these texts or as described on the Schedules to the EPBC and TSC Acts.

The stands of vegetation present are described in accordance to Keith and Benson (1988) and Mt King Ecological Surveys (1989).

The state and national conservation significance of those plants and animals recorded is made with reference to the EPBC and TSC Acts, the publication Rare or Threatened Australian Plants (ROTAP) (Briggs and Leigh 1996) and Oberon Council's State of the Environment Report. In the regional context, the conservation significance of those plants and animals recorded was established with reference to:

- The natural vegetation of the Katoomba 1:100,000 map sheet (Keith and Benson 1988); and
- The Jenolan Caves Reserve Draft Plan of Management Vegetation survey (Mt King Ecological Surveys 1989);
- The Jenolan Karst Conservation Reserve Draft Plan of Management (Manidis Roberts 2004).

# Flora results.

# 5.1. Plant species.

A list of plant species recorded within the study area is provided in Appendix I. It should be noted that this is not a comprehensive list of all exotic or weed species present, and only represents those plants recorded whilst searching for species of national or regional conservation concern that are known or have the potential to occur in the study area. It is a comprehensive list of those native plant species present.

By the completion of the field survey, no species of national or state conservation significance as listed on the Schedules to the EPBC or TSC Acts had been recorded.

Consultation of the DEC and DEH online databases identified a number of plants of conservation significance that have been previously recorded in the area of the Katoomba 1:100,000 map sheet. Of these, II were considered to have the potential to occur in the study area based on their known habitat requirements and the habitats occurring in association with the cut slopes (Table 2). Although these species were targeted during the field investigations, none were located within, or in close proximity to, the boundaries of any of the proposed works sites.

**Table 2.** Plant species of conservation significance previously recorded in the Oberon Local Government Area.

## Key

SI = Schedule I (Endangered). S2 = Schedule 2 (Vulnerable).

Regionally Significant: The species is considered to be of regional significance by some authors due to its restricted occurrence in the study region.

Species (Family)	Conservation Status				
	ROTAP	Regional Significance	EPBC Act	TSC Act	
Acacia flocktoniae (Mimosaceae)	2VC-		S2	S2	
Beyeria lasiocarpa (Rutaceae)	Not listed	R	Not listed	Not listed	
Caladenia tessellata (Orchidaceae)	3∨		S2	SI	
Eucalyptus pulverulenta (Myrtaceae)	3∨		S2	S2	
Euphrasia scabra (Scrophulariaceae)	3Kca		Not listed	SI	
Geranium graniticola (Geraniaceae)	3RC-		Not listed	Not listed	
Gonocarpus longifolius (Haloragaceae)	3RC-		Not listed	Not listed	
Hakea dohertyi (Proteaceae)	2VCi		SI	SI	
Melaleuca armillaris (Myrtaceae)	Not listed	R	Not listed	Not listed	
Persoonia acerosa (Proteaceae)	2VC-		S2	S2	
Pseudanthus divaricatissimus (Euphorbiaceae)	3RCa		Not listed	Not listed	
Stemmacantha australis (Asteraceae)	3∨		S2	Presumed	
Thesium australe (Santalaceae)	3VCi+		S2	S2	

During the field survey, Blackberry (Rubus ulmifolius) was recorded at cut slopes 4.22, 7.02, 7.58 and 8.13, this being listed as a noxious within the Oberon Local Government Area (Upper Macquarie County Council pers.comm. 4/2/05). This is a Class 3 weed, thereby requiring that it be prevented from spreading and its numbers and distribution be reduced. In relation to the presence of this plant, it is noted that the Upper Macquarie County Council undertakes regular spraying of those weed species that occur along Jenolan Caves Road (Upper Macquarie County Council pers.comm. 4/2/05).

# 5.2. Vegetation communities.

No Endangered Ecological Communities listed under the TSC and/or EPBC Acts were recorded within the study area, and none have been previously identified in the study region.

The study area along Jenolan Caves Road grades from a dry open-forest on the upper slopes with a sparse shrub and groundcover layer, to a moist open-forest with a dense shrub layer and a dense understorey of grasses, climbers and ferns. The community is generally consistent throughout the length of the road, with some species either present or absent at a site-specific level as a result of soil moisture and aspect differences. Southern Blue Gum *Eucalyptus bicostata* only occurs on the lower parts of the ridge, in association with those cut slopes that are present near the Jenolan River.

The study area and the surrounding vegetation was mapped and described by Mt King Ecological Surveys in 1989 as part of a Draft Plan of Management for the Jenolan Caves Reserve (Mt King Ecological Surveys 1989). That study updated and refined the vegetation community descriptions provided in Keith and Benson (1988). The Mt King study mapped nine vegetation communities within the Jenolan Karst Conservation Area, the area on the eastern side of Binoomea Ridge above 1100m (along which Jenolan Caves Road is constructed) is mapped as being:

Map unit 9n Open-forest: Eucalyptus fastigata, E. dalrympleana ssp. dalrympleana and E. viminalis.

All of the cut slopes showed signs of past disturbance, possibly including logging. Past disturbances for road construction have resulted in areas of unstable slopes where soil slip continues to create disturbances to the vegetation.

The trees occurring in and around each of the cut slopes / walls were:

- Cut slope C1.74: Eucalyptus viminalis E. dalrympleana E. blaxlandii E. fastigata Openforest.
- Cut slope C2.63: Eucalyptus viminalis E. dalrympleana E. fastigata Open-forest.
- **Cut slope C3.64:** Eucalyptus viminalis E. dalrympleana E. fastigata E. blaxlandii Openforest.
- Cut slope C4.22: Eucalyptus viminalis E. dalrympleana E. fastigata E. blaxlandii Openforest.
- Cut slopes C5.08 and 5.29: Eucalyptus viminalis E. dalrympleana E. fastigata E. blaxlandii Open-forest.
- Cut slope C7.02: Eucalyptus viminalis E. dalrympleana E. blaxlandii E. bicostata Openforest.
- Walls 40/41: Eucalyptus eugenoides Eucalyptus bicostata Open-forest.
- Cut slope C7.58: Eucalyptus viminalis E. dalrympleana E. blaxlandii E. fastigata E. bicostata Open-forest.
- Cut slope C8.13: Eucalyptus viminalis E. dalrympleana E. blaxlandii E. fastigata E. bicostata Open-forest.

For reference, a description of the main species occurring at each of the sites is provided below.

Cut slope C1.74: Eucalyptus viminalis – E. dalrympleana - E. blaxlandii – E. fastigata Open-forest.

#### Structure:

Open-forest with trees to 15m in height forming a moderate foliage cover. The shrub layer is generally sparse with low shrubs to 2m in height. The groundcover consists of a variable density layer of grasses and herbs.

The down slope side is very steep with unstable rocky soil. Vegetation consists of the same species but with a higher density of ferns and grasses. The area was not surveyed on foot due to safety concerns.

# Common Species (\* = exotic species):

#### Trees

Manna Gum Eucalyptus viminalis, Brown Barrel E. fastigata, Blaxland's Stringybark E. blaxlandii and Mountain Gum E. dalrympleana. The tall shrub/small tree Wattle Blackwood Acacia melanoxylon also occurs.

## Shrubs:

River Lomatia Lomatia myricoides and Scrub Nettle Urtica incisa.

## Groundcovers:

Spiny Mat-rush Lomandra longifolia, Mother-shield Fern Polystichum proliferum, Prickly Starwort Stellaria pungens, Native Tussock Poa labillardieri, Pennywort Hydrocotle peduncularis, Cranesbill Geranium potentilloides, Native Violet Viola hederacea and Centuary Centaurium tenuiflorum \*.

# Cut slope C2.63: Eucalyptus viminalis – E. dalrympleana - E. fastigata Open-forest.

## Structure:

Open- forest with a dense stand of sapling trees to about 10m in height forming a moderate foliage cover. The shrub layer is generally sparse. The groundcover consists of a dense cover of *Lomandra longifolia* as well as native grasses and herbs.

The down slope side of the road is very steep and consists of the same species mix but highly disturbed by previous road works. The area was not surveyed on foot due to safety concerns.

# Common Species:

#### Trees:

Manna Gum Eucalyptus viminalis, Brown Barrel E. fastigata and Mountain Gum E. dalrympleana. The tall shrub/small trees Wattle Blackwood Acacia melanoxylon and Broad-leaved Hickory Acacia falciformis also occur.

# Shrubs:

Blackthorn Bursaria spinosa ssp. spinosa, River Lomatia Lomatia myricoides, Cherry Ballarat Exocarpos cupressiformis and Narrow-leaved Geebung Persoonia linearis.

#### Groundcovers:

Spiny Mat-rush Lomandra longifolia, Smooth Darling-pea Swainsona galigefolia, Prickly Starwort Stellaria pungens, Pennywort Hydrocotle peduncularis, Cranesbill Geranium potentilloides, Native Violet Viola hederacea and Native Tussock Poa labillardieri.

## Cut slope C3.64: Eucalyptus viminalis – E. dalrympleana - E. fastigata – E. blaxlandii Open-forest.

## Structure:

Open – forest with sparse trees that up are to 15m in height within the study area, forming a moderate foliage cover. Sparse shrub layer to 2m in height. The groundcover consists of a variable layer of sparse grasses and herbs.

The down slope side is very steep and consists of the same species but is more highly disturbed by previous road works. The area was not surveyed on foot due to safety concerns.

**Note:** This description also covers the proposed new access track and works site. The access track and works site are located in an area that is generally covered in young trees with little or no shrubs and a very sparse groundcover layer. The species occurring in these areas are the same as those occurring above the outting but in much lower abundance.

# Common Species:

## Trees:

Manna Gum Eucalyptus viminalis, Brown Barrel E. fastigata, Blaxland's Stringybark E. blaxlandii and Mountain Gum E. dalrympleana. The tall shrub/small tree Wattled Blackwood Acacia melanoxylon also occurs.

#### Shrubs:

Blackthorn Bursaria spinosa ssp. spinosa, River Lomatia Lomatia myricoides, Native Cranberry Lissanthe strigosa, Native Holly Oxylobium ilicifolium and Narrow-leaved Geebung Persoonia linearis.

#### Groundcovers:

Spiny Mat-rush Lomandra longifolia, Smooth Darling-pea Swainsona galigefolia, Prickly Starwort Stellaria pungens, Pennywort Hydrocotle peduncularis, Bracken Fern Pteridium esculentum, Hyacinth Orchid Dipodium punctatum and Native Tussock Poa labillardieri.

# Cut slope C4.22: Eucalyptus viminalis – E. dalrympleana - E. fastigata – E. blaxlandii Open-forest.

#### Structure:

Open – forest with trees to about 15m in height, forming a moderate foliage cover. A sparse low shrub layer to 2m in height occurs across the slope. The groundcover consists of a sparse layer of grasses and herbs.

The down slope side is steep and consists of the same species but is more highly disturbed by previous road works. The area was not surveyed on foot due to safety concerns.

# Common Species:

#### Trees:

Manna Gum Eucalyptus viminalis, Brown Barrel E. fastigata, Blaxland's Stringybark E. blaxlandii and Mountain Gum E. dalrympleana. A single Grey Gum E. punctata also occurs in the study area. The tall shrub/small tree Wattled Blackwood Acacia melanoxylon also occurs.

# Shrubs:

Blackthorn Bursaria spinosa ssp. spinosa, River Lomatia Lomatia myricoides, Native Cranberry Lissanthe strigosa, Native Holly Oxylobium ilicifolium and Narrow-leaved Geebung Persoonia linearis.

#### Groundcovers:

Spiny Mat-rush Lomandra longifolia, Smooth Darling-pea Swainsona galigefolia, Prickly Starwort Stellaria pungens, Pennywort Hydrocotle peduncularis, Bracken Fern Pteridium esculentum, Wallaby Grass Austrodanthonia sp. and Native Tussock Poa labillardieri.

Cut slopes C5.08 and 5.29: Eucalyptus viminalis – E. dalrympleana - E. fastigata – E. blaxlandii Openforest.

#### Structure

Open-forest with trees to about 15m in height, forming a moderate foliage cover. A sparse low shrub layer to 2m in height occurs. The groundcover consists of a sparse to locally dense layer of native grasses and herbs. The site grades from a dry forest to a more moist forest on the southern face of cut slope 5.29.

The down slope side is very steep and consists of the same species but is more highly disturbed by previous road works. The area was not surveyed on foot due to safety concerns.

# Common Species:

#### Trees

Manna Gum Eucalyptus viminalis, Brown Barrel E. fastigata, Blaxland's Stringybark E. blaxlandii and Mountain Gum E. dalrympleana. The tall shrub/small tree Wattled Blackwood Acacia melanoxylon and Blueberry Ash Eleocarpus reticulatus also occurs.

#### Shrubs:

Blackthorn Bursaria spinosa ssp. spinosa, Tree Violet Hymenanthera dentata, River Lomatia Lomatia myricoides, Native Cranberry Lissanthe strigosa, Nodding Blue Lily Stypandra glauca, Native Holly Oxylobium ilicifolium and Everlasting Daisy Ozothamnus diosmifolium.

#### Groundcovers:

Spiny Mat-rush Lomandra longifolia, Pennywort Hydrocotle peduncularis, Prickly Starwort Stellaria pungens, Sickle Fern Pellaea falcata, Maidenhair Fern Adiantum aethiopicum and Necklace Fern Asplenium flabellifolium.

# Climbers

Old Man's Beard Clematis aristata and Scrambling Lily Geitonoplesium cymosum.

# Cut slope C7.02: Eucalyptus viminalis – E. dalrympleana - E. blaxlandii – E. bicostata Open-forest.

#### Structure

Open – forest with trees to about 15m in height that form a moderate foliage cover. A sparse low shrub layer to 2m in height occurs. The groundcover consists of a sparse to locally dense layer of native grasses and herbs.

The down slope side is extremely steep and unstable, and consists of the same species but is more highly disturbed by previous road works. The area was not surveyed on foot due to safety concerns.

# Common Species:

#### Trees:

Manna Gum Eucalyptus viminalis, Blaxland's Stringybark E. blaxlandii, Mountain Gum E. dalrympleana and Southern Blue Gum E. bicostata. The tall shrub/small tree Wattle Blackwood Acacia melanoxylon also occurs.

# Shrubs:

Blackthorn Bursaria spinosa ssp. spinosa, Tree Violet Hymenanthera dentata, River Lomatia Lomatia myricoides, Native Cranberry Lissanthe strigosa, Lance Beard-heath Leucopogon lanceolatus and Hop-Goodenia Goodenia ovata.

## Groundcovers:

Spiny Mat-rush Lomandra longifolia, Pennywort Hydrocotle peduncularis, Prickly Starwort Stellaria pungens, Sickle Fern Pellaea falcata, Maidenhair Fern Adiantum aethiopicum, Necklace Fern Asplenium flabellifolium and Bracken Fern Pteridium esculentum.

#### Climbers

Old Man's Beard Clematis aristata, False Sarsaparilla Hardenbergia violaceae and Scrambling Lily Geitonoplesium cymosum.

# Walls 40/41: Eucalyptus eugenoides - Eucalyptus bicostata Open-forest.

Note: A large portion of these walls has already been cleared and remediated.

#### Structure:

Open – forest with trees to about 10m in height form a sparse to moderate foliage cover. A dense low shrub layer to 1m in height occurs across the slope. The groundcover consists of a sparse layer of mat rush, grasses and herbs.

## Common Species:

#### Trees:

Thin-leaved Stringybark Eucalyptus eugenoides and Southern Blue Gum E. bicostata.

#### Shrubs:

Blackthorn Bursaria spinosa, Native Cranberry Lissanthe strigosa, Broad-leaved Hickory Acacia falciformis, Austral Indigo Indigophora australis and Large Mock Olive Notelaea longifolia.

#### Groundcovers:

Spiny Mat-rush Lomandra longifolia, Kangaroo Grass Themeda australis, Wallaby Grass Austrodanthonia sp., Kidney Weed Dichondra repens, Prickly Starwort Stellaria pungens and Necklace Fern Asplenium flabellifolium.

Cut slope C7.58: Eucalyptus viminalis – E. dalrympleana - E. blaxlandii - E. fastigata – E. bicostata Openforest.

#### Structure:

Open- forest with trees to about 15m in height, forming a moderate foliage cover. A moderately dense shrub layer to 2m in height occurs. The groundcover consists of a locally dense layer of native grasses and herbs. The site is south-facing and has higher ground moisture levels. The low shrubby weed Tutsan Hypericum androsaemum covers most of the slope. Blackberry also occurs.

The down slope side is very steep and consists of the same species but is more highly disturbed by previous road works and an existing dirt road. The area was not surveyed on foot due to safety concerns.

# **Common Species:**

#### Trees:

Manna Gum Eucalyptus viminalis, Blaxland's Stringybark E. blaxlandii, Southern Blue Gum E. bicostata and Mountain Gum E. dalrympleana. The tall shrub/small tree Blackwood Acacia melanoxylon also occurs.

#### Shrubs

Blackthorn Bursaria spinosa ssp. spinosa, Tree Violet Hymenanthera dentata, River Lomatia Lomatia myricoides, Lance Beard-heath Leucopogon lanceolatus and Sticky Hop-bush Dodonaea viscosa.

### Groundcovers:

Spiny Mat-rush Lomandra longifolia, Pennywort Hydrocotle peduncularis, Prickly Starwort Stellaria pungens, Sickle Fern Pellaea falcate and Bracken Fern Pteridium esculentum.

#### Climbers

Old Man's Beard Clematis aristata, False Sarsaparilla Hardenbergia violaceae and Scrambling Lily Geitonoplesium cymosum.

Cut slope C8.13: Eucalyptus viminalis – E. dalrympleana - E. blaxlandii - E. fastigata – E. bicostata Openforest.

#### Structure:

Open- forest with trees to about 15m in height, forming a moderate foliage cover. A moderately dense shrub layer to 2m in height occurs. The groundcover consists of a locally dense layer of native grasses and herbs. The site is south-facing, close to Jenolan River and has higher ground moisture levels.

The down slope side is very steep and consists of the same species but is more highly disturbed by previous road works and an existing dirt road. The area was not surveyed on foot due to safety concerns.

# Common Species:

### Trees:

Manna Gum Eucalyptus viminalis, Blaxland's Stringybark E. blaxlandii, and Southern Blue Gum E. bicostata and Mountain Gum E. dalrympleana. The tall shrub/small tree Blackwood Acacia melanoxylon also occurs.

#### Shrubs:

Blackthorn Bursaria spinosa ssp. spinosa, Tree Violet Hymenanthera dentata, River Lomatia Lomatia myricoides, Blue Nodding Lily Stypandra glauca and Sticky Hop-bush Dodonaea viscosa.

### Groundcovers:

Spiny Mat-rush Lomandra longifolia, Pennywort Hydrocotle peduncularis, Prickly Starwort Stellaria pungens, Tongue Orchid Dendrobium linguiforme and Bracken Fern Pteridium esculentum.

## Climbers

Old Man's Beard Clematis aristata, False Sarsaparilla Hardenbergia violaceae and Scrambling Lily Geitonoplesium cymosum.

#### 5.3. Flora discussion.

The sites surveyed are all very small and do not show a great diversity of species. At each site generally only a few species make up the majority of the vegetation community. This is common in many alpine and semi-alpine habitats. None of the cut slopes are important habitat for any of the threatened plants, plant populations or ecological communities that are known to occur in the region. The direct impacts of the removal of vegetation from the study area would be small in comparison to the amount of similar vegetation that occurs on Binoomea Ridge and within the surrounding region.

Though targeted, no threatened plants were found in the study area and the vegetation community recorded is not listed as an Endangered Ecological Community under either the TSC and/or EPBC Acts. The removal of up to 6.15ha of this vegetation type, which is common throughout Binoomea Ridge, from the study area would not result in the loss of any plant biodiversity from the locality.

#### 6. Fauna results.

# 6.1. Habitat types.

One habitat type, a eucalypt woodland, is uniformly present throughout the study area (including the proposed access track and works site), this habitat type also being present adjacent to, and beyond the limits of, the likely works areas.

The eucalypt woodland supports trees that are between 10 and 15m in height, the majority of which, particularly those on the cut slopes themselves, are not hollow bearing. Whilst this is the case, particularly on top of the cut slopes, isolated hollow bearing trees are present at various locations, these supporting hollows that have a diameter of 700mm (density of hollow bearing trees throughout the eucalypt woodlands is approximately 1 hollow bearing tree per 0.2ha). Throughout the eucalypt woodland the tree canopy is generally continuous, though some 8m wide gaps are present. The understorey is either absent, or composed of isolated saplings that are to 2m in height. Similarly the ground cover layer is absent, or composed of a sparse distribution of native grasses, ferns and forbs. Leaf litter, fallen trees and branches are common, as is some exposed rock. For reference, percentage covers of those habitat layers observed within a randomly selected 10 x 10m quadrate are provided:

- Tree cover = 15%;
- Shrub cover = >1%:
- Ground cover = 10%:
- Leaf litter = 70%; and
- Bare earth = 30%.

On the cut slopes themselves, exposed rock faces are common, none of which were observed to support any suitable sheltering caves, crevices or ledges. The Jenolan Karst system (Jenolan Caves) is located nearby, this providing a vast supply of potential resources for cave-dwelling native fauna. Given the extent of works proposed, the Jenolan Karst system would not be affected by the Proposal. The cut slopes are vegetated by several native saplings, shrubs and ground cover plants, the density of which is generally sparse. In regards to several of those plants present on the cut slopes, these have either been removed or trimmed as part of the ongoing maintenance activities associated with the use of Jenolan Caves Road. Where present, the trees are to 8m in height, the shrubs 2m and the ground cover plants 0.3m. No hollow bearing trees were observed in association with any of the cut slopes.

As noted previously, the Proposal would require the removal of approximately 6.15ha of woodland. In comparison with the surrounding 350,106ha of similar bushland, the woodland present within the study area is not considered to represent a significant area of habitat for any native animals. The removal of those plants that have re-established on the rock batters after construction of Jenolan Caves Road is not considered to have an adverse impact on the local or regional occurrence of any native fauna. The resources offered by the study area are not unique to this site, this environment being regularly recorded in the surrounding region. As such, the proposed works can proceed as planned without significantly altering the region's biodiversity.

As mentioned, no drainage lines were observed within the study area.

# 6.2. Fauna species recorded.

By the completion of the field investigations, a total of 19 native mammals, 34 native birds and 2 reptiles had been recorded (Appendix 2). In regards to the detection of these species:

- All birds were either observed within, adjacent to or flying over the study area, or identified from their distinct calls;
- The Tawny Frogmouth Podargus strigoides was spot lite on the 6/01/05 whilst the Southern Boobook Ninox novaeseelandiae was heard calling during each of the spotlighting sessions;

- The Powerful Owl Ninox strenua and Sooty Owl Tyto tenebricosa were both identified during the call playback sessions;
- The Grass Skink Lampropholis delicata was observed during the ground debris searches, whilst a
  road kill Red-bellied Black Snake Pseudechis porphyriacus was observed on Jenolan Caves Road,
  north of cut slope 1.74;
- The Brown Antechinus Antechinus stuartii, Greater Glider Petauroides volans, Common Brushtail Possum Trichosurus vulpecula, Eastern Grey Kangaroo Macropus giganteus, Red-necked Wallaby Macropus rufogriseus and Swamp Wallaby Wallabia bicolor were all spot lite;
- The Short-beaked Echidna Tachyglossus aculeatus and Common Wombat Vombatus ursinus were both identified through the observation of their characteristic droppings;
- The Yellow-bellied Glider Petaurus australis was heard calling during the call playback sessions; and
- All microchiropterans were detected through the analysis of those bat calls recorded (Table 3).

Of those species recorded by the completion of the field investigation the Powerful Owl Ninox strenua, Sooty Owl Tyto tenebricosa, Satin Flycatcher Myiagra cyanoleuca, Yellow-bellied Glider Petaurus australis, Large-eared Pied Bat Chalinolobus dwyeri, Eastern False Pipistrelle Falsistrellus tasmaniensis, Large-footed Myotis Myotis adversus and Eastern Bentwing Bat Miniopterus schreibersii are all listed under the state and/or national environmental legislations. In addition to these species, the Gang-gang Cockatoo Callocephalon fimbriatum has been Preliminary listed (i.e. a Preliminary Determination has been made by the NSW Scientific Committee) for inclusion as a vulnerable species under Schedule 2 of the TSC Act.

In regards to the detection of these species of state and/or national conservation concern:

- The Powerful Owl, a species listed under Schedule 2 of the TSC Act, was heard during the call playback sessions, this species being heard down slope of Jenolan Caves Road at playback sites 2 (1 individual) and 4 (2 individuals);
- The Sooty Owl (Schedule 2 of the TSC Act) responded to the call playback undertaken at playback site 4, this species entering cut slope 5.29 from a southerly, down slope, direction;
- A pair of Satin Flycatchers (migratory bird listed under the EPBC Act) were observed traversing through the woodland that is present on cut slope 5.29;
- Several Yellow-bellied Gliders (Schedule 2 of the TSC Act) were heard down slope of playback sites I and 4;
- The threatened microchiropterans were recorded at bat sites 1, 3 and 4 (Table 1). Of those microchiropterans recorded, it is noted that the Large-eared Pied Bat Chalinolobus dwyeri is listed under the Schedules to both the EPBC and TSC Acts, the remainder of the bats only being listed under the TSC Act; and
- The Gang-gang Cockatoo was heard calling down slope of cut slopes 3.64, 5.08 and 7.02.

For reference, profiles of these species of conservation concern are provided in Sections 6.2.1 to 6.2.9 of this report. As an aside, it is noted that the Powerful Owl, Sooty Owl, Eastern False Pipistrelle and Eastern Bentwing Bat were all recorded within the study area during the previous investigation undertaken at this site (LesryK Environmental Consultants 2004).

The remainder of the native fauna species recorded are protected, as defined under the NSW National Parks and Wildlife Act 1974, but considered to be common to abundant throughout their distribution ranges. These animals would be regularly recorded in the surrounding region in association with their documented habitat types. None of the species recorded would be solely dependant upon the resources provided by the study area, such that the disturbance of those habitats

present would cause either the local or regional displacement of any of these animals. The undertaking of the Proposal would not remove any habitats important to any of these animals, such that the disturbance of these habitats would affect the local or regional status of any of these species. The proposed works would not present a barrier to the dispersal patterns of any of these species, nor would it isolate any proximate areas of their necessary habitats.

Table 3. Results of bat call analysis.

Survey Common Name Location		Scientific Name	Call Confidence	No. of Passes
Bat I	Gould's Wattled Bat	Chalinolobus gouldii	С	13
	Chocolate Wattled Bat	Chalinolobus morio	P	3
	# Eastern Bentwing Bat	Miniopterus schreibersii	C	11
	Large Forest Bat	Vespadelus darlingtoni	C	102
	Southern Forest Bat	Vespadelus regulus	С	9
	Little Forest Bat	Vespadelus vulturnus	P	3
	Eastern Freetail Bat	Mormopterus sp. 2	P	2
	Unidentified bat			40
	White-striped Freetail Bat	Nyctinomus australis	С	
Bat 2	Large Forest Bat	Vespadelus darlingtoni	С	T
	Little Forest Bat	Vespadelus vulturnus	С	1
	Unidentified bat			1
Bat 3	# Eastern Bentwing Bat	Miniopterus schreibersii	Ро	1
	# Large-footed Myotis	Myotis adversus	P	1
	Large Forest Bat	Vespadelus darlingtoni	С	1
	Southern Forest Bat	Vespadelus regulus	Р	I
	Little Forest Bat	Vespadelus vulturnus	С	5
	Unidentified bat			3
Bat 4	* # Large-eared Pied Bat	Chalinolobus dwyeri	С	2
	Chocolate Wattled Bat	Chalinolobus morio	P	2
	# Eastern False Pipistrelle	Falsistrellus tasmaniensis	Р	2
	# Eastern Bentwing Bat	Miniopterus schreibersii	С	2
	Large Forest Bat	Vespadelus darlingtoni	С	71
	Southern Forest Bat	Vespadelus regulus	Р	I
	Little Forest Bat	Vespadelus vulturnus	С	6
	Unidentified bat			21

<sup>\* -</sup> indicates species listed under the EPBC Act.

## Note:

In relation to the analysis of those microchiropteran calls obtained, it is noted that some insectivorous bat species have distinctive echolocation calls that are unlikely to be confused with those of other species. Other bat species overlap in both call frequency and structure making identification problematic in some cases. The degree of confidence attached to call identifications will depend on the quality of the recordings as well as the activity of the bat at the time of recording and its direction of flight. In some instances a particular species may be identified with confidence, while at other times its identification will be less certain. For this report, echolocation call identifications have been assigned to three categories with regard to certainty of identification, these being:

- C Confident Identification. Small possibility of confusion of calls with those of other bat species.
- P Probable Identification. Some possibility of confusion of calls with those of other bat species.
- Po Possible Identification. Likely to be confused with calls with those of other bat species.

<sup># -</sup> indicates species listed under the TSC Act.

# 6.2.1. Powerful Owl (Ninox strenua).

The Powerful Owl favours gullies and gorges that are unlogged to lightly logged (Chafer 1992, Debus and Chafer 1994). These gullies usually consist of wet to dry sclerophyll forest with a dense understorey (Garnett 1993, Hollands 1991). It nests in large hollows, nearly always in the trunk or the top of a broken eucalypt (Hollands 1991). When not breeding, the Powerful Owl will roost during the day within shelter provided by a dense overstorey canopy, such as a bushy eucalypt or vine forest, usually clutching the remains of the previous evenings meal (Pavey 1995, McNabb 1996). Information on the size of its home range is scant with estimates ranging from 300ha to more than 1000ha (Garnett 1993, McNabb 1996). The Powerful Owl breeds from June to September with pairs being faithful to particular roost trees (C.Chafer, researcher, pers.comm., Pavey et al. 1994). The close proximity of roosts to residential and/or recreational areas does not appear to affect the breeding success of Powerful Owls (Pavey et al. 1994). This species is able to traverse open country therefore not being affected by habitat fragmentation and isolation (Garnett 1993). The Powerful Owl's main prey are the medium-sized arboreal marsupials, particularly the Ringtail Possum and Sugar Glider (Pavey et al. 1994, Pavey 1995, McNabb 1996). Birds, rodents, fruit bats and rabbits will also be taken (Pavey et al. 1994). The main threat to the survival of this species is the loss of old-growth forest elements, particularly trees that are large enough for the owl to use for nesting (Garnett 1993).

Based on the above information, and the results of the field investigations, it is not considered that the Powerful Owl would rely upon the study area such that the Proposal would have any impact on this species, its population or habitats. Although this is the case, to further consider the likely impacts of the works on this species, an assessment using the criteria listed under Section 5A of the Environmental Planning and Assessment Act 1979 (these commonly being referred to as the "eight part test") has been undertaken in Section 7.2.5.

# 6.2.2. Sooty Owl (Tyto tenebricosa).

Occurring along the south-eastern coast and adjacent southern and eastern slopes of the Great Dividing Range, the Sooty Owl is distributed from south-eastern Queensland through to southern Victoria (Garnett 1993, Simpson and Day 1996). Throughout this range it is considered to be scarce (Garnett 1992). Inhabiting tall, wet, old growth forests on fertile soils with a dense understorey, the Sooty Owl usually roosts in the trunks of mature Eucalypts. (Garnett 1993). This habitat is usually confined to gully areas with the Sooty Owl appearing to be loyal to nest sites (Garnett 1993, Hollands 1991). Prey species include arboreal mammals, though some birds and terrestrial mammals will be taken (Frith 1977, Garnett 1993). Accurate home range estimates for this species are presently unknown, but current radiotelemetric research on tagged individuals caught in the Royal National Park, Sydney, approximated 3000ha (R.Kavanagh, NSW Forestry, pers. comm.). Within this home range, the owls have only been recorded as using two thirds of this total area (R.Kavanagh, pers. comm.).

The survival of this species is threatened through habitat clearance, inappropriate forestry practices, fire, and habitat isolation (Garnett 1993, Hollands 1991). There also appears to be a strong correlation between the presence of this species and a high diversity and abundance of prey species (Garnett 1993). Where this is not the case, this species is not found, even though the habitat structure may be suitable (Garnett 1993). The Sooty Owl has therefore been described as an indicator species of undisturbed old growth forest and hollow-dependent mammal species (Norton and Lindenmayer 1991).

As with the Powerful Owl, it is not considered that the Sooty Owl would be reliant upon those habitats recorded within the study area. As such, the Proposal would not have a significant impact on this species, its populations or habitats. To further consider the impacts of the Proposal on this species, an eight part test has been undertaken (Section 7.2.6). In regards to this species it is noted that the cut slopes generally occur near the top of a ridge and that the Sooty Owl detected entered the study area from a southerly, down slope location.

# 6.2.3. Satin Flycatcher (Myiagra cyanoleuca).

The Satin Flycatcher is a migratory bird that over winters in New Guinea and its adjacent islands (Frith 1997). This species moves north between March and April, returning south between September and October (Frith 1997). The Satin Flycatcher occupies eucalypt woodlands, forests and timbered watercourses, this species feeding on a variety of insects, including grasshoppers, beetles and moths (Frith 1997, Beruldsen 2003). Breeding occurs between October and January, the Satin Flycatcher nesting in loose colonies of 2 to 5 pairs (Frith 1997).

To further consider the impacts of the Proposal on this species, an assessment using the EPBC Act's Administrative Guidelines on Significance for a migratory species has been undertaken in Section 7.1.2 of this report.

# 6.2.4. Yellow-bellied Glider (Petaurus australis).

The Yellow-bellied Glider is distributed from eastern Victoria through to central Queensland, with an isolated population occurring in northern Queensland (Russell 1980, Strahan 1995). Throughout these areas this animal's distribution is patchy, the Yellow-bellied Glider being restricted to areas of tall mature eucalypts where suitable feed trees are available (Strahan 1995). A nocturnal species, the Yellow-bellied Glider sleeps during the day in a large mature trees (Strahan 1995). This species is an exudivorous feeder, feeding predominantly on the sap that is obtained from incisions gnawed into the trunks of eucalyptus trees (Goldingay 1989, Strahan 1995). Preferred feed trees include Eucalyptus gummifera, E. maculata and E. piperita with E. saligna, E. viminalis and E. fastigata also being utilised (Goldingay 1989, Goldingay and Kavanagh 1991, Goldingay and Kavanagh 1993). These food resources undergo seasonal variations in abundance, therefore the Yellow-bellied Glider will modify its home range to utilise other food resources including nectar, pollen and insect honeydew (Goldingay 1989, Van Dyck 1992).

The Yellow-bellied Glider is a highly mobile species, gliding or climbing through the forest canopy (Braithwaite 1983, Goldingay and Kavanagh 1991). Where the tree cover is of sufficient height and density to provide for unobstructed movement, glide distances can be quite considerable (in the order of 70 – 100m) (author's field notes, Goldingay 1989, Goldingay and Kavanagh 1991, Engel and Fanning 1995).

Glider groups are usually comprised of three to four individuals, often consisting of an adult breeding pair and several subadults (Goldingay and Kavanagh 1993). This group will inhabit an exclusive home range, the size of which is variable, with estimates being from 20 to 85ha (Henry and Craig 1984, Craig 1985, Goldingay 1992, Goldingay and Kavanagh 1993, Goldingay et al. 2001, Lindenmayer 2002). Within this home range, the Yellow-bellied Glider will generally occupy one mature hollow bearing tree, the family group being loyal to this site (this loyalty appears to extend over a series of breeding periods) (author's field notes).

The Yellow-bellied Glider is threatened by habitat clearing and fragmentation, including the removal of hollow-bearing trees utilized for nesting, certain fire regimes which may isolate populations or affect food resources, and predation by feral animals such as foxes and cats (NPWS 1999).

During the field survey, no characteristic feeding incisions were observed on any of the trees present within the study area. Similarly, during the dusk sampling sessions, no individuals were heard exiting any of the hollow bearing trees present within the study area, particularly those that occur above cut slope 3.64. During the field surveys, whilst several Yellow-bellied Glider's were heard calling down slope of Jenolan Caves Road, none were actually detected within the study area itself. On occasion the Yellow-bellied Glider could potentially traverse through and across the study area, but given their ability to traverse relatively large open space areas, the extent of works proposed is not considered to present any barriers, or fragment any habitat areas. Given the restriction of the works to small portions of the road reserve of Jenolan Caves Road, opportunities would still exist for the east west movement of this species. Whilst the Proposal is not considered to have a significant impact on this species, its populations or habitats, to further consider the impacts of the slope remediations on this species, an eight part test has been undertaken in Section 7.2.7.

# 6.2.5. Large-eared Pied Bat (Chalinolobus dwyeri).

The Large-eared Pied Bat is distributed from central southern Queensland through to southern NSW (Strahan 1995, Churchill 1998). Throughout this range its status is described as uncommon (Parnaby 1992). Its preferred habitat is timbered woodland and dry sclerophyll forest (Hall and Richards 1979, Strahan 1995). The Large-eared Pied Bat is known to roost in caves, tunnels, rock overhangs, mines if available or even the abandoned nests of Fairy Martins (Strahan 1995, Churchill 1998, NPWS 2000). In contrast to other bats this species often chooses to roost close to the entrance of the cave, within the "twilight areas" (Strahan 1995, Churchill 1998). The Large-eared Pied Bat is a slow to moderate flier, with good manoeuvrability that forages on insects collected below the tree canopy (Strahan 1995, NPWS 2000). Threats to the survival of this species include the loss of caves which provide suitable roosting and breeding habitat (Strahan 1995).

Within the study area, no suitable caves, tunnels or rock overhangs were observed. As such, this species would not be roosting within the study area. Foraging opportunities exist within the study area for the Large-eared Pied Bat, though the loss of isolated patches of woodland from several sites within the entire study area is not considered to constitute a significant impact. The cumulative loss of a total of 6.15ha of potentially insect attractive plants, from the extensive area of similar woodland is not considered to reduce or significantly affect the extent of foraging resources available to this species. To further consider the potential impacts of the Proposal on the Large-eared Pied Bat, an assessment using the EPBC Act's Administrative Guidelines on Significance for a vulnerable species has been undertaken in Section 7.1.2 of this report. In addition, an eight part test has also been undertaken within Section 7.2.8 of this report.

# 6.2.6. Eastern False Pipistrelle (Falsistrellus tasmaniensis).

The Eastern False Pipistrelle is distributed southwards from south-eastern Queensland, along the coast and Great Dividing Range through to western Victoria and Tasmania (Strahan 1995). This species commonly occurs at high elevations with cool climates, and in Victoria shows a clear preference for wet habitats with trees taller than 20m (Menkhorst and Lumsden 1996). This species has also been recorded within eucalypt woodlands (Menkhorst and Lumsden 1996). Usually roosting in tree hollows, this species has also been recorded within caves in the Jenolan area and cave substitutes (e.g. buildings) (Menkhorst and Lumsden 1996). Known home ranges are in the order of 12km, though this may be a maximum size (Menkhorst and Lumsden 1996). The Eastern False Pipistrelle feeds on a variety of insects that are usually collected from around, or just below, the tree canopy (Menkhorst and Lumsden 1996). In relation to this species winter activities, there appears to be some conflict within the literature with some researchers suggesting that the Eastern False Pipistrelle migrates coastward, while others comment that it is a sedentary hibernator (Menkhorst and Lumsden 1996). Though not documented in the literature, the main threat to the survival of this species is expected to be the loss of suitable roosting trees.

Based on the information provided, and the results of the field survey it is not considered that the Eastern False Pipistrelle would significantly rely upon the study area such that the Proposal would have an adverse impact on this species. Although the works are not considered to have an adverse impact on this microchiropteran, an eight part test has been completed (Section 7.2.9).

## 6.2.7. Large-footed Myotis (Myotis adversus).

Found where there is permanent and/or slow flowing water, this species is generally found in the coastal regions of south-eastern South Australia, through Victoria, New South Wales, Queensland, the Northern Territory and the top of Western Australia (Hall and Richards 1979, Parnaby 1992, Strahan 1995). This species commonly roosts in caves and cave substitutes, but will also occupy tree hollows and dense foliage, the roosting site nearly always being in the vicinity of a suitable water body (Churchill 1998). This species emerges at dusk, feeding on aquatic insects that are "raked" off the waters surface (Strahan 1995). This species appears to be restricted to the vicinity of major waterways, some of which can be brackish (Hall and Richards 1979, Smith and Smith 1990, Parnaby 1992). In Victoria, Myotis roosting sites have been located both immediately over, and up to 400m away from, suitable water bodies (Lumsden and Menkhorst 1996). Breeding occurs between

November and December, with young being weaned after 3 to 4 weeks (Churchill 1998). The main threat to this species appears to be the disturbance of colonies, particularly during the colder months (Reardon and Flavel 1987).

Within the study area, no suitable caves or cave substitutes are present. Similarly, no water bodies suitable for the foraging needs of this species are present. Given the number of passes recorded for this species, the individual recorded is expected to have only been detected whilst traversing across the site. Given that no resources suitable for the life cycle requirements of the Large-footed Myotis are present within the study area, it is not considered that any adverse impacts would arise that would threaten either the local or regional occurrence of this microchiropteran. Whilst this is the case, to further consider the likely impacts of the Proposal on the presence of this species, an eight part test has been undertaken in Section 7.2.10 of this report.

# 6.2.8. Eastern Bentwing Bat (Miniopterus schreibersii).

The Eastern Bentwing Bat is the dominant cave-dwelling bat in south-eastern Australia (Parnaby 1992). This species occurs along the east coast and ranges of Australia, from south-eastern South Australia through to Queensland, the northern parts of Western Australia and the Northern Territory. Within its distribution this species roosts in caves, storm water channels, mines and other cave substitutes (Strahan 1995). Estimates of home ranges for this bat are in the order of 10km², which is a distance this species may travel from its roosting site during foraging periods (Hoye and Spence 2004). This species forages within habitats that include well timbered woodlands and open grasslands (Churchill 1998). Large distances, usually to 300km, are travelled between different roosts within a population's specific territory according to seasonal requirements (Churchill 1998). During winter, cold roosts are sought to allow for hibernation (Strahan 1995). Annually, discrete populations of females will travel great distances (up to 300km) to a nursery cave where the temperature, humidity and physical dimensions permit breeding and rearing of young (Churchill 1998). Nursery caves may support up to 150,000 females and juveniles and these may be used by a number of groups year after year (Reardon and Flavel 1987). After leaving maternity roosts, juvenile bats disperse into roosts only utilised by juvenile bats, before moving to adult roosts after one year (Hoye and Spence 2004). This species dependence on suitable seasonal caves has placed the Eastern Bentwing Bat in jeopardy (Strahan 1995).

Based on the information provided, and the results of the habitat assessments (during which time no suitable caves or cave substitutes were observed) it is not considered that the Eastern Bentwing Bat would significantly rely upon the study area such that the Proposal would have a significant impact on this species. Although this is the case, to further consider the impacts of the Proposal on this species, an eight part test has been undertaken (Section 7.2.8).

# 6.2.9. Gang-gang Cockatoo (Callocephalon fimbriatum).

The Gang-gang Cockatoo is distributed from southern Victoria through to south and central eastern NSW (Shields and Crome 1992). During summer, the Gang-gang Cockatoo prefers the higher altitude tall montane forests and woodlands, particularly in heavily timbered and mature wet sclerophyll forests (Frith 1997). In winter, the Gang-gang Cockatoo occurs at lower altitudes in drier, more open eucalypt forests and woodlands, particularly in box-ironbark assemblages, or in dry forest in coastal areas (Shields and Crome 1992). This species has also been observed within urban areas including gardens and parklands (Morcombe 1986). During breeding, the Gang-gang Cockatoo utilises tree hollows that are located within the trunks or limbs of large trees (Gibbons 1999, Gibbons and Lindenmayer 2000). Nests are most commonly found within large live eucalypt trees, close to water (Beruldsen 1980). Breeding occurs between October and January (Frith 1977). The primary food source of this Cockatoo includes fruits of native shrubs and trees, although they have been known to take fruits off exotic trees (Frith 1977). The main threat to their survival is habitat destruction, with the alteration of fire regimes contributing to this threat (NSW Scientific Committee 2005).

The Gang-gang Cockatoo is being considered for listing under the TSC Act due to a dramatic decline in this species' numbers as a result of unknown causes (NSW Scientific Committee 2005).

The Gang-gang Cockatoo was only recorded down slope of Jenolan Caves Road, though it is likely that it could forage within the study area on occasion. No evidence of any occupation of those hollow bearing trees present was obtained during the field investigation, though there is the potential that this species could use several of these on occasion (though the lack of proximity to water would reduce their suitability). Whilst this is the case, the loss of one or two hollow bearing trees, compared to the extent of similar resources in the surrounding region, is not considered to present a significant impact to the occurrence of the Gang-gang Cockatoo. As the hollow bearing trees were mainly recorded above cut slope 3.64, within the area proposed for the access track and works site, it is expected that, given the density of hollow bearing trees at this location, an alignment / works area can be selected that minimises the number of hollow bearing trees requiring removal. Whilst the Proposal is not considered to have a significant impact on this species, its populations or habitats, to further consider the impacts of the slope remediations on the Gang-gang Cockatoo, an eight part test has been undertaken (Section 7.2.11).

# 6.3. Fauna species of conservation significance previously recorded in the study region.

Based on the consultation of the DEH and DEC databases, and previous studies that are relevant to this region, 21 terrestrial fauna species listed under the TSC and EPBC Acts are known, or have the potential to be present, within this part of the Oberon Local Government Area (Appendix 3). Though targeted, none of these threatened species were observed or indicated as occurring within the study area. Within the area surveyed, no habitats important to the roosting or breeding requirements of any of the species listed in Appendix 3 were observed. Although there are some hollow-bearing trees located within, and in close proximity to, the access track, proposed work site and several of the cut slopes, it is not considered that the loss of several of these would present a significant effect to the occurrence of any of the hollow dependant fauna. The study area may provide some foraging resources for some of the animals listed in Appendix 3, however since the Proposal would only remove a maximum of 6.15ha (which is minimal compared to 350,106ha of surrounding conserved vegetation), it is not considered that the works would have a significant impact on the local or regional occurrence of any of these species. Post-development, it is considered that those state and national listed threatened species known or potentially occurring within the study area would still be able to traverse across and forage within the study area.

## 7. Ecological assessments.

## 7.1 Commonwealth Environment Protection and Biodiversity Conservation Act 1999.

#### 7.1.1 Flora considerations.

By the completion of the field investigations, no plants listed under the Schedules to the EPBC Act had been recorded within, or in the vicinity of, the proposed works. Similarly, no nationally listed Endangered Ecological Communities or populations are listed as occurring, or were recorded in the study area. The works would not have a detrimental impact on any species of national conservation significance and therefore it is not considered that the matter requires referral to the Federal Minister for the Environment for further consideration and approval in regards to botanical matters of national environmental significance.

#### 7.1.2 Fauna considerations.

By the completion of the field surveys, two species, the Satin Flycatcher Myiagra cyanoleuca and Largeeared Pied Bat Chalinolobus dwyeri, listed under the EPBC Act had been recorded. Within the study area suitable foraging and nesting habitat exists for the Satin Flycatcher, whilst the Large-eared Pied Bat is only expected to be foraging through the area (due to a lack of any suitable roosting and breeding sites). Based on a consideration of the EPBC Act's Administrative Guidelines on Significance for a migratory and vulnerable species, it is not considered that the Proposal would:

- substantially modify (including by fragmenting, altering fire regimes, altering nutrient cycles or altering hydrological cycles), destroy or isolate an area of important habitat for the Satin Flycatcher;
- result in invasive species that are harmful to the Satin Flycatcher becoming established in an area of important habitat for this migratory species;
- seriously disrupt the lifecycle (breeding, feeding, migration or resting behaviour) of an ecologically significant proportion of the Satin Flycatcher's population;
- lead to a long-term decrease in the size of an important population of the Large-eared
   Pied Bar:
- reduce the area of occupancy of an important population of the Large-eared Pied Bat;
- fragment an existing important Large-eared Pied Bat population into two or more populations;
- adversely affect habitat critical to the survival of the Large-eared Pied Bat;
- disrupt the breeding cycle of an important Large-eared Pied Bat population;
- modify, destroy, remove or isolate or decrease the availability or quality of habitat to the extent that the Large-eared Pied Bat is likely to decline;
- result in invasive species that are harmful to the Large-eared Pied Bat becoming established; or
- interfere substantially with the recovery of the Large-eared Pied Bat.

"Land clearance" has been listed as a threatening process under the EPBC Act. The Proposal would include the clearance of a total of 6.15ha of native vegetation. Based on the findings of the field investigations, habitat assessments and literature review process, it is not considered that the Proposal would:

- cause a native species or an ecological community to become eligible for listing as extinct, extinct in the wild, critically endangered, endangered or vulnerable;
- cause a native species or an ecological community to become eligible to be listed in another category representing a higher degree of endangerment; or
- adversely affect 2 or more listed threatened species or 2 or more listed threatened ecological communities.

Therefore, giving consideration to the obligations and objectives of the EPBC Act, it is not considered that the Proposal would require referral to the Federal Minister for the Environment for further consideration or approval in relation to fauna matters of national environmental significance.

# 7.2. State Environmental Planning and Assessment Act 1979.

## 7.2.1 Flora assessment.

No plant species, Endangered Ecological Communities or populations listed under the Schedules of the *TSC Act* were recorded or indicated as occurring within the study area. The vegetation communities present within the study area are not unique to this location, these occurring within the surrounding bushland areas, including the large adjacent conservation reserves of the Blue Mountains and Kanangra-Boyd National Parks and the Jenolan Karst Conservation Reserve.

Although no species, populations or ecological communities listed on the Schedules to the TSC Act were recorded within the study area, based on a precautionary approach, a generic eight part test has been completed below.

# 7.2.2 Eight part test - Flora.

(a) "...in the case of a threatened species, whether the life cycle of the species is likely to be disrupted such that a viable local population of the species is likely to be placed at risk of extinction..."

The habitats present within the study area are not considered critical for the life cycle needs of any plant species of conservation significance that could potentially occur in the area, based on the habitat types present. No threatened species were located during the field surveys and the activities associated with the Proposal would not result in the removal of any individuals of threatened species, or any habitat that are important for the survival of any potentially occurring threatened plants. This is due to the lack of suitable habitat, the very small area potentially affected by the Proposal and the absence of any threatened species within, and adjacent to, the study areas.

(b) "...whether the life cycle of the species that constitutes the endangered population is likely to be disrupted such that the viability of the population is likely to be significantly compromised..."

There are no listed endangered populations in the study area or within the sphere of influence of the proposed works.

(c) "...in relation to the regional distribution of the habitat of a threatened species, population or ecological community, whether a significant area of known habitat is to be modified or removed..."

The habitat that would be removed to permit the undertaking of the works is not considered to be significant for any of those threatened species that are known to occur in the region. The further disturbance of the habitat present would not have an impact on, or compromise the viability of, any of those threatened plants potentially occurring in either the locality or surrounding region. No threatened populations or Endangered Ecological Communities occur at within the study area and none are listed as occurring in the surrounding district.

(d) "...whether an area of known habitat is likely to become isolated from currently interconnecting or proximate areas of habitat for a threatened species, population or ecological community..."

Jenolan Caves Road currently forms a minor barrier to plant interbreeding and the minor widening of the existing road pavement by 2 to 3m would not change the existing situation in terms of connectivity or cross-pollination potential.

(e) "...whether critical habitat will be affected..."

No part of the study area is listed as critical habitat under Part 3 Division 1 of the TSC Act. There is no critical habitat within the sphere of influence of the Proposal.

(f) "...whether a threatened species, population or ecological community, or their habitats, are adequately represented in conservation reserves (or other similar protected areas) in the region..."

No threatened species, ecological communities or populations occur in the study area. All of the species and ecological communities recorded within the study area are common throughout the Jenolan Karst Conservation Reserve and Kanangra-Boyd National Park.

(g) "...whether the development or activity proposed is of a class of development or activity that is recognised as a threatening process..."

'Loss of biodiversity as a result of loss and/or degradation of habitat following clearing and fragmentation of native vegetation' is a Key Threatening Process on Schedule 3 of the TSC Act. However, the current proposal would not result in the further clearance of any significant or

extensive existing native vegetation stands and would not result in the significant loss or degradation of native habitat, or the loss of biodiversity from the locality or the region.

(h) "...whether any threatened species, populations or ecological community is at the limit of its known distribution..."

No threatened species, ecological communities or populations occur in the study area.

#### 7.2.3. Flora conclusion.

The minor widening of Jenolan Caves Road along Binoomea Ridge Hill at the sites surveyed would not affect any threatened species, ecological communities or populations listed on the Schedules to the TSC Act. The preparation of a Species Impact Statement that further considers the Proposal in relation to its impact on threatened plants, is therefore not considered necessary.

#### 7.2.4. Fauna assessment.

The potential impacts associated with the Proposal on the Powerful Owl Ninox strenua, Sooty Owl Tyto tenebricosa, Yellow-bellied Glider Petaurus australis, Large-eared Pied Bat Chalinolobus dwyeri, Eastern False Pipistrelle Falsistrellus tasmaniensis, Large-footed Myotis Myotis adversus and Eastern Bentwing Bat Miniopterus schreibersii are considered using the eight part test as provided under Section 5A of the Environmental Planning and Assessment Act 1979. These criteria are designed to determine "whether there is likely to be a significant effect on these threatened species, their populations, ecological communities, or habitats", and consequently whether a Species Impact Statement is required.

In accordance with the NPWS's information circular on the eight part test (NPWS 1996), due to the similarity in the habitat requirements of the Large-eared Pied Bat *Chalinolobus dwyeri* and Eastern Bentwing Bat *Miniopterus schreibersii* (i.e. both are cave roosting and woodland foraging species) these species have been grouped together when undertaking the Section 5A assessment.

It is noted that the Gang-gang Cockatoo Callocephalon fimbriatumare is currently being considered for listing under the TSC Act. Given that a favourable decision is expected to be made in regards to the listing of this species prior to the commencement of the Proposal an eight part test for this bird has also been prepared.

## 7.2.5. (a) Eight part test - Powerful Owl.

(a) "...in the case of a threatened species, whether the life cycle of the species is likely to be disrupted such that a viable local population of the species is likely to be placed at risk of extinction..."

During the field investigations no evidence was obtained that would indicate that the Powerful Owl was roosting or breeding within the any of the cut slopes. When detected through use of call playbacks, the Powerful Owl was only heard down slope of Jenolan Caves Road, no individuals being detected within any of the cut slope sites. Whilst this species is expected to forage over the study area, the removal of a maximum 6.15ha of native vegetation is not considered to reduce the extent of foraging resources available to the Powerful Owl's prey species. All of the Powerful Owl's prey species were recorded beyond the limits of the proposed remediation sites, in association with the better developed woodlands, particularly those areas that support hollow bearing trees. In relation to the proposed access track and works site that are to be located on top of cut slope 3.64, whilst these may require the removal of several hollow bearing trees, the loss of these in regards to the breeding needs of the Powerful Owl is not considered to be significant, particular given the extent of similar resources that occur within the study region. As such, the Proposal is not considered to significantly disrupt the life cycle of the locally occurring Powerful Owl population such that it is placed at risk of extinction.

(b) "...whether the life cycle of the species that constitutes the endangered population is likely to be disrupted such that the viability of the population is likely to be significantly compromised..."

An 'endangered population' is defined as a "population specified in Part 2 of Schedule 1" of the TSC Act. Therefore the Powerful Owl is not an endangered population.

(c) "...in relation to the regional distribution of the habitat of a threatened species, population or ecological community, whether a significant area of known habitat is to be modified or removed..."

The study area is not considered to constitute a significant regional area of known habitat for the Powerful Owl. Within the study area, no significant Powerful Owl breeding, roosting or foraging sites were observed. The study area may provide a small portion of this species foraging resources however, given that only a maximum of 6.15ha of vegetation would be modified, it is not considered that this represents a significant area of this species regional habitat.

(d) "...whether an area of known habitat is likely to become isolated from currently interconnecting or proximate areas of habitat for a threatened species, population or ecological community..."

The Powerful Owl is a highly mobile species, one that is known to easily negotiate open spaces (including the existing Jenolan Caves Road). As such, the Proposal would not present any new barriers to the movement patterns of this species. Therefore, no areas of habitat known or expected to be used by this species would be isolated or further fragmented.

(e) "...whether critical habitat will be affected..."

No critical habitat will be adversely affected by the Proposal. The study area is not listed as critical habitat under Part 3 Division I of the TSC Act.

(f) "...whether a threatened species, population or ecological community, or their habitats, are adequately represented in conservation reserves (or other similar protected areas) in the region..."

The Powerful Owl is known to occur within the adjacent Kanangra-Boyd National Park (DEC 2005), though whether it is adequately represented in this area is unknown. Although this is the case, the undertaking of the Proposal is not considered to threaten the presence of any Powerful Owl individuals, populations or their necessary habitats.

(g) "...whether the development or activity proposed is of a class of development or activity that is recognised as a threatening process..."

Currently 21 Key Threatening Processes for mainland NSW are listed under Schedule 3 of the *TSC* Act. Of these, "clearing of native vegetation" is applicable to the Proposal. The Proposal would result in the clearance of a maximum of 6.15ha of native vegetation, this, when compared to the surrounding 350,106ha, not considered to present a significant loss. As such, it is not considered that the Proposal would constitute a Key Threatening Process such that the life cycle requirements of this species would be significantly compromised.

(h) "...whether any threatened species, populations or ecological community is at the limit of its known distribution..."

The Powerful Owl does not reach the limits of its known distribution range in the vicinity of the study area.

# 7.2.5. (b) Expected impact on the Powerful Owl.

The undertaking of the Proposal would not disturb, remove, modify or fragment any habitats critical to the life cycle requirements of the Powerful Owl. No habitats were observed within the area of possible impact (including both direct and indirect impacts) that would be considered significant for the conservation and preservation of this species. Due to the small scale of the likely works and the extent of similar bushland in the surrounding region, no Powerful Owl dispersal or movement corridors would be disturbed, and no significant areas of local or regional habitat would be removed or isolated. During the field survey, no roosting populations of this species, or their necessary habitat areas, were recorded within the study area. As such, no locally viable populations of this animal are considered to occur. Therefore, the expected impacts associated with the Proposal on the Powerful Owl are considered to be minimal, and therefore, the preparation of a Species Impact Statement is not recommended.

# 7.2.6. (a) Eight part test - Sooty Owl.

(a) "...in the case of a threatened species, whether the life cycle of the species is likely to be disrupted such that a viable local population of the species is likely to be placed at risk of extinction..."

During the field investigations no evidence was obtained that would indicate that the Sooty Owl was roosting or breeding within the any of the cut slopes. When detected through use of call playbacks, the Sooty Owl was only heard down slope of Jenolan Caves Road, no individuals being detected within any of the cut slope sites themselves. Whilst this species is expected to forage over the study area, the removal of a maximum 6.15ha of native vegetation is not considered to reduce the extent of foraging resources available to the Sooty Owl's prey species. All of the Sooty Owl's prey species were recorded beyond the limits of the proposed remediation sites, in association with the better developed woodlands, particularly those areas that support hollow bearing trees. In relation to the proposed access track and works site that are to be located on top of cut slope 3.64, whilst these may require the removal of several hollow bearing trees, the loss of these in regards to the breeding needs of the Sooty Owl is not considered to be significant, particular given the extent of similar resources that occur within the study region. As such, the Proposal is not considered to significantly disrupt the life cycle of the locally occurring Sooty Owl population such that it is places at risk of extinction.

(b) "...whether the life cycle of the species that constitutes the endangered population is likely to be disrupted such that the viability of the population is likely to be significantly compromised..."

An 'endangered population' is defined as a "population specified in Part 2 of Schedule 1" of the TSC Act. Therefore the Sooty Owl is not an endangered population.

(c) "...in relation to the regional distribution of the habitat of a threatened species, population or ecological community, whether a significant area of known habitat is to be modified or removed..."

The study area is not considered to constitute a significant area of regional habitat for the Sooty Owl. Within the study area, no significant breeding, roosting or foraging sites were observed. The study area may provide a small portion of this species foraging resources however, given that only a maximum of 6.15ha of vegetation would be modified, it is not considered that a significant area of known regional habitat will be removed.

(d) "...whether an area of known habitat is likely to become isolated from currently interconnecting or proximate areas of habitat for a threatened species, population or ecological community..."

The Sooty Owl is a highly mobile species known to easily negotiate open spaces (including the existing Jenolan Caves Road). As such, the proposed works would not present any new barriers to the movement patterns of this species. Therefore, no areas of habitat known to be used by this species will be isolated or further fragmented.

(e) "...whether critical habitat will be affected..."

No critical habitat will be adversely affected by the proposed development. The study area is not listed as critical habitat under Part 3 Division 1 of the TSC Act.

(f) "...whether a threatened species, population or ecological community, or their habitats, are adequately represented in conservation reserves (or other similar protected areas) in the region..."

The Sooty Owl is known to occur within Kanangra-Boyd National Park (DEC 2005), though whether it is adequately represented in this area is unknown. Although this is the case, the undertaking of the Proposal is not considered to threaten the presence of any Sooty Owl individuals, populations or their necessary habitat areas.

(g) "...whether the development or activity proposed is of a class of development or activity that is recognised as a threatening process..."

Of the 21 Key Threatening Processes listed for mainland NSW, "clearing of native vegetation" is applicable to the Proposal. The Proposal would result in the clearance of only a small portion of native vegetation (6.15ha in total), this, when compared to the surrounding 350,106ha, not considered to present a significant loss in relation to the life cycle requirements of the Sooty Owl. As such, it is not considered that the Proposal would constitute a Key Threatening Process such that the life cycle requirements of this species would be significantly compromised.

(h) "...whether any threatened species, populations or ecological community is at the limit of its known distribution..."

The Sooty Owl does not reach the limits of its known distribution range in the vicinity of the study area.

## 7.2.6. (b) Expected impact on the Sooty Owl.

The undertaking of the Proposal would not disturb, remove, modify or fragment any habitats critical to the life cycle requirements of the Sooty Owl. No habitats were observed within the area of possible impact (including both direct and indirect impacts) that would be considered significant for the conservation and preservation of this species. Due to the vast surrounding conservation reserves, no Sooty Owl dispersal or movement corridors would be disturbed, and no significant areas of local or regional habitat would be removed or isolated. During the field survey, no roosting populations of this species, or their necessary habitat areas, were recorded within the study area. As such, no locally viable populations of this animal are considered to occur. Therefore, the expected impacts associated with the Proposal on the Sooty Owl are considered to be minimal and therefore the preparation of a Species Impact Statement is not necessary.

# 7.2.7. (a) Eight part test - Yellow-bellied Glider.

(a) "...in the case of a threatened species, whether the life cycle of the species is likely to be disrupted such that a viable local population of the species is likely to be placed at risk of extinction..."

During the field survey, no individuals of the Yellow-bellied Glider were spot lite or heard calling from the study area, all records being made down slope of Jenolan Caves Road. Whilst this is the case, it is expected that this species would forage and possibly roost within, and upslope of, the study area on occasion. On the cut slopes themselves, no hollow bearing trees are present therefore no possible Yellow-bellied Glider roosting or breeding sites would be removed. In regards to the access track and works site, the loss of several hollow bearing trees from this area, in comparison with the surrounding extent of similar resources, is not considered to present a significant impact on the local viability of this species. In regards to this area, it is noted that no individuals were heard calling during

the dusk call identifications, as such, given the loyalty of this species to its roosting sites, no resident sheltering populations are considered to be present. Given the extent of better developed bushland within the surrounding region, the loss of only a small portion of native vegetation (a maximum of 6.15ha in total) is not considered to present a significant disruption to the life cycle requirements of this species. As such, the viability of the local Yellow-bellied Glider population is not considered to be compromised such that this species would be placed at risk of extinction.

(b) "...whether the life cycle of the species that constitutes the endangered population is likely to be disrupted such that the viability of the population is likely to be significantly compromised..."

An 'endangered population' is defined as a "population specified in Part 2 of Schedule 1" of the TSC Act. Therefore the Yellow-bellied Glider is not an endangered population.

(c) "...in relation to the regional distribution of the habitat of a threatened species, population or ecological community, whether a significant area of known habitat is to be modified or removed..."

Based on the results of the field investigation, the lack of any detections of this species within any of the cut slopes and the lack of any evidence that would indicate this species is foraging in these areas (i.e. no incised trees were observed), it is not considered that the study area would constitute a significant regional resource for this species. As such, no significant areas of regional habitat for the Yellow-bellied Glider would be removed or modified as a result of the undertaking of the Proposal.

(d) "...whether an area of known habitat is likely to become isolated from currently interconnecting or proximate areas of habitat for a threatened species, population or ecological community..."

The Proposal would not isolate any currently interconnecting or proximate areas of habitat suitable for use by the Yellow-bellied Glider. Due to the existing presence of Jenolan Caves Road and its associated series of exposed rock batters, the eucalypt woodlands are already considered to be "fragmented", the proposed works not considered to have an adverse cumulative impact when combined with the existing situation. As such the Proposal would not further isolate any areas of importance to the foraging or dispersal needs of this species. Given this, as well as the extent of the proposed works and the maintained connectivity of those corridors that occur beyond the limits of the proposed slope remediation sites, the Proposal would not present any new barriers to the movement patterns of this species. Therefore, no areas of habitat known or expected to be used by this species would be isolated or further fragmented.

(e) "...whether critical habitat will be affected..."

No critical habitat will be adversely affected by the proposed development. The study area is not listed as critical habitat under Part 3 Division I of the TSC Act.

(f) "...whether a threatened species, population or ecological community, or their habitats, are adequately represented in conservation reserves (or other similar protected areas) in the region..."

The Yellow-bellied Glider is known to occur within the adjacent national park, although whether it is adequately represented in this area is unknown. Although this is the case, the undertaking of the Proposal is not considered to threaten the presence of any Yellow-bellied Glider individuals, populations or their necessary habitat areas.

(g) "...whether the development or activity proposed is of a class of development or activity that is recognised as a threatening process..."

Twenty Key Threatening Processes for mainland NSW are listed under Schedule 3 of the TSC Act. Of these, "the clearing of native vegetation" is applicable to the Proposal. Whilst it is acknowledged that the Proposal would result in the clearing of some native vegetation (a maximum of 6.15ha in total) potentially available for the foraging and roosting needs of the Yellow-bellied Glider, taking into account the presence of around 350,106ha of similar bushland in the surrounding conservation reserve network, it is not considered that the clearing that would occur would result in a significant loss of any habitat for this species from the region. As such, it is not considered that the Proposal would constitute a significant Key Threatening Process such that the life cycle requirements of the Yellow-bellied Glider would be compromised.

(h) "...whether any threatened species, populations or ecological community is at the limit of its known distribution..."

The Yellow-bellied Glider does not reach the limits of its known distribution range in the vicinity of the study area.

# 7.2.7. (b) Expected impact on the Yellow-bellied Glider.

The undertaking of the Proposal would not disturb, remove, modify or fragment any habitats critical to the life cycle requirements of the Yellow-bellied Glider. Due to the small scale of the Proposal, and the presence of similar conserved bushland area in the surrounding region, no Yellow-bellied Glider dispersal or movement corridors would be disturbed, and no significant areas of local or regional habitat would be removed or isolated. Therefore, the expected impacts associated with the Proposal on the Yellow-bellied Glider are considered to be minimal, and therefore the preparation of a Species Impact Statement is not necessary.

# 7.2.8. (a) Eight-part test - Cave dependant microchiropterans (Large-eared Pied Bat and Eastern Bentwing Bat).

(a) "...in the case of a threatened species, whether the life cycle of the species is likely to be disrupted such that a viable local population of the species is likely to be placed at risk of extinction..."

The resources present within the study area are not considered to constitute a major component of the Large-eared Pied Bat or Eastern Bentwing Bat's roosting, breeding or foraging requirements. Within the study area, no natural or artificial caves suitable for the roosting requirements of either of these species were observed. Neither the Large-eared Pied Bat nor the Eastern Bentwing Bat are considered to be solely dependant upon those resources present in the study area such that the undertaking of the Proposal would significantly affect the viability of a local population of either of these microchiropterans.

(b) "...whether the life cycle of the species that constitutes the endangered population is likely to be disrupted such that the viability of the population is likely to be significantly compromised..."

An 'endangered population' is defined as a "population specified in Part 2 of Schedule 1" of the TSC Act. Therefore the Large-eared Pied Bat and Eastern Bentwing Bat are not an endangered population.

(c) "...in relation to the regional distribution of the habitat of a threatened species, population or ecological community, whether a significant area of known habitat is to be modified or removed..."

The study area is not considered to constitute a significant regional area of known habitat for either of the cave dependant microchiropterans that were recorded during the field survey. There were no suitable caves observed within the study area, which is an essential habitat feature for the roosting

requirements of these species. The study area itself may provide some foraging resources for these species, however, the value of the vegetation proposed to be removed is minimal compared to the remaining areas of similar foraging resources (both adjacent to, and beyond the limits of, the study area). Therefore, the Proposal would not modify or remove a significant area of known regional habitat for either of the cave dependant microchiropterans.

(d) "...whether an area of known habitat is likely to become isolated from currently interconnecting or proximate areas of habitat for a threatened species, population or ecological community..."

The cave dependant microchiropterans are both known to easily negotiate urban infrastructure, including roads, open fields and developed areas (Hoye and Spence 2004). The study area is surrounded by 350,106ha of well conserved bushland. As such, the Proposal would not present a barrier to the movement patterns of these species such that their necessary habitat areas are likely to become isolated.

(e) "...whether critical habitat will be affected..."

No critical habitat would be adversely affected by the proposed development. The study area is not listed as critical habitat under Part 3 Division I of the TSC Act.

(f) "...whether a threatened species, population or ecological community, or their habitats, are adequately represented in conservation reserves (or other similar protected areas) in the region..."

Both of the cave dependant microchiropterans are known to be present within the Kanangra-Boyd National Park, including roosting populations within the nearby Jenolan Caves, though whether they are adequately represented in these areas is unknown. Although this is the case, the undertaking of the Proposal is not considered to threaten the presence of any cave dependant microchiropterans, their populations or necessary habitat areas.

(g) "...whether the development or activity proposed is of a class of development or activity that is recognised as a threatening process..."

Of the 21 Key Threatening Processes listed for mainland NSW "the clearing of native vegetation" is applicable to the Proposal. Whilst it is acknowledged that the Proposal would result in the clearing of some insect attracting native vegetation (this equating to a maximum of 6.15ha) potentially available for the foraging needs of the cave dependant microchiropterans, taking into account the presence of around 350,106ha of similar bushland in the surrounding conservation reserve network, it is not considered that this clearance would result in a significant loss of any habitat for these species from the region. As such, it is not considered that the Proposal would constitute a significant Key Threatening Process such that the life cycle requirements of any cave dependant microchiropterans would be compromised.

(h) "...whether any threatened species, populations or ecological community is at the limit of its known distribution..."

Neither of the cave dependant microchiropterans reach the limits of their known distributions in the vicinity of the study area.

## 7.2.8. (b) Expected impact on cave dependant microchiropterans.

The undertaking of the Proposal would not disturb, remove, modify or fragment any habitats critical to the life cycle requirements of either of the cave dependant microchiropterans recorded during the field investigation. No habitats were observed within the area of possible impact (including both direct and indirect impacts) that would be considered significant for the conservation and preservation of

these species. Due to the extent of similar woodland in the surrounding conservation reserves, no microchiropteran dispersal or movement corridors would be disturbed, and no significant areas of local or regional habitat would be removed or isolated. During the field survey, no roosting sites suitable for the needs of these species were recorded within the study area, and therefore no locally viable populations of these animals are considered to occur. Therefore, the expected impacts associated with the Proposal on the cave dependant microchiropterans is considered to be minimal, and therefore, the preparation of a Species Impact Statement for these species is not necessary.

# 7.2.9. (a) Eight-part test - Eastern False Pipistrelle.

(a) "...in the case of a threatened species, whether the life cycle of the species is likely to be disrupted such that a viable local population of the species is likely to be placed at risk of extinction..."

The resources present within the study area are not considered to constitute a major component of the Eastern False Pipistrelle's roosting, foraging or breeding requirements. During the field survey, no caves or suitable sheltering sites (tree hollows) were observed on any of the cut slopes, the only possible roosting/breeding sites being recorded above cut slope 3.64. At this location, the establishment of the proposed access track and works compound is expected to result in the removal of several hollow bearing trees, though the number is expected to be minimised through appropriate design. The loss of several hollow bearing trees when compared to the extent of similar resources adjacent to and beyond the limits of the study area is not considered to adversely affect the local viability of a population of the Eastern False Pipistrelle, such that it is placed at risk of extinction.

(b) "...whether the life cycle of the species that constitutes the endangered population is likely to be disrupted such that the viability of the population is likely to be significantly compromised..."

An 'endangered population' is defined as a "population specified in Part 2 of Schedule 1" of the TSC Act. Therefore the Eastern False Pipistrelle is not an endangered population.

(c) "...in relation to the regional distribution of the habitat of a threatened species, population or ecological community, whether a significant area of known habitat is to be modified or removed..."

The study area is not considered to constitute a significant regional area of known habitat for the Eastern False Pipistrelle. Within the study area, no significant roosting or foraging areas are present, the resources present being continuous with those that occur beyond the limits of the likely works area. On occasion, the Eastern False Pipistrelle may forage over and through the study area however the clearing that would occur would only result in the removal of 6.15ha of possibly insect attracting plants from the surrounding 350,106ha of similar bushland. Therefore, the Proposal would not modify or remove a significant area of known regional habitat that is currently important to the presence of the Eastern False Pipistrelle.

(d) "...whether an area of known habitat is likely to become isolated from currently interconnecting or proximate areas of habitat for a threatened species, population or ecological community..."

Proposal would not present a barrier to the movement patterns of the Eastern False Pipistrelle such that its necessary habitat areas are likely to become isolated.

(e) "...whether critical habitat will be affected..."

No critical habitat would be adversely affected by the Proposal. The study area is not listed as critical habitat under Part 3 Division 1 of the TSC Act.

(f) "...whether a threatened species, population or ecological community, or their habitats, are adequately represented in conservation reserves (or other similar protected areas) in the region..."

The Eastern False Pipistrelle is known to be present within the Kanangra-Boyd National Park, and has been found in Jenolan Caves, though whether it is adequately represented in these areas is unknown. Although this is the case, the undertaking of the Proposal is not considered to threaten the presence of any Eastern False Pipistrelle individuals, populations or their necessary habitats.

(g) "...whether the development or activity proposed is of a class of development or activity that is recognised as a threatening process..."

Of the 21 Key Threatening Processes listed for mainland NSW, "clearing of native vegetation" is applicable to the Proposal. The Proposal would result in the clearance of only a small portion of native vegetation (6.15ha), this, when compared to the surrounding 350,106ha, not considered to present a significant loss in relation to the life cycle requirements of the Eastern False Pipistrelle. As such, it is not considered that the Proposal would constitute a Key Threatening Process such that the life cycle requirements of this species would be significantly compromised.

(h) "...whether any threatened species, populations or ecological community is at the limit of its known distribution..."

The Eastern False Pipistrelle does not reach the limits of its known distribution range in the vicinity of the study area.

# 7.2.9. (b) Expected impact on the Eastern False Pipistrelle.

The undertaking of the Proposal would not disturb, remove, modify or fragment any habitats critical to the life cycle requirements of the Eastern False Pipistrelle. No habitats were observed within the area of possible impact (including both direct and indirect impacts) that would be considered significant for the conservation and preservation of this species. Due to the extent of similar woodland in the surrounding conservation reserves, no Eastern False Pipistrelle dispersal or movement corridors would be disturbed, and no significant areas of local or regional habitat would be removed or isolated. As such, no locally viable populations of this animal are considered to occur. The expected impacts associated with the Proposal on the Eastern False Pipistrelle are therefore considered to be minimal. As such, the preparation of a Species Impact Statement is not necessary.

# 7.2.10. (a) Eight part test - Large-footed Myotis.

(a) "...in the case of a threatened species, whether the life cycle of the species is likely to be disrupted such that a viable local population of the species is likely to be placed at risk of extinction..."

No resources are present within the study area that would be suitable for the Large-footed Myotis' roosting, breeding or foraging requirements. As such, no impacts would arise that would disrupt the local viability of this species. Therefore, the undertaking of the Proposal is not considered to remove any resources important to the local viability of this species.

(b) "...whether the life cycle of the species that constitutes the endangered population is likely to be disrupted such that the viability of the population is likely to be significantly compromised..."

An 'endangered population' is defined as a "population specified in Part 2 of Schedule 1" of the TSC Act. Therefore the Large-footed Myotis is not an endangered population.

(c) "...in relation to the regional distribution of the habitat of a threatened species, population or ecological community, whether a significant area of known habitat is to be modified or removed..."

The study area is not considered to constitute a significant regional area of known habitat suitable for the Large-footed Myotis. Within the study area, no suitable roosting, foraging or breeding sites are present. Therefore, the Proposal would not modify or remove a significant area of known regional habitat that is important to the occurrence of the Large-footed Myotis.

(d) "...whether an area of known habitat is likely to become isolated from currently interconnecting or proximate areas of habitat for a threatened species, population or ecological community..."

The proposed works would not present a barrier to the movement patterns of the Large-footed Myotis such that its necessary habitat areas are likely to become isolated. This species is known to easily negotiate open space areas (e.g. open expanses of water), therefore no impacts to the dispersal or movement patterns of this species are expected to arise.

(e) "...whether critical habitat will be affected..."

No critical habitat would be adversely affected by the proposed development. The study area is not listed as critical habitat under Part 3 Division 1 of the TSC Act.

(f) "...whether a threatened species, population or ecological community, or their habitats, are adequately represented in conservation reserves (or other similar protected areas) in the region..."

The Large-footed Myotis is known to be present within the Kanangra-Boyd National Park though whether it is adequately represented in this area is unknown. Although this is the case, the undertaking of the Proposal is not considered to threaten the presence of any Large-footed Myotis individuals, populations or their necessary habitat areas.

(g) "...whether the development or activity proposed is of a class of development or activity that is recognised as a threatening process..."

The activities likely to be undertaken during the proposed remediation works would not have an adverse impact on any resources important to the Large-footed Myotis. The works would not threaten any Myotis foraging, roosting or breeding site. As such, the Proposal is not considered to constitute a Key Threatening Process such that the life cycle requirements of this species would be significantly compromised.

(h) "...whether any threatened species, populations or ecological community is at the limit of its known distribution..."

The Large-footed Myotis does not reach the limits of its known distribution range in the vicinity of the study area.

# 7.2.10. (b) Expected impact on the Large-footed Myotis.

The undertaking of the Proposal would not disturb, remove, modify or fragment any habitats suitable for the life cycle requirements of the Large-footed Myotis. No habitats were observed within the area of possible impact (including both direct and indirect impacts) that would be considered significant for the occurrence of this species. As such, no locally viable populations of this animal are considered to occur and therefore none would be significantly affected. The expected impacts associated with the Proposal on the Large-footed Myotis are considered to be minimal, and therefore, the preparation of a Species Impact Statement is not necessary.

# 7.2.11. (a) Eight part test - Gang-gang Cockatoo.

(a) "...in the case of a threatened species, whether the life cycle of the species is likely to be disrupted such that a viable local population of the species is likely to be placed at risk of extinction..."

During the field survey, no individuals of the Gang-gang Cockatoo were observed or heard calling from the study area, all records being made down slope of Jenolan Caves Road. Whilst this is the case, it is expected that this species would forage and possibly roost within, and upslope of, the study area on occasion. On the cut slopes themselves, no hollow bearing trees are present therefore no possible roosting and breeding sites would be removed. In regards to the access track and works site, the loss of several hollow bearing trees from this area, in comparison with the surrounding extent of similar resources, is not considered to present a significant affect on the local viability of this species. Given the extent of better developed bushland within the surrounding region, the loss of only a small portion of native vegetation (this equating to a maximum of 6.15ha) is not considered to present a significant disruption to the life cycle requirements of this species. As such, the viability of the local Gang-gang population is not expected to be placed at risk of extinction.

(b) "...whether the life cycle of the species that constitutes the endangered population is likely to be disrupted such that the viability of the population is likely to be significantly compromised..."

An 'endangered population' is defined as a "population specified in Part 2 of Schedule 1" of the TSC Act. Therefore the Gang-gang Cockatoo is not an endangered population.

(c) "...in relation to the regional distribution of the habitat of a threatened species, population or ecological community, whether a significant area of known habitat is to be modified or removed..."

The habitats within the study area extend well beyond the boundaries of the Proposal into the surrounding national park, this covering an area of 350,106ha. At a regional level, the habitats present within the study area are not considered to constitute a significant area in relation to the regional requirements of the Gang-gang Cockatoo.

(d) "...whether an area of known habitat is likely to become isolated from currently interconnecting or proximate areas of habitat for a threatened species, population or ecological community..."

This species is highly mobile and can traverse open spaces and as such the Proposal would not isolate any currently interconnecting or proximate areas of habitat suitable for use by the Gang-gang Cockatoo.

(e) "...whether critical habitat will be affected..."

No critical habitat would be adversely affected by the proposed development. The study area is not listed as critical habitat under Part 3 Division 1 of the TSC Act.

(f) "...whether a threatened species, population or ecological community, or their habitats, are adequately represented in conservation reserves (or other similar protected areas) in the region..."

The Gang-gang Cockatoo has been recorded within various conservation reserves throughout its distribution (DEC 2005) though whether it is adequately represented in these areas is unknown. Although this is the case, it is not expected that the Proposal would compromise the viability of a resident population of this species.

(g) "...whether the development or activity proposed is of a class of development or activity that is recognised as a threatening process..."

Of the 21 listed Key Threatening Processes, "clearing of native vegetation" is applicable to the Proposal. The Proposal would result in the clearance of only a small portion of native vegetation (this equating to a maximum of 6.15ha), this not considered a significant loss in comparison to the remaining 350,106ha. As such, it is not considered that the Proposal would constitute a Key Threatening Process such that the life cycle requirements of this species would be significantly compromised.

(h) "...whether any threatened species, populations or ecological community is at the limit of its known distribution..."

The Gang-gang Cockatoo does not reach the limits of its known distribution range in the vicinity of the study area.

# 7.2.11. (b) Expected impact on the Gang-gang Cockatoo.

The Proposal is not considered to have a significant impact on the local status of the Gang-gang Cockatoo. The works would not remove any significant portions of this species roosting or breeding sites and no major foraging areas would be significantly affected. The works would not present a barrier to the dispersing or movement patterns of this species, the Gang-gang Cockatoo known to easily negotiating open space and rocky areas. Therefore it is not considered that the Proposal would have a significant impact on this threatened species, its population, ecological community or habitats. Therefore, the preparation of a Species Impact Statement which further considers the impacts of the works on this species is not required.

# 7.3 State - State Environmental Planning Policy No. 44 (SEPP 44) - Koala Habitat Protection.

The Oberon Local Government Area is identified under Schedule I – Local Government Areas of SEPP 44 – Koala Habitat Protection. This Policy seeks to encourage the proper conservation and management of areas that provide habitat for Koalas.

Six eucalypts were recorded during the botanical surveys, these being, Eucalyptus bicostata, E.dalrympleana, E. blaxlandii, E. eugenoides, E. viminalis and E. fastigata. Of these, E.viminalis is a listed Koala feed tree under Schedule 2 of SEPP 44. Within the study area, E.viminalis constitutes greater than 15% of the total tree canopy and therefore, based on the criteria provided under SEPP 44, the study area is considered to constitute potential Koala habitat. Although this is the case, during the field surveys no individuals of this animal were spot lite or observed, none were heard calling during the nocturnal surveys and no characteristic scratching or scats were found. As such, the study area is not considered to be core Koala habitat. Given the limited extent of the works proposed, the known ability for Koalas to traverse open ground, combined with the amount of bushland present both adjacent to and beyond the limits of the study area it is not considered that the Proposal would have a significant impact on any Koala individuals, their populations or habitat. Therefore a Plan of Management for the conservation and management of areas of Koala habitat is not required to be prepared as part of the current Proposal.

#### 8. Conclusions.

Based on the results of the flora and fauna surveys, combined with a review of known literature and database sources, it is not considered that there are any ecological constraints to the proposed stabilisation of several of the cut slopes that occur adjacent to Jenolan Caves Road proceeding as planned. The Proposal would not significantly affect any populations of any native plants or animals such that they are placed at risk of extinction. Similarly the works would not remove or significantly affect any habitats of local, regional, state or national conservation concern.

No regionally significant, state or nationally listed plants or ecological communities were recorded within the study area. As such, no plants or vegetation communities of conservation concern would be adversely affected as a result of the undertaking of the Proposal.

The proposed works are not considered to affect, threaten or have an adverse impact on any of those plants or animals listed under the Commonwealth Environment Protection and Biodiversity Conservation Act 1999 (including the migratory Satin Flycatcher Myiagra cyanoleuca and vulnerably listed Large-eared Pied Bat Chalinolobus dwyeri that were recorded during the field survey). Therefore, it is not considered that the matter would require referral to the Federal Minister for the Environment for further consideration or approval.

Within the areas of likely disturbance, the habitats and vegetation communities present are considered to be of limited value for those species recorded or expected. The proposed works sites are all very small, none providing any significant areas of foraging, sheltering, roosting or breeding habitat. The proposed works would therefore not result in any threatened plants or animals (including the seven threatened animals recorded during the survey), their populations, ecological communities or habitats being significantly impacted upon such that a viable population of that species is placed at risk of extinction. Similarly, the works would not fragment, disturb or alter any of these species movement, dispersal or pollination vector corridors, or isolate any proximate areas of suitable habitat. Therefore, giving consideration to the assessment criteria listed under Section 5A of the NSW Environmental Planning and Assessment Act 1979, the preparation of a Species Impact Statement for any threatened plants or animals would not be required.

The Proposal would not have an adverse impact on the local or regional viability of the Gang-gang Cockatoo Callocephalon fimbriatum, a bird that has been Preliminary listed for inclusion under the TSC Act. Based on a consideration of the habitat requirements of this species, combined with the results obtained during the field survey, it is not considered that the proposed remediation works would have a significant effect on this species, its populations or habitats. As such, the preparation of a Species Impact Statement that further considers the impact of the Proposal on this species is not required.

Whilst meeting the criteria of potential Koala habitat as provided under SEPP 44, the study area is not considered to be core Koala habitat. Therefore, giving consideration to the objectives of SEPP 44, it is not considered that the proposed remediation works would require the preparation of a Plan of Management for Koalas, or the adoption of any other appropriate mitigative measures.

## 9. Recommendations.

The following recommendations are provided to ensure that the Proposal does not have an adverse impact on those habitats that occur beyond the limits of the works. The recommendations are also provided to ensure that the works are undertaken in an ecologically sustainable manner:

- All areas that occur beyond the limits of the proposed works should be clearly defined on site to
  ensure they are not disturbed. These areas should be highlighted on any plans provided to the
  RTA's woks contractors to ensure no adjacent habitats are adversely affected.
- The sighting of the access track and works site should be such that it minimise the number of hollow bearing trees requiring removal from atop of cut slope 3.64. Given the sparse distribution of mature hollow bearing trees at this site, a suitable alignment for each component of this works area could be selected that minimises the number of hollow bearing trees requiring removal.
- An erosion and sediment control plan should be prepared. This plan should include the stabilisation of exposed surfaces as soon as possible to reduce the potential for any erosion.
- The erosion and sedimentation control plan should ensure that no sediments leave the study area
  and that the works do not adversely affect the Jenolan River. The quality of this drainage line
  should not be reduced as a result of the Proposal.

- Cleared native vegetation should be mulched and used in the sites stabilisation works posttreatment.
- The Blackberry (Rubus ulmifolius) infestations recorded at cut slopes 4.22, 7.02, 7.58 and 8.13 should be treated. The treatment of this noxious weed should be undertaken in consultation with Upper Macquarie County Council.
- Weeds and seed bearing exotic plants that are removed should not be mulched but should be taken to an approved Council waste facility.
- If a chemical herbicide is used to aid in the removal of weed species, a product should be selected that will readily break down and not impact on any fauna species.
- Cleared and disturbed areas should be stabilised with suitable native grasses and ground cover plants as soon as possible to prevent soil erosion.

#### 10. Bibliography.

- Australian Heritage Commission (2005) Register of the National Estate. http://www.ahc.gov.au/register/. [Accessed January 2005].
- Bennett, A.F. (1993) Microhabitat use by the Long-nosed Potoroo, *Potorous tridactylus*, and other small mammals in remnant forest vegetation of South-western Victoria. *Wildlife Research*. 20(3), 267-285.
- Beruldsen, G. (2003) Australian birds, their nests and eggs. G. Beruldsen, Kenmore Hills, Queensland.
- Braithwaite, L.W. (1983) Studies on the arboreal marsupial fauna of eucalypt forests being harvested for woodpulp at Eden NSW I. The species and distribution of animals. *Australian Wildlife Research*. 10, 219-229.
- Briggs, J. and Leigh, J. (1996) Rare or Threatened Australian Plants. CSIRO Publishing, Collingwood, Victoria.
- Brooker, M.I.H. and Kleinig, D.A. (1999) Field guide to Eucalypts. South-eastern Australia Volume 1 Second Edition. Bloomings Books, Hawthorn, Victoria.
- Brouwer, J. and Garnett, S. (1990) Threatened Birds of Australia RAOU Report Number 68. Royal Australian Ornithologists Union, Victoria.
- Buckingham, R. and Jackson, L. (Eds) (1990) A field guide to Australian birdsongs, Cassette Numbers 5 and 6. Audio Cassette, Bird Observers Club Australia, Victoria.
- Bureau of Meteorology (2005) Bureau of Meteorology Climate Averages. http://www.bom.gov.au/climate/averages. [Accessed January 2005].
- Chafer, C.J. (1992) Observations of the Powerful Owl (Ninox strenua) in the Illawarra and Shoalhaven regions of New South Wales. Australian Bird Watcher. 14, 289-300.
- Churchill, S. (1998) Australian bats. Reed New Holland, Frenches Forest, NSW.
- Cogger, H. (1992) Reptiles and amphibians of Australia. Reed Books, Chatswood, NSW.
- Costermans, L. (1996) Native trees and shrubs of South-eastern Australia. Landsdowne Publishing, Sydney, NSW.
- Craig, S.A. (1985) Social organisation, reproduction and feeding behaviour of a population of Yellow-bellied Gliders, *Petaurus australis* (Marsupialia: Petauridae). *Australian Wildlife Research*. 12, 1-18.
- Cropper, S. (1993) Management of Endangered Plants. CSIRO, Melbourne, Victoria.
- Debus, S.J. and Chafer, C.J. (1994) The Powerful Owl in New South Wales. Australian Birds. 27.
- Department of Environment and Conservation (2005) Atlas of NSW Wildlife Database. http://wildlifeatlas.npws.gov.au [Accessed January 2005].
- Department of Environment and Heritage (2005a) The Greater Blue Mountains Area: Inscribed 2000. http://www.biodiversity.ea.gov.au/heritage/worldheritage/sites/blue/index.html [Accessed February 2005].
- Department of Environment and Heritage (2005b) Environment Protection and Biodiversity Conservation Act Online Database. http://www.environment.gov.au/epbc/db/index.html [Accessed January 2005].
- Ehmann, H. (1992) Encyclopaedia of Australian Animals Reptiles. Angus and Robertson. Pymble, NSW.

- Ehmann, E. (1997) Threatened frogs of New South Wales: Habitats, status and conservation. Frog and Tadpole Study Group, Sydney, NSW.
- Eldridge, M.D.B. and Close, R.L. (1995) Brush-tailed Rock-wallaby, in Strahan, R. (Ed.) The Mammals of Australia. Reed Books, Chatswood, NSW.
- Engel, D. and Fanning, F.D. (1995) A review of the Yellow-bellied Glider, proposed golf course extension, Pambula, Fauna Impact Statement. Report prepared by Gunninah Consultants, Crows Nest, NSW.
- Fairley, A. and Moore, P. (2000) Native plants of the Sydney District: an identification guide. Kangaroo Press, Kensington, NSW.
- Ford, H., Davies, W., Debus, S., Ley, A., Recher, H. and Williams, B. (1993) Foraging and aggressive behaviour of the Regent Honeyeater (*Xanthomyza phrygia*) in northern NSW. *EMU*. 93(4), 277-280.
- Frith, H.J. (Ed) (1997) Complete book of Australian birds. Readers Digest, Surry Hills, NSW.
- Garnett, S. (1992) The action plan for Australian birds Australian National Parks and Wildlife Service, Endangered Species Program. Project Number 121, Australian Museum.
- Garnett, S. (Ed) (1993) Threatened and Extinct Birds of Australia. RAOU Report Number 82, Royal Australian Ornithologists Union, Victoria.
- Gibbons, P. (1999) Habitat-tree retention in wood production forests. PhD thesis. Australian National University, Canberra, ACT.
- Gibbons, P. and Lindenmayer, D. (2000) Tree hollows and wildlife conservation in Australia. CSIRO Publishing, Canberra, ACT.
- Goldingay, R. (1989) The behavioural ecology of the gliding marsupial, <u>Petaurus australis</u>. Ph.D. Thesis, University of Wollongong, Wollongong, NSW.
- Goldingay, R. (1992) Socioecology of the Yellow-bellied Glider (<u>Petaurus australis</u>) in a coastal forest. Australian Journal of Zoology. 40, 267-278.
- Goldingay, R. and Kavanagh, R. (1991) The Yellow-bellied Glider: a review of its ecology, and management considerations in *Conservation of Australia's Forest Fauna* Chapter 31 Royal Zoological Society of New South Wales pp 365-375.
- Goldingay, R. and Kavanagh, R. (1993) Home-range estimates and habitat of the yellow-bellied glider (*Petaurus australis*) at Waratah Creek, New South Wales. *Australian Wildlife Research*. 20, 387-404.
- Goldingay, R., Quin, D. and Churchill, S. (2001) Spatial variability in the social organisation of the Yellow-bellied Glider near Ravenshoe, north Queensland. Australian Journal of Zoology. 49, 397-409.
- Hall, L.S. and Richards, G.C. (1979) Bats of Eastern Australia. Queensland Museum Booklet No 12.
- Harden, G. (Ed) (1992-2002) Flora of New South Wales Vols 1,2,3 and 4. NSW University Press, Kensington, NSW.
- Henry, S.R. and Craig, S.A. (1984) Diet, ranging behaviour and social organisation of the Yellowbellied Glider (*Petaurus australis* Shaw) in Victoria. Pp. 331-341 in A.P. Smith and I.D. Hume (Eds) *Possums and Gliders.* Australian Mammal Society, Sydney, NSW.
- Hollands, D. (1991) Birds of the Night. Reed Books, Chatswood, NSW.

- Hoye, G. and Spence, J. (2004) The Large Bent-wing Bat Miniopterus schreibersii in urban environments: a survivor? Pp 138-147 in D. Lunney and S. Bergin (Eds) Urban wildlife: more than meets the eye. Royal Zoological Society of New South Wales, Mosman, NSW.
- Keith D.A and Benson, D.H., (1988) The natural vegetation of the Katoomba 1:100,000 map sheet. Cunninghamia. 2(1).
- King, D.P. (1994) Soil Landscapes of the Katoomba 1:100 000 Sheet. (mount Tomah, Woodford, Jenolan Caves, Hampton). Department of Conservation and Land Management, Sydney, NSW.
- LandScope Environmental Consultants (1996) Flora and Fauna Assessment: Proposed widening of Jenolan Caves Road between Lithgow Road and Hampton Halfway House, and Duckmaloi Road between Oberon and Jenolan Caves Road. Report prepared for the Roads and Traffic Authority (Western Region) by LandScope Environmental Consultants, Bundeena, NSW.
- LandScope Environmental Consultants (1997) Review of Environmental Factors. Maintenance of a culvert under the Grand Arch at Jenolan Caves, NSW. Report prepared for the Roads and Traffic Authority (Western Region) by LandScope Environmental Consultants, Bundeena, NSW.
- LesryK Environmental Consultants (2004) Flora and fauna assessment of five sites that occur adjacent to Jenolan Caves Road, Jenolan Caves, NSW. Report prepared for the Roads and Traffic Authority by LesryK Environmental Consultants, Bundeena, NSW.
- Lendon, A.H. (1979) Australian Parrots in Field and Aviary. Angus and Robinson, Sydney, NSW.
- Lindenmayer, D. (2002) Gliders of Australia. University of NSW Press, Sydney, NSW.
- Manidis Roberts (2004) Jenolan Karst Conservation Reserve Draft Plan of Management Version 3- 27/2/04. Manidis Roberts, Sydney, NSW.
- McNabb, E.G. (1996) Observations on the Biology of the Powerful Owl Ninox strenua in Southern Victoria. The Australian Bird Watcher. 16(7), 267-295.
- Menkhorst, P.W. (Ed) (1995) Mammals of Victoria: Distribution, Ecology and Conservation. Oxford University Press, Melbourne, Victoria.
- Menkhorst, P.W. and Lumsden, L.F. (1996) Eastern False Pipistrelle. Menkhorst, P.W. (Ed) Mammals of Victoria: distribution, ecology and conservation. Oxford University Press, Melbourne, Victoria.
- Menkhorst, P.W., Weavers, B.W. and Alexander, J.S.A. (1988) Distribution, habitat and conservation status of the Squirrel Glider *Petaurus norfolcensis* (Petauridae: Marsupialia) in Victoria. *Australian Wildlife Research*. 15, 59-72.
- Menkhorst, P.W and Collier, M. (1987) Diet of the Squirrel Glider, *Petaurus norfolcensis* (Marsupialia: Petauridae) in Victoria. *Australian Mammalogy*. 11, 109-116.
- Morcombe, M. (1986) The Great Australian Bird Finder. Lansdowne Press, Sydney, NSW.
- Mt King Ecological Surveys (1989) Jenolan Caves Reserve Draft Plan of Management Vegetation survey (In Mitchell McCotter 1989).
- Norton, T. and Lindenmayer, D. (1991) Integrated management of forest wildlife: towards a coherent strategy across state borders and land tenures. *Conservation of Australia's Forest Fauna*. Pp 237 244. D. Lunney (Ed), Royal Zoological Society of New South Wales, Mosman, NSW.
- NSW Heritage Office (2005) Online State Heritage Register. http://www.heritage.nsw.gov.au/ [Accessed January 2005].

- National Parks and Wildlife Service (1996) Information circular No. 2: Threatened species assessment under the EP&A Act: The '8 Part Test' of significance. NSW National Parks and Wildlife Service, Hurstville, NSW.
- National Parks and Wildlife Service (1998) Glovebox guide your new way to discover your national parks. NSW National Parks and Wildlife Service, Hurstville, NSW.
- National Parks and Wildlife Service (1999) Threatened species management Species information. NSW National Parks and Wildlife Service, Hurstville, NSW.
- National Parks and Wildlife Service (2000) A guide to threatened fauna of the Northern Central Tablelands. NSW National Parks and Wildlife Service, Mudgee, NSW.
- NSW Scientific Committee (2005) Threatened Species Final Determinations. NSW Scientific Committee. http://www.npws.nsw.gov.au/news/tscdets/index.html [Accessed January 2005].
- Oberon Council (2004) State of the Environment Report. Oberon Council, Oberon, NSW.
- Parnaby, H. (1992) An Interim Guide to Identification of Insectivorous Bats of South-eastern Australia. Technical Reports of the Australian Museum No 8.
- Pavey, C.R. (1995) Food of the Powerful Owl Ninox strenua in suburban Brisbane, Queensland. EMU. 95(3), 231-232.
- Pavey, C., Smith, A. and Mathieson, M. (1994) The breeding season diet of the Powerful Owl (Ninox strenua) at Brisbane, Queensland. EMU. 94(4), 278-284.
- Reardon, T.B. and Flavel, S.C. (1987) A guide to the Bats of South Australia. South Australian Museum, South Australia.
- Robinson, L. (1994) Field guide to the native plants of Sydney. Second edition. Kangaroo Press, Sydney, NSW.
- Russell, R. (1980) Spotlight on Possums. University of Queensland Press, St Lucia, Queensland.
- Schodde, R. (1994) The bird fauna of western New South Wales: geography and status Future of the Fauna of Western New South Wales (Eds D.Lunney, S.Hand, F.Reed and D.Buthcher). Royal Zoological Society of NSW Mosman, 107-121.
- Shields, J. and Chrome, F. (1992) Parrots and pigeons of Australia. Angus and Robertson, Sydney, NSW.
- Simpson, K. and Day, N. (1999) Field guide to the birds of Australia. Version 6. Penguin Books Australia, Victoria.
- Smith, J. and Smith, P. (1990) Fauna of the Blue Mountains. Kangaroo Press, Kenthurst, NSW.
- Smith, P., Smith, J., Pressey, R. and Whish, G. (1995) Birds of Particular Conservation Concern in the Western Division of New South Wales: Distributions, Habitats and Threats. National Parks and Wildlife Service Occasional Paper Number 20, National Parks and Wildlife Service, Hurstville NSW.
- Stewart, D. (1999) Bird and Mammal Calls of NE-NSW Western Slopes and Plains. Nature Sound, Mullumbimby, NSW.
- Stone, B. (2003) Assessment of the environmental impacts of self-guided tours on Sooty Owl occupying Nettle Cave. University of Sydney, Orange campus, NSW.
- Strahan, R. (Ed) (1995) The mammals of Australia. Reed Books, Chatswood, NSW.

- Swan, G., Shea, G. and Sadlier, R. (2004) A field guide to reptiles of New South Wales second edition. Reed New Holland, Sydney, NSW.
- Triggs, B. (1996) Tracks, scats and other traces: A field guide to Australian mammals. Oxford University Press, Melbourne, Victoria.
- Van Dyck, S. (1992) Lasting impressions of Mahogany Gliders (Petaurus gracilis). Australian Natural History. 32-41.
- Woodlots and Wetlands Pty Ltd and Urban Bushland Management Consultants (2004) Review of environmental factors for weed removal and bushland regeneration works at the Jenolan Karst Conservation Reserve. Report prepared for Jenolan Caves Reserve Trust by Woodlots and Wetlands Pty Ltd and Urban Bushland Management Consultants, Sydney, NSW.

#### Appendix I. Plant species list.

#### KEY:

CI = Cut slope C1.74.

C2 = Cut slope C2.63.

C3 = Cut slope C3.64, plus the proposed access track and work site.

C4 = Cut slope C4.22.

C5 = Cut slope C5.08 and C5.29.

C6 = Cut slope C7.02.

W = Walls 40/41.

C7 = Cut slope C7.58.

C8 = Cut slope C8.13.

\* = Introduced species.

FAMILY	GENUS	SPECIES	CI	C2	C3	C4	C5	C6	W	C7	C8
FILICOPSIDA											
Adiantaceae	Adiantum aethi	opicum	•				•	•		•	
	Pellaea falcata						•		•		
Aspleniaceae	Asplenium flabe							•	•	•	
Dennstaedtiaeae	Pteridium escul				•	•		•		•	
Dryopteridaceae	Polystichum pro	oliferum	•								
7											
MAGNOLIOPSIDA – MAGNOLIIDAE											
Apiaceae	Hydrocotle ped	uncularis	•	•	•	•	•	•			
Asteraceae	Bracteantha br		•	•	•	•	•	•	•	•	
	Brachycome ac	uleata			•						
	Brachycome an						•				
		n semipapposum	•	•	•	•		•			
	Cirsium vulgare						•			•	
	Galinsoga parvi						•				
	Gnaphalium gy		•	•		•	•	•		•	
	Hypochoeris ra	dicata *			•	•	•	•		•	•
	Ozothamnus di	osmifolium					•				
	Senecio lautus :	ssp. dissectifolius				•			•		
	Senecio linearif	olius			•		•	•		•	
	Senecio madag	ascariensis *	•	•	•	•	•	•	•	•	
	Sonchus olerace			•	•	•	•	•	•	•	•
	Vittadinia cuned	ıta		•	•						
Bignoniaceae	Pandorea pand	orana					•				
Boraginaceae	Austrocynogloss	um latifolium	•	•							
	Echium plantag		•			•					
	Cynoglossum su	iaveolens	•	•							
Campanulaceae	Wahlenbergia d		•	•	•	•	•	•	•	•	•
	Wahlenbergia s	tricta		•			•				
Carophyllaceae	Stellaria punger			•	•	•	•	•	•	•	•
Clusiaceae	Hypericum and									•	•
Convolvulaceae	Dichondra repe	ns	•	•	•	•	•		•		
Elaeocarpaceae	Elaeocarpus ret	iculatus					•				
Epacridaceae	Leucopogon lan	ceolatus			•	•	•			•	
	Lissanthe strigo	sa	1	•	•			•	•	•	•
Euphorbiaceae	Poranthera mic			•						•	
Fabaceae: Faboideae	Desmodium vai										•
	Glycine microph	ıylla									
	Hardenbergia v	,		•			•	•			
	Indigophora aus						•				
	Oxylobium ilicife				•						
	Swainsona gale							6			
	Trifolium camp		6								
	Trifolium repen		•								
	Trifolium subter		•		-						
Fabaceae: Mimosoideae	Acacia falciform							•		6	

FAMILY	GENUS SPECIES	CI	C2	C3	C4	C5	C6	W	C7	C8
	Acacia implexa	•	•	•	•	•		•		•
	Acacia melanoxylon	•								
Gentianaceae	Centaurium tenuiflorum *	9		•					•	
Geraniaceae	Geranium potentilloides									
	Geranium solanderi var. solanderi		•			0				
Goodeniaceae	Goodenia ovata						•			
Lamiaceae	Plectranthus parviflorus		•							
Malvaceae	Sida rhombifolia *		•	•			•		•	•
	Sida corrugata			•	•					
Myrtaceae	Eucalyptus blaxlandii	•	•	•	•					
	Eucalyptus bicostata						•	•	•	
	Eucalyptus dalrympleana				•	•				
	ssp.dalrympleana									
	Eucalyptus eugenoides							•		
	Eucalyptus fastigata									•
	Eucalyptus viminalis	•	•	•						
Oleaceae	Notelaea longifolia forma longifolia						•			•
Onagraceae	Epilobium billardierianum.	•			•		•		•	
Oxalidaceae	Oxalis corniculata *		•	•	•	•	•		•	•
Pittosporaceae	Billardiera scandens		•							
	Bursaria spinosa ssp. spinosa	•	•	•	•	•	•	•	•	•
Plantaginaceae	Plantago lanceolata *	•	•	•	•	•	•		•	•
	Plantago varia		•							
Polygonaceae	Persicaria decipiens	•								
	Rumex sp.	•		•			•		•	•
Primulaceae	Anagallis arvensis *	•								
Proteaceae	Lomatia myricoides	•	•	•	•	•			•	•
	Persoonia linearis		•		•	•	•			
Ranunculaceae	Clematis aristata	•	•	•	•	•	•		•	•
Rhamnaceae	Pomaderris ?prunifolia									•
Rosaceae	Acaena ovina	6	•	•	•	•	•		•	•
	Rosa rubignosa *						•			
	Rubus ulmifolius *				•		•		•	•
Rubiaceae	Galium gaudichaudii	-	-			•			-	
Santalaceae	Exocarpos cupressiformis		•		•	•		•		
Sapindaceae	Dodonaea viscosa				•		-	•	•	•
Scrophulariaceae	Verbascum virgatum *	•	•				•		•	•
<u> </u>	Veronica pleibeia	-		•						
Solanaceae	Solanum prinophyllum	•	-						•	•
Stylidiaceae	Stylidium graminifolium	-	-		-				-	•
Urticaceae	Urtica incisa		•	•		•	•		•	•
Violaceae	Hymenanthera dentata	-	-			•	•		•	•
MAGNOLIOPSIDA -	Viola betonicifolia	•	•	•	•	•	•		•	•
LILIIDAE										
Anthericaceae	Dichopogon fimbriatus	-	-	-					-	-
Asphodeliaceae	Bulbine bulbosa	-		-	-		•		-	
Cyperaceae	Lepidosperma laterale	-		-			•		•	•
Lomandraceae	Lomandra longifolia	-	-	•	-	-	-		-	•
Lomandraceae	Lomandra glauca ssp. glauca		•		•	•	•	•	•	•
	Lomandra multiflora	-	-	•	•	•	-			
Orchidaceae	Dipodium punctatum	-	-	•	•	•	-	•	-	-
Philesciaceae	Geitonoplesium cymosum	+		•	-	•				
Phormiaceae	Dianella longifolia var. longifolia						-			
	Stypandra glauca	-	-	-	-		-			•
Poaceae	Austrodanthonia sp.					•				
· Cuccuc	Avena fatua	-	-	-	-	-			-	
	Echinopogon caespitosus	-			-		•			6
	var. coespitosus						9			
	Paspoium dilatatum *	-		-					1	
	Poa labiliardieri				6			6		45
	Themeda australis	+			-		•	-	6	

### Appendix 2. Fauna species recorded or previously detected within the study region.

#### Source of Records:

I = Species recorded during the current investigation.

2 = DEC (2005).

3 = LesryK Environmental Consultants (2004).

4 = Landscope Environmental Consultants (1996).

#### KEY:

A - Indicates a species listed under the EPBC Act.

F - Migratory Family listed under the EPBC Act.

B - Indicates a species listed under the TSC Act.

P - Preliminary determination for listing under the TSC Act.

C - Confident identification of bat call analysis.

Pr - Probable identification of bat call analysis.

\* - Indicates introduced species.

A	В	Common Name	Family and Scientific Name	1	2	3	4
		MAMMALS					
			Tachyglossidae				
		Short-beaked Echidna	Tachyglossus aculeatus	×	×		×
			Dasyuridae				
X	X	Spotted-tailed Quoll	Dasyurus maculatus		×		
		Brown Antechinus	Antechinus stuartii	×	X		
		Dusky Antechinus	Antechinus swainsonii		×		
		Common Dunnart	Sminthopsis murina		×		
			Phascolarctidae				
	x	Koala	Phascolarctos cinereus		X		
			Vombatidae				
		Common Wombat	Vombatus ursinus	×	×	X	X
			Petauridae				
	×	Yellow-bellied Glider	Petaurus australis	×	×		
		Sugar Glider	Petaurus breviceps		X	Х	
			Pseudocheiridae	-			
		Greater Glider	Petauroides volans	×	×	X	
		Common Ringtail Possum	Pseudocheirus peregrinus		×	X	
			Acrobatidae				
		Feathertail Glider	Acrobates pygmaeus		X		
			Phalangeridae				
		Common Brushtail Possum	Trichosurus vulpecula	×	X	X	×
			Macropodidae				
		Eastern Grey Kangaroo	Macropus giganteus	×	×	X	×
		Common Wallaroo	Macropus robustus		X		
		Red-necked Wallaby	Macropus rufogriseus	×	×	X	
X	X	Brush-tailed Rock-Wallaby	Petrogale penicillata		X		
		Swamp Wallaby	Wallabia bicolor	×	×		×
			Rhinolophidae				
		Eastern Horseshoe Bat	Rhinolophus megaphyllus			X	
			Vespertilioidae				
х	X	Large-eared Pied Bat	Chalinolobus dwyeri	C	X		
		Gould's Wattled Bat	Chalinolobus gauldii	C	×	X	
-		Chocolate Wattled Bat	Chalinolobus morio	Pr	X		1

A	В	Common Name	Family and Scientific Name	-	2	3	4
	X	Eastern False Pipistrelle	Falsistrellus tasmaniensis	Pr	X	×	
	X	Large-footed Myotis	Myotis adversus	Pr			
	X	Eastern Bentwing Bat	Miniopterus schreibersii	С	×	×	
		Lesser Longeared Bat	Nyctophilus geoffroyi		X		
		Gould's Longeared Bat	Nyctophilus gouldi		X		
		Eastern Broadnosed Bat	Scotorepens orion			X	
		Large Forest Bat	Vespadelus darlingtoni	C	X	X	
		Southern Forest Bat	Vespadelus regulus	C	X		
		Little Forest Bat	Vespadelus vulturnus	C	X		
			Molossidae				
		White-striped Freetail Bat	Nyctinomus australis	C	X	×	
			Muridae				
		* House Mouse	Mus musculus		X		
		Bush Rat	Rattus fuscipes		X		
		* Black Rat	Rattus rattus		X		
			Canidae				
		Dingo	Canis lupus dingo		×		
-		* Fox	Vulpes vulpes		X	×	X
-			Leporidae				
-		* Rabbit	Oryctolagus cuniculus		X		X
-			Suidae				
-		* Pig	Sus scrofa		×		-
-		BIRDS				_	-
-			Podicipedidae				-
-		Australasian Grebe	Tachybaptus novaehollandiae				×
=			Anatidae				-
-		Pacific Black Duck	Anas superciliosa		×		X
-		Grey Teal	Anas gracilis				×
-		Australian Wood Duck	Chenonetta jubata				X
-			Rallidae		-		-
		Eurasian Coot	Fulica atra		-		X
-			Ardeidae				-
-	-	White-faced Heron	Egretta novaehollandiae		X		×
=			Charadriidae				
1		Masked Lapwing	Vanellus miles				×
=			Accipitridae				-
-		Wedge-tailed Eagle	Aquila audax		X	X	X
			Falconidae	,			-
-		Brown Falcon	Falco berigora				×
-		Nankeen Kestrel	Falco cenchroides			-	×
			Columbidae		-	-	-
-		Wonga Pigeon	Leucosarcia melanoleuca	×	X	X	-
-		7701184 1180011	Cacatuidae	-   ~	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	-	-
-		Yellow-tailed Black Cockatoo	Calyptorhynchus funereus	×	X		×
-	P	Gang-Gang Cockatoo	Callocephalon fimbriatum	×	X	×	×
-	-	Galah	Eolophus roseicpilla	^	^	-	X
-		Sulphur-crested Cockatoo	Cacatua galerita	×	X	X	X
-		Sulphul -Crested Cockatoo	Psittacidae	X	^		1

A	В	Common Name	Family and Scientific Name	i	2	3	4
		Rainbow Lorikeet	Trichoglossus haematodus			Х	
		Australian King Parrot	Alisterus scapularis		X		X
		Crimson Rosella	Platycercus elegans	×	X	X	X
		Eastern Rosella	stern Rosella Platycercus eximius				X
			Cuculidae				
		Fan-tailed Cuckoo	Cuculus flabelliformis		X		
		Channel-billed Cuckoo	Scthrops novaehollandiae		X		Г
			Strigidae				
	X	Powerful Owl	Ninox strenua	×	X	X	
		Southern Boobook	Ninox novaeseelandiae	×	X	X	
	X	Barking Owl	Ninox connivens		X		
			Tytonidae				
	X	Sooty Owl	Tyto tenebricosa	×	X	X	
		Barn Owl	Tyto alba		X		
1			Podargidae				
		Tawny Frogmouth	Podargus strigoides	×	X		
			Caprimulgidae				$\vdash$
1		White-throated Nightjar	Eurostopodus mysticalis		X		-
			Aegothelidae				$\vdash$
		Australian Owlet-nightjar	Aegotheles cristatus		X		$\vdash$
			Apodidae				$\vdash$
X		White-throated Needletail	Hirundapus caudacutus		X		
-			Alcedinidae				$\vdash$
-		Laughing Kookaburra	Dacelo naxaeguineae	×	X	X	)
+		Sacred Kingfisher	Todiramphus sanctus	×	-	1	-
-			Menuridae				$\vdash$
-		Superb Lyrebird	Menura novaehollandiae	×	×		-
-			Neosittidae				-
+		Varied Sittella	Daphoenositta chrysoptera		X		-
+			Climacteridae				+
-		White-throated Treecreeper	Cormobates leucophaeus	×	X		)
+		Red-browed Treecreeper	Climacteris erythrops		X		-
-			Maluridae				-
-		Superb Fairy-wren	Malurus cyaneus	×	X	-	)
+		Variegated Fairy-wren	Malurus lamberti		X		+
-			Pardalotidae				$\vdash$
+		Spotted Pardalote	Pardalotus punctatus		X		>
1		Striated Pardalote	Pardalotus striatus	×	X		1>
-		Rockwarbler	Origma solitaria		X		+
-		White-browed Scrubwren	Sericornis frontalis	×	X	-	1
+		Brown Gerygone	Gerygone mouki		X	-	-
+		Brown Thornbill	Acanthiza pusilia	×	X	X	1
-		Yellow Thornbill	Acanthiza nana		X	X	1
+		Striated Thornbill	Acanthiza lineata	×	X	1-	1
+		Buff-rumped Thornbill	Acanthiza reguloides		X		-
-		Yellow-rumped Thornbill	Acanthiza chrysorrhoa			1	7
1			Meliphagidae		-		1
-		Red Wattlebird	Anthochaera carunculata	×	×	X	>

AB	Common Name	Family and Scientific Name	1	2	3	4
	Noisy Friarbird	Philemon corniculatus	×	X		×
	Bell Miner	Manorina melanophrys	×		Х	
	Lewin's Honeyeater	Meliphaga lewinii		X	X	
	Yellow-faced Honeyeater	Lichenostomus chrysops	×	X		X
	White-eared Honeyeater	Lichenostomus leucotis		X		X
	White-plumed Honeyeater	Lichenostomus pencillatus	×	X		
	Brown-headed Honeyeater	Melithreptus brevirostris		X		
	White-naped Honeyeater	Melithreptus lunatus		X		
	New Holland Honeyeater	Phylidonryis novaehollandiae		X		
	Eastern Spinebill	Acanthorhynchus tenuirostris	×	X		X
		Orthonychidae				
	Eastern Whipbird	Psophodes olivaceus	×	X		
		Cinclosomatidae				
	Spotted Quail-thrush	Cinclosoma punctatum		X		
		Petroicidae				
	Rose Robin	Petroica rosea		X		
	Flame Robin	Petroica phoenicea		X		
	Scarlet Robin	Petroica multicolor		×		
	Eastern Yellow Robin	Eopsaltria australis		X		
		Pachycephalidae				
	Grey Shrike-thrush	Colluricincla harmonica	×	X		X
	Golden Whistler	Pachycephala pectoralis		X		
		Dicruridae				
	Grey Fantail	Rhipidura fuliginosa		X		X
×	Rufous Fantail	Rhipidura rufifrons		X		
	Willie Wagtail	Rhipidura leucophrys				×
	Leaden Flycatcher	Myiagra rubecula		X		
X	Satin Flycatcher	Myiagra cyanoleuca	×	X		
	Magpie Lark	Grallina cyanoleuca				×
		Ptilonorhynchidae				
	Satin Bowerbird	Ptilonorhychus violaceus		X		
		Campephagidae				
	Black-faced Cuckoo-shrike	Coracina novaehollandiae	×	X		×
	Cicadabird	Coracina tenuirostris		X		
		Artamidae				
	Grey Butcherbird	Cracticus torquatus	×	X		
	Pied Butcherbird	Cracticus nigrogularis				×
	Australian Magpie	Gymnorhina tibicen	×	х	Х	×
	Pied Currawong	Strepera graculina	×	X		X
	Grey Currawong	Strepera versicolor		X	×	×
		Corvidae				
	Australian Raven	Corvus coronoides	×	X	×	X
		Corcoracidae				
	White-winged Chough	Corcorax melanorhamphos		x	×	
		Hirundinidae				
	Welcome Swallow	Hirundo neoxena	×	X	×	X
	Fairy Martin	Hirundo ariel				×
		Motacillidae				

A	В	Common Name	Family and Scientific Name		2	3	4
		Richard's Pipit	Anthus naovaeseelandiae				X
			Alaudidae				
		Singing Bushlark	Mirafra javanica				X
			Passeridae				
		* House Sparrow	Passer domesticus				X
			Fringillidae				
		* European Goldfinch	Carduelis carduelis				X
			Ploceidae				
		Red-browed Finch	Neochmia temporalis		×		
			Dicaeidae				T
		Mistletoebird	Dicaeum hirundinaceum			X	
			Zosteropidae				Г
		Silvereye	Zosterops lateralis	×	X		X
F			Muscicapidae				T
		Bassian Thrush	Zoothera lunulata		X		Г
			Sturnidae				
		* Common Starling	Sturnus vulgaris			X	X
		* Common Myna	Acridotheres tristis				X
							1
		REPTILES					
			Agamidae				
		Jacky Lizard	Amphibolurus muricatus				X
		Eastern Water Dragon	Physignathus lesueurii				X
1			Scincidae				1
		Red-throated Skink	Bassiana platynota		X		
7		"No Common Name"	Cyclodomorphus michaeli		X		
		Cunningham's Skink	Egernia cunninghami		X		
1		Heatwole's Water Skink	Eulamprus heatwolei		X		$\vdash$
		Eastern Water Skink	Eulamprus quoyii		Х		
		Grass Skink	Lampropholis delicata	×	X		X
		Garden Skink	Lampropholis guichenoti		×		
7		Southern Forest Cool-skink	Niveoscincus coventryi		X		
1		Woodland Tussock-skink	Pseudemoia entrecasteauxii		X		
1		"No Common Name"	Pseudemoia spenceri		X		
		Weasel Skink	Saproscincus mustelinus		X		$\vdash$
		Blotched Blue-tongued lizard	Tiliqua nigrolutea				×
1		Eastern Blue-tongued Lizard	Tiliqua scincoides				X
			Elapidae				$\vdash$
		Red-bellied Black Snake	Pseudechis porphyriacus	×	X		
		AMPHIBIANS					
1			Myobatrachidae				
		Common Eastern Froglet	Crinia signifera		×		X
		Eastern Banjo Frog	Limnodynastes dumerilii		×		
		Striped Marsh Frog	Limnodynastes peronii		×		X
			Hylidae				1
1		Leseur's Tree Frog	Litoria lesueuri		X	1	
-		Leaf Green Tree Frog	Litaria phyllochrae		×		
+		Verreaux's Tree Frog	Litoria verreauxii		X	<u> </u>	

## Appendix 3. Fauna species of conservation significance previously recorded in the study region.

Common and Scientific Legislation Habitat Requirements\* Presence Consideration Name

BIRDS			
White-throated Needletail (Hirundapus caudacutus)	EPBC Act (m)	The White-throated Needletail breeds in the northern hemisphere and arrives in Australia in October. Most commonly associated with the east coast highlands, coastal plains and the hinterlands of arid inland Australia. Within this are, becomes locally nomadic in response to local weather changes. Drinks and feeds on insects while on the wing. Roost during the night in trees in forests.	Due to its nomadic nature and ability to traverse over a variety of habitat types, this species could be present throughout all portions of the study area. Although this is the case, the Proposal would not have a significant impact on any resources important to the local or regional occurrence of this species.
Rufous Fantail (Rhiþidura rufifrons)	EPBC Act (m)	The Rufous Fantail migrates south from north-eastern Queensland and New Guinea to breed within the southern states during the summer months (October to February). Generally this species inhabits rainforests, moist sclerophyll forests and vegetated riparian corridors along the east coast and ranges. This bird forages on a variety of insects that occur within the shrub layers of its preferred habitat type.	The necessary habitat requirements of this species are not present within the study area. As such, the Rufous Fantail would not be present.
Glossy Black-Cockatoo (Calyptorhynchus lathami)	TSC Act	Nesting and roosting in hollows of large eucalypt trees this bird can spend up to 88% of each day foraging. Inhabits eucalypt woodland and feeds almost exclusively on Casuarina fruits. This species shows a strong preference for individual trees with a high seed to cone ratio.	This species was not observed or heard calling during any of the field investigations. Similarly, this species was not detected during the previous investigation (LesryK Environmental Consultants 2004). During the surveys, no crushed Casuarina cones were discovered. The Glossy Black-Cockatoo is not considered to be dependant upon those portions of the eucalypt woodland that occur within the study area.

<sup>\*</sup> habitat requirements were generally extracted from Frith (1997), Cogger (1992), Strahan (1995), NPWS (1999) and the NSW Scientific Committee (2005), with other references used being identified in the bibliography. (m) - migratory bird listed under the EPBC Act.

Common and Scientific Name	Legislation	Habitat Requirements*	Presence Consideration
Speckled Warbler (Chthinicola sagittata)	TSC Act	Distributed from Suttor Creek in southeast Queensland, through central and eastern NSW to the Grampians in Victoria. Occupies eucalypt and cypress woodlands with an open grassy and shrubby understorey often associated with gullies and rocky ridges. Has a home range area of between 6 to 12ha. Foraging for seeds, insects, larvae and other invertebrates, it occurs amongst leaf litter and under shrubs, trees and grasses. The breeding season is from August to January. Generally not being present in areas of habitat less than 100ha in size.	This species may forage within the study area on occasion, however, the removal of a maximum of 6.15ha of bushland, compared to the remaining 350,106ha that occurs within the surrounding conservation reserves, is not considered to significantly reduce the extent of any resources available for this species.
Swift Parrot EPBC Act (Lathamus discolor) TSC Act		The Swift Parrot breeds in Tasmania but migrates to mainland Australia to feed on winter blossoms during the winter months. On the mainland, this species occurs in a wide variety of habitats, depending on where there are flowering blossoms. Feeds either alone or in parties within the topmost branches of eucalypts. Winter flocks are nomadic in response to the availability of food sources, but, where suitable resources are present, may remain in one place for a while.	This species may forage within the study area on occasion. However the removal of a total of 6.15ha of bushland, compared to the remaining 350,106ha that occurs within the surrounding conservation reserves, is not considered to significantly reduce the extent of any resources available for this species.
Australian Painted Snipe (Rostratula benghalensis australis)	EPBC Act TSC Act	The Painted Snipe is a well camouflaged, nomadic bird that lives within muddy ground in boggy swamps. They prefer shallow freshwater swamps where they feed on aquatic insects and earthworms found in soft mud. They are primarily a nocturnal bird however they have been known to be active during the day. The Painted Snipe nests in a raised area of damp mud, lined with grass and reeds, surrounded by shallow water often within River Red Gum <i>Eucalyptus camaldulensis</i> . The Painted Snipe breeds between October and December.	Not targeted as no suitable habitat for this species is present within the study area.
Regent Honeyeater (Xanthomyza phrygia)	EPBC Act TSC Act	The Regent Honeyeater prefers open forests, woodlands, timbered watercourses, and a variety of other habitat types. This species constructs a grass nest in trees or saplings. This species feeds primarily on four eucalypt species, Red Ironbark Eucalyptus sideroxylon, White Box E. albens, Yellow Box E. melliodora and Yellow Gum E. leucoxylon as well as heavy infestations of mistletoe (Amyema spp.). The Regent Honeyeater breeds from August to January.	This species may forage within the study area on occasion, however, the removal of a total of 6.15ha of bushland, compared to the remaining 350,106ha that occurs within the surrounding conservation reserves, is not considered to significantly reduce the extent of any resources available for this species.

Common and Scientific Name	Legislation	Habitat Requirements*	Presence Consideration
Grey Falcon (Falco hypoleucos)	TSC Act	Flat mainly treeless or lightly timbered plains with open, drier vegetation such as tussock grassland. Nest in large eucalypt trees near, or overhanging dry or wet watercourses. Forages in wooded area adjacent to water bodies where prey species drink. Feeds on species caught on the ground, such as ground birds, small mammals and reptiles.	Not targeted as no suitable habitat for this species is present within the study area. Species not observed or heard calling during any of the field surveys.
Barking Owl (Ninox connivens)	TSC Act	Inhabits tall, wet, old growth forests on fertile soils with a dense understorey. Has a home range area of between 200ha to 800ha in which a permanently bonded pair occurs. Breeds in the trunks of mature Eucalypts and appears to be loyal to nest sites. Roosts apart by day on a number of set perches throughout their territory. Prey species include mainly arboreal mammals.	Specifically targeted during the field investigations. Though not recorded, this species may be present in the eucalypt woodlands. However the removal of a total of 6.15ha of bushland, compared to the remaining 350,106ha that occurs within the surrounding conservation reserves, is not considered to significantly reduce the extent of any resources available for this species.
MAMMALS			
Spotted-tailed Quoll (Dasyurus maculatus)	EPBC Act TSC Act	The Spotted-tailed Quoll occurs within a variety of habitat types including wet and dry sclerophyll forests through to rainforests. The quoll is nocturnal and shelters in tree hollows, dense undergrowth, hollow logs or under rock outcrops. Home range sizes for this species are known to be large with males travelling up to 15km²/night, and females between 3-4km²/night. The quoll preys on a wide variety of terrestrial and arboreal vertebrates, including rabbits, brush-tails and ringtails.	Specifically targeted during the investigations. During the surveys this species was not recorded. Within the study area, no habitats significant for the local occurrence of this species are present. Post development, this species is still expected to be able to traverse over, and forage within/through, the study area if present on occasion.
Brush-tailed Rock-Wallaby (Petrogale penicillata)	EPBC Act TSC Act	The Brush-tailed Rock-Wallaby is found in suitably rocky areas within a variety of habitats such as rainforest gullies, wet and dry sclerophyll forest, open woodland and rock outcrops in semi-arid country. Sites with numerous ledges, caves and crevices are favoured.	During the survey this species was not recorded. The majority of Brush-tailed Rock-Wallaby's present in this region are confined to a predator proof enclosure that occurs near Jenolan Caves. Within the study area, no habitats significant for the local occurrence of this species are present. Post development, this species is still expected to be able to traverse over, and forage within/through, the study area if present on occasion.

Common and Scientific Name	Legislation	Habitat Requirements*	Presence Consideration
Long-nosed Potoroo (Potorous tridactylus tridactylus)	EPBC Act TSC Act	Generally restricted to areas with an annual rainfall greater than 760mm, it inhabits coastal heath and dry and wet sclerophyll forests with dense cover, which provides diurnal sheltering sites and protection from predators. Forages in adjacent, open areas. Feeds predominantly on fungi, which is dug for within soft and sandy soil. Also known to feed on roots, fruits, seeds and soft bodied animals in the soil.	During the survey this species was not recorded. No significant impacts on this species are considered to occur as a result of the Proposal.
Squirrel Glider (Petaurus norfolkensis)	TSC Act	Inhabits woodlands and dry sclerophyll forests, usually in diverse stands of shrubs and trees. Shelters and breeds in tree hollows, and is primarily an insectivorous animal but has also been known to ingest plant exudates. Family groups occupy a home range of 2 - 4ha. Where trees are up to 20m in height, this species is known to traverse across open space areas 40m wide.	Specifically targeted during the field investigations. Though not recorded, this species may be present in the eucalypt woodlands. However the removal of a total of 6.15ha of bushland, compared to the remaining 350,106ha that occurs within the surrounding conservation reserves, is not considered to significantly reduce the extent of any resources available for this species.
Koala (Phascolarctos cinereus)	TSC Act	The Koala occupies areas of acceptable food trees in open eucalypt forests and woodlands. Areas of preferred feed trees appear to be restricted to sites that support high nutrient soils, areas that have historically been converted to farmland.	No evidence, such as characteristic scratchings or scats were observed within the study area. Post development, if present on occasion, the Koala is still expected to be able to traverse over, and forage within/through, the study area.
Greater Longeared Bat (Nyctophilus timoriensis)	EPBC Act TSC Act	The Greater Long-eared Bat inhabits dry open woodland areas and mallees. Within these areas this species roosts in tree hollows and under loose bark. This species feeds on insects such as large moths, beetles, ants and crickets.	Specifically targeted during the field investigations. During the surveys the species was not recorded. Within the proposed development areas, no hollow bearing trees, caves or cave substitutes are present.
Grey-headed Flying Fox (Pteropus poliocephalus)	EPBC Act TSC Act	The Grey-headed Flying Fox is a canopy-feeding frugivore, blossomeater and nectarivore that inhabits a variety of habitats. Roosts and breeds communally in 'camps', with these camps containing between 500 to 5000 individuals. Individuals generally exhibit a high fidelity to traditional camps and return annually to give birth and rear offspring. Foraging occurs opportunistically on both native and exotic plants, often at distances between 30-70km from camps.	Specifically targeted during spotlighting. During the survey the species was not recorded, nor were any active or historic roosting camps observed. The Grey-headed Flying Fox has the potential to fly over the study area on occasion. Although this is the case, this bat is known to easily traverse open space areas.

Common and Scientific Name	Legislation	Habitat Requirements*	Presence Consideration
REPTILES			
Broad-headed Snake	EPBC Act	This species is largely confined to the Hawkesbury Sandstone	Not targeted as no suitable habitat for this species is
(Hoplocephalus bungaroides)	TSC Act	formations within the wider Sydney basin. Sheltering under exfoliated material, in rock crevices and caves during the day, and to hunt at night, usually feeding on small lizards, geckos and frogs.	present within the study area.
AMPHIBIANS		, , ,	
Borroolong Frog (Litoria booroolongenis)	TSC Act	The Booroolong Frog occurs along the Great Dividing Range of NSW. It is almost always associated with rocky flowing streams in mountainous regions.	Not targeted as no suitable habitat for this species is present within the study area.
Giant Burrowing Frog	EPBC Act	Associated with sandstone outcrops. Lives in small semi-permanent to	Not targeted as no suitable habitat for this species is
(Helcioporus australiacus)	TSC Act	slightly flowing streams, breeding in sandy river bank burrows. Not found in creeks affected by stormwater or other pollutants, or in urbanised areas.	present within the study area.
Red-crowned Toadlet	TSC Act	The Red-crowned Toadlet is confined to drainage lines in areas of	Not targeted as no suitable habitat for this species is
(Pseudophryne australis)		Hawkesbury Sandstone, especially those that support weathered shale lenses. This species shelters under stones, vegetation or logs and is highly susceptible to pollutants, storm water runoff from urban areas and weed infested areas.	present within the study area.
INVERTEBRATES			
Purple Copper Butterfly (Paralucia spinifera)	EPBC Act TSC Act	Locations for the Purple Copper Butterfly are restricted, with all occurring above 900m in altitude. This butterfly is only found in open eucalypt woodlands/forests with a sparse understorey dominated by Blackthorn shrubs (Bursaria spinosa subsp. lasiophylla). This shrub is important for the occurrence of the Purple Copper Butterfly, these plants always having to be present thereby meeting the foraging requirements of the butterfly's larvae. Most occupied sites are exposed to full day sun, generally having a northwest to westerly aspect. The Purple Copper Butterfly is also associated with a species of small ant (Anonychomyrma itinerans). To date, all published records for this butterfly have been made to the east of Bathurst.	Targeted surveys for this species did not identify any areas of suitable habitat (refer to Appendix 4). During the field investigation only <i>Bursaria spinosa</i> ssp. <i>spinosa</i> was recorded, this plant not known to be utilised by the Purple Copper Butterfly. As such, this species would not be present within the study area.

# Appendix 4. Results of targeted survey undertaken to determine the presence of the Purple Copper Butterfly (Paralucia spinifera).

23" December 2004

Mr. Nick Francesconi Acting Environmental Officer - Biodiversity and Sustainability Level 5 260 Elizabeth Street Surry Hills, NSW, 2010



Dear Nick,

In accordance with your request for an inspection of the Jenolan Caves roadworks for habitat of the Purple Copper Butterfly (*Paralucia spinifera*) I visited the site on 13.1.5 and checked for key habitat attributes at cuttings associated with Wall 1 and chainages C3.64, C4.22, C5.08, C5.29 and C7.58, as well as at the compound.

These rispections covered the range of altitudes and aspects presented by the site, and while suitable elements existed in terms of aspects and incident sunshine as well as some of the associated vegetation (particularly Lissanthe strigosa, Monotoca scoparia and Stellaria pungeria) the species of Blackthorn noted throughout (Bursaria spinosa) has a glabrous undersurface to the leaf (see attached specimen), being a species which is not known to be utilised by the butterfly - B. lasiophylla atriplicina, the food plant of the butterflies larvae, has a minutely hairy I hoary underside to the leaf.

During the field assessment a consulting botanist (John Spate) was also engaged in inspections of the proposed cuttings, and he was briefed on requirements of the butterfly and the differences in the Blackthorn species, and directed to alert my office if he found any plants resembling *B. lesiophylla atriplicina*. He was contacted on 23.1.5 and again confirmed that there were none of this species on the site.

The Jenolar project area does not contain habitat for the Purple Copper Butterfly, and there will be no impact on this species under the proposal, or any requirement for further assessment for this species.

If you have any further questions or requirements please do not hesitate to contact me.

Yours

Raymond Mjadv esch (consulting ecologist)
Principal Mjadwesch Environmental Service Support

K Nejadwerth.

MJADWESCH ENVIRONMENTAL SERVICE SUPPORT 26 Keppel Street BATHURST NSW 2795 email: mjad@tpg.com .au ph / fax: (02) 6331 5653 ABN: 72 676 295 925




Figure 1. Wetter vegetation occurs at lower altitudes where it is often too shady for the butterfly ...



Figure 2. ...however drier more suitable habitats occur at higher altitudes and on exposed knolls




Figure 3. Bursaria spinosa occurs right up to the edge of existing cuttings...



Figure 4 ... however this species, which sometimes takes the form of a small tree, is not utilised by the Purple Copper Butterfly

VJAOWESCH ENVIRONMENTAL SERVICE SUPPORT 6 Keptel Street ATHURST NSW 2795 email: mjad@tpg.com..au ph / fax (02) 6331 5858 ABN: 72 878 295 925

# Appendix B Landscape and Visual study



# Jenolan Caves Road Landscape and Visual Assessment

PROPOSAL TO REMEDIATE CUT SLOPES on JENOLAN CAVES ROAD (Main Road No. 253)



NSW ROADS AND TRAFFIC AUTHORITY Parramatta

#### URBAN DESIGN OFFICE PTY LTD

allowed to a temperature of the major and the temperature profit forms of the form of the



## CONTENTS

EXECUTIVE SUMMARY	
INTRODUCTION	
SCOPE OF WORK	
VISUAL ASSESSMENT METHODOLOGY	
EXISTING LANDSCAPE CHARACTER	
LANDSCAPE AND VISUAL ASSESSMENT	9
SUMMARY OF FINDINGS	10
RECOMMENDATIONS	11
VISUAL ASSESSMENT PROFORMA SHEETS	12
APPENDIX	47
- MAP OF STUDY AREA - DELETED SITE #4, WALL 1/CH 2.6	48 50
CONTACT	

#### **EXECUTIVE SUMMARY**



Exercise obgrader just north of Rempton and the Great Dividing Range is Linky open and solubilities.



The agreement the Creat Dividing Range in the region of Bindo the topography becomes more small visit in the aleuter torest cover.



When the Process area the topography is steep, arginal and densely logisted, amost to the exchange of a Long week. Merechalls are strongly travel by road son Cologs throughout



#### JENETAN CAVES DOAD LAND COAPE and VISUAL ASSESSMENT

#### BACKGROUND

The NSW Bends and Traffic Authority (NTA) proposes to remediate out slopes on Jenelan Caves Read (Main Board No. 25%). The proposed work sites are located nearby and to the north of Jenelan Caves.

The remodiation works at the troid to set slopes would involve scaling loose rock, drilling holes for rock belt installation, installing galvanised and claim link rock terries, and repeating becomen tet drainage structures. Works at an interlegate at stept. Out 3.64 would require scaling lease rock, and deling holes to enable inpert pieconeties and inclinement at a being rock, Works above 10 in 3.64 may require establishment of an access track (500m length, 5m width) and a working area. Mative vegetation would need to be removed to establish an access track, and some native vegetation would need to be removed to establish an access track, and some native vegetation would need to be removed to establish an access track.

In addition, a compound site world be used during construction works for sterage of plant and mixerial. The compound site is located approximately 2km north of Wall 1 (see *Location Plan* opposite).

Construction works would be undertaken during night shifts (April 16 Team) from Sunday nights to Thruseko nights inclusive

An RLL is required for the Proposal to fulfil the requirements of *Section 111 iP.int Vier the Love virus at Planning and Assessment.*Act RCD and to take into account all matters affecting or likely to affect the environment as a result of the Proposal. Specialist input is required for the RLP in the area of landscape and visual impact assessment.

#### LIMITS OF STUDY AREA

The Study Area constructed 10 cut slopes, plus Gut 3,64 and a compound site within 10km of Jonelan Caves.

#### PHINDOSE OF STURY

Jenolan Caves Board is surrounced by a network of large conservation reserves. These reserves and other protected lands include the Jenolan Caves Reserve Conservation Area. Blue Mountains and Kanangra Boyd National Park sand both Junolan and Hampton Stare Forests. The road leads to the popular Jenolan Caves found destination of regional and international somitions of the area is therefore of great againspace and as such potentially sensitive to any proposal that could potentially impact on the pusing character of the languages.

This landscape and visual assessment will be used by the BTA in determining the effects of the Proposal on the landscape and visual amenity of the study area, and in the development of appropriate national on measures for any identifical postation posts.

It is NTA's intention that the landscape and visual assessment produce one set of working paper, which will identify matters relevant to the study area and satisfy the relevant legislation, policies and quidelines of NSW and the Commonwealth Gorarmonts.

#### FINDING

The visual assessment was carried our over 3 days in fine weather. Lach of the proposed week sites was assessed, plus the existing compound site. The Proposal was also assessed from the camping ground med way between the polar Caves and Mount Inspiration.

The Study Four Ether Theoremsensitivity' to the Proposal would be limited to the users of Jenolan Cayes IVaar - the group that will be will have trees the croposal.

The Study found that the Proposal would have a Low to Moderate Visual Impact during the Construction Phase, and a Low Visual Impact in the Construction Phase.

The one exception to this finding is the proposal to construct an access track to the hill open above Cut 3364 for the purpose of achieving then the verks at that out. This Study concluded that the construction of the track cannot be achieved without significant bligh, long term. Visual Impact upon the existing landscape character. Furthermore, the Study questioned the buildability and practicality of constructing the track. This Study recommends that other methods of achieving this particular section of work be serious considered. For example, the work could be substantially completed from the coach below by an extra long exceptor. Work beyond the reach of a specialist machine may be achieved varieting by band from a cherry picker, or examining about by absolute. A number of options are available. This Study strongly recommends that the access track option is plantioned.


#### RECOMMENDATIONS

The Stray recommends that with the exception of the access track discussed above, the Proposal does not present an unacceptable visual impact either in the construction or operational phase, and may therefore process. A number of mitigation options are discussed in the report.



#### INTRODUCTION

Appendix A Jenolan Caves Road MR253 Proposed treatment programme: retaining walls and ARL1-2 slopes



Retaining wall (symbol anchored at uphill end)

Retaining walls included in treatment programme (see 41 highest priority)

ARL 1 cutting

ARL 2 cutting

/ Road Fire Track Walking Track

500 Meters Topographic contour (50 miniterval)





#### SENCEAN CAVES BOAD TANDSCAPE and VISUAL ASSETS THE

#### INTRODUCTION

#### BACKGROUND

The NSW Boads and Traffic Authority (RTA) proposes to remediate cut slopes on Jenolan Caves Road (Main Boad No. 253). The proposed work sites are located nearby and to the north of Jenolan Caves.

The remediation works at the ten (10) cut slopes would involve scaling loose rock, drilling holes (installing rock bolts), installing steed mesh and barrier tending, and repair replacement of drainage structures. Works at an additional cut slope 'Cut 3.64' would require scaling loose rock, and onling holes to enable insert piezometers and inclinometers to be inserted. Works above 'Cut 3.64' may require establishment of an access track (500m length, 5m width) and a working area. Native vegetation would need to be removed to establish an access track, and some native vegetation would need to be removed to establish a working area.

In addition, a compound site would be used during construction works for storage of plant and material. The compound site is located approximately 2km north of Wall 1 (see Location Plan opposite).

Construction works would be undertaken during night shifts (4pm to 10am) from Sunday nights to Thursday nights inclusive

An BLE is required for the Proposal to fulfil the requirements of Section 111 (Part V) of the Environmental Planning and Assessment Act 1979 and to take into account all matters affecting or likely to affect the environment as a result of the Proposal. Specialist input is required for the REF in the area of landscape and visual impact assessment.

The Study Area locations (10 cut slopes, plus Cut 3.64, compound site) are identified on the Location Plan opposite. The serslopes are identified as.

- Cut slope, yellow highlight (7 sites);
- Cut slope, orange highlight (1 site to the west of Inspiration Lookout);
- Cut slope, Wall 1 (1 site):
- Cut slope, Wall 40/41 (1 site).
- Cut 3.64 (1 site, orange highlight to the north of Inspiration Lookout);
- Access track (500m length, 5m width) to above Cut 3.64 and work area above the cut (see pink markup); and
- Compound site (approximately 2km north of Wall 1).

Note: Chainage markers are present on site at 100m intervals commencing at the top of the hill (north end - CH. 0m) and finishing near Jenolan Caves (south end - CH. 8000m).

#### KEY TO VISUAL ASSESSMENT LOCATIONS (from north to south, up to down).

ASSESSMENT SITES	Cut No.	Chainage
#1 COMPOUND SITE		
#2 KATOOMBA VIEW LOOKOUT		
#3 PROPOSED CUT SHE	C1.74	1.72 - 1.86
#4 PROPOSED GUT SHE		-2.26-2.4
#5 PROPOSED CUT SITE	C2.63	2.6 - 2.75
#6 PROPOSED ACCESS TRACK		
#7 PROPOSED CUT SITE	C3.64	3.6 - 3.9
#8 PROPOSED CUT SITE	C4.22	4.2 - 4.4
#9 INSPIRATION LOOKOUT		
#10 PROPOSED CUT SITE	C5.08 and C5.29	5.06 - 5.48
#11 PROPOSED CUT SITE	C7.02	7.0 - 7.18
#12 PROPOSED CUT SITE	Wall 40/41	7.4 - 7.5
#13 PHOPOSED CUT SITE	C7.58	7.58 - 7.8
#14 VALLEY CAMPING SITE		
#15 PROPOSED CUT SITE	C8.13	8.1 - 8.25

Note: The Study Team carried out the Visual Assessment in the order described above from north to south over 3 days. Refer to the Methodology below.


Note: On completion of the site assessment the RTA directed the Site #4/Wall 1 was to be excluded from the assessment



#### SCOPE OF WORK



Faller heas are common above the Road cultings due to a combination of steepty inclined rock and sed wash with. This Progressive valuered in crear to stabilised the cuts and to reduce the risk of hower drain code the mod.



and one look cuts are constantly externing leading to the undermining of frees such as this



#### JENOLAN CAVES DOAD, LANDSCAPE BOY VISUAL ASSESSMENT

#### SCOPE OF WORK

#### BACKGROUND DATA

All relevant, available information on the proposal was reviewed including the following data.

- Study Area Map Showing the Proposal as provided with the RTA Brief Ulerostin Cares Houri- Car Shope Hamedicapa, Landscape, and Visual Impact Assessment Prior BTA, December 2004;
- Aenal photograph at the Study area as provided by the RTA.
- Concept Designs for the Proposed Works provided by Golder Associates (as available, for the site assessment 12.01.05).
- Ecology Report, There and Laurer Assessment of Five Sites That Occur Adjacent to Jeneium Cases Reset Jeneium Cases, NSW Learn's Environmental Consultants, May 2004.

#### KNOWN SENSITIVE SHES

Eased on a proliminary review of existing documentation and darabase searches the following consitive sites are known to occur within the vicinity of the sitely area:

- Kanangra Bevel National Park.
- Greater Elijie Mountains Area' schich is a World Heritage listed area.
- Jonolan Karst Conservation Reserve
- . Dry stone walls along Jonolan Cases Coart.

#### ANALYSIS OF EXISTING ENVIRONMEN

A site analysis was undertaken over a 3-day period between the 12th and 14th January 2005 in erder to brialyse and record the existing landscape and visual environment.

Each proposed site within the windy area was assessed inatu against a visual assessment "Proteing" in order to actives, such assessment and

- The existing landscape character.
- A description of existing vegetation.
- A description of the adiacent landiform and
- A typical cross section of the read reserve.

#### The analysis included.

- The significance of existing landscape types (i.e., Fliah, Moderate or Low);
- . The sensitivity of the landscape to alteration by the Proposal
- Viewer sensitivity to afforation by the Proposal for all relevant viewer groups, and
- The significance of existing views and vistas e.g. are the views significant on a local regional, ware indicated a incremental level?

The viewshed was mapped for a minimum distance of one (1) km from each cut sicple, see

#### PURPOSE OF STUD

This landscape and associated to the broad associated by the RTA in determining the effects of the Proposal on the landscape are secural amenity of the strety area, and in the decelopment of appropriate mitigation measures for any identified potential impacts.

It is RTA contention that the land-cape and visual assessment produce one set of working papers which call identity matters ownwrite the study area and satisfy the relevant legislation, policies and guidelines of MSW and the Coronorwealth Governments

UDO

#### LANDSCAPE AND VISUAL ASSESSMENT



#### VISUAL ASSESSMENT METHODOLOGY

#### PROGRAM CONSTRAINTS

A significant feature of this study was the required program. The study was initiated at the end of December 2004, just prior Christmas shut-down period. The Draft Study was required to be completed by 21st January 2005. The following critical cases therefore shaped the adopted methodology,

- The Study Engagement commenced 21st December 2004
- Draft documents for Typical Cut Stope (C1.74) received from Golder Associates C.O.B 22nd December 2004.
- Electronic copy of Ecology Report, plus received from RTA 22nd December 2004.
- C.O.B. 22nd December 2004, 10th January 2005 UDO Christmas shut-down period.
- During the Christmas shut-down period UDO completed the background data review, review of the typical design concept provided by Golders Associates, created the base Study Report, prepared the visual assessment "Proforma" sheets.
- 11th January 2005 briefing reviews with Golders Associates and RTA prior to site assessment.

12th January 2005 Study Team commenced on Site visual assessment. The assessment Team consisted of 2 lands apparatheets, an assessor and a 'spotter/recorder', (A 2-man team that included a 'spotter/was necessary owing to the potential canging out traffic conditions prevailing on this very narrow winding road.) The on-site assessment and analysis was carried out as per the (Scoper of Morky description above and recorded on the pre-prepared 'Proforma' sheets.

- 14th January 2005 Study Team complete on the visual assessment.
- 17th 20th January 2005 complete desk-top visual assessment, photomontage analysis and graft report production
- 21st January 2005 Draft Visual Assessment submitted to RTA for review and comment.

#### ON SITE VISUAL ASSESSMENT

Jenolan Caves Road is a very narrow winding road with many blind corners. OH&S issues were therefore of primary concern when executing the on site visual assessment.

The first day of the site assessment was taken up with travelling to the site from Sydney. On the way into the Study Area an indust assessment was made of the Compound Site. The Study Team then travelled the full extent of the Study Area several times in order to become fully familiar with the general layout and extent of the works within the landscape context. During this initial analysis the team included the order of assessment for the following day.

On Day 2 of the assessment the Study Team commenced at first light in order to avoid traffic. Starting at Cut #1, the highest, the Study ream worked back down towards Jenolan Caves, assessing each work area and lookout in succession.

As each subject area was approached a traffic cone was dropped at the kerbside (or on top of an appropriate fence post) adjacent to the start of the proposed work area. A second cone was dropped at the kerbside adjacent to the end of the proposed work area. The Study Fearn then proceeded back up the road to the next blind corner north of the subject area. The Study Fearn then proceeded slowly back down towards the subject area noting the various view corridors and varitage points along the way. As soon as the start of the work area could be seen (i.e. because the 1st traffic cone was visible) the Study Team commenced a photographic record of the visual assessment. On reaching the each subject area in proposed works (if known) were assessed against the existing visual condition and the assumed extent of impact noted. This method was repeated for each of the subject areas flinduphout the rost of Day 2 until all work areas except for Cuts #9 and #10 had been assessed.

At first light of Day 3, Cuts # 9 and #10 were assessed. Then the rest of the morning was spent reviewing the assessment again working from Cut #1 back down to Cut #10. The Study Team also used this opportunity to confirm and record all of the significant view comidors along the entire Study Area.

Each on site assessment was recorded in draft on the pre-prepared visual assessment *Protorma* sheets. These were later finalises, electronically.

UDO

#### FINDINGS OF LANDSCAPE AND VISUAL ASSESSMENT



#### JEDDEAN CAVESTROAD CALIBOCAPE and VESTAL ASSESSMENT

This Study refers to the neelogy study. Fire and Fauna Assessment of Fire Siles That Occur Adia, vert to Jeresian Cairis Road. Jenuian Causs, ASA1, it carek Fourienmental Consultants), for contirmation of the veget trion typology within the Study area.

The flora and fauna assessment was uncertaken in May 2004 within and in close previously to five of the preposed work areas.

Storiotics Covers Read is formited various a brucker per that is characterised by store to very steep vertexis. The deministrational soils of the stuck area are element from Devenian and Shinan metasediments and volcanics (long-1994). These conset percentived Shinan metasediments and volcanics (long-1994). These conset percentived Shinan metasediments and volcanics Lorins : Lithesoils fon welky steer sienes end ciestst. Brown, Bod and Yollow Perceile Soils fan the Aseas sienes and alkiwat soils along diguage lines (king 1994). These soils have leatility, and are susceptible to say on usite proposit

Natural elevations within the study erea are between 740 and 1150 metros above per level. The annual everage calabates the respect is 966.2 millionates with the createst falls being exercised during the summer menths (Burgar of Metroicles) Janvian Cares 2004), Avenage temperatures range between a winter low of 0.2 Č to a summe hem et 15.6 C discesso et Mesceristers Janeius Caves 2004). Frosts are also common during the winter months (Oberen Council 2005).

Dialogge lines that each downstope of the prepagal works include Jonalan River. Physiciate Nest and Salis Crooks, Cooks. Gully and several unarimed desiracje i harmels . The smaller drainage lines reed into the Amelia Dury, this ever eventually liberary into the Coss Basi. (Skin east of the share usa. The annumed dramage channels are all considered to be observed, which the major means and creeks are perminent water bedies. Each of the changed lines occurs within a catchinent that is deministed the

denotan Grees Boot is sunconclect by a network of know conservation reserves. Unser reserves, or other protected tenes. wichigh the Josepha Ceves Reserve Consessation Area, Blue Alcontains and Kneagana Bow J National Parks and point skinder rails Thropton State Forests. These reserves cover areas of 2360, 264848, 66661, 2607, and 4771 for respectively (Oberen Cours). 2003, NPWS 2004, In relation to the Blue Mountains and Kananara Boya National Parks, these are tweet or a proper of reservois that correlate to the largest conservation area in NSW (Oboren Council 2003).

Jonolan Caves Board haverses Innountian area that is dominated by eucatrot weedkinds. As such, for majority of the provise a rock authrias surport a suito et carve plants, though the species diversity of these is dependent upon the myxicts assectative with the previous rand works activities, and any engoing vagotation maintenance attached recketion schemes.

Me plants or vegesarion communities of national, state or regional conservation significance were recorded or indicated as occurring within the study area. The proposed works are not considered to significantly after thany threatenes) plants or constitution communities, thereby causing them to become locally extrict. No ecological constraints were identified that would impose the

As need in the Floor and France Assessment, Jenelan Caves Road grades from a unior upper slope to a moist gully, with the segistation changing from forest with a tall shirth understoney in the area of the proposed compound site, through to an open lovest structure with a low shruls layer and sparse grass groundcover, to a moist open forest with an uniterstorry of grasses. Clinite of and forms. This immatrion is represented by the varied dominance of the indigenous Eucalyptus alimas. However, the variation for a subtle that to the casual, untrained observer the general character of open forest structure is constant.

The vegetarien communities tapproximate zones occurring within the Study Area:

Between Cuts 1.71 and 5.0k (Wall 1 of Clova and Laura Assessment). Boweren Cuts 5:06 and 7:02 (Mail 15 of Dora and Fauna Assessment). Between Out 7:02 and 7:35 (Wall 30:41 of Tiegrand Favora Assessment): Open Forest of Freship is executable F. treat to

Below Out 7:58 (Mail: 48 of Four and Fana) Assessment:

#### Cleaneri Granner

Open Longst of Encytypias removas: L. repseumen. Open Forest of Electronian various

Open Forest of Consultus evacemendes e. Extractat.



## FINDINGS OF LANDSCAPE AND VISUAL ASSESSMENT



JENGLAN CAVES HOAD, LANDSCAPE, JAIG VISUAL ASSESSED IN

#### EXISTING VEGETATION (CONT)

All of the proposed work sites show signs of disturbance. Past disturbances as a result of the roads construction have resulted in areas of unstable slopes where soil slip continues to create disturbances to the vegetation.

#### COMPOUND SITE

The works compound site is a highly disturbed area and has been previously used as a parking area for fourist coaches and for react materials storage/disposal. Large mounds of old road base and pavement material occur across the site and the area is veget at a by weed species. There is a secure tenced area, containing demountable office and storage sheds, within the compound. Come hardy native species also occur in the disturbed area. The surrounding bushland is vegetated by the native eucallyst face? Open hardy native encountries are grasses and herbs. This faces is not expected to be directly disturbed by the use of the site as a works compound.

#### Common Species

#### lices

Manna Gum Fucallyptus viminalis. Brown Barret Fucallyptus Instigata, Blaxland's Stringybark Fucallyptus blaxlandir and this stirubsamaltine Black Wattle Acada melanoxylon occur in the area surrounding the proposed compound site.

#### Shrubs

Common shrubs are Evolusting Daisy Bracteantha bracteata and Lance-leaved Board heath Leucopegon knockolutes.

#### Groundcovers

Common groundcover species include Spiny Mat-rush Lomandra longitolia, Prickly Starwort Stational pangens. Whilaby Grass Austrodunthonia sp., and Native Tussock Poa kibillandieri.

#### Moores

Groundcover species in the cleared compound area include the weeds Pimpernel Anngallis anvenses, Fernnel Foedictions (Association Control of Co

#### Note: Weed Control

#### 'Denotes exotic weed species.

The compound is bordered by a low berm of site-sail that controls overland flows generated within the site. This fit of discharges off the site through a gap in the berm midway along the western edge, directly opposite a ferred off Wildele-Reserve' about 40m west of the compound. It is evident that weed growth generated within the compound is spreading off-site with the overland flow. We strongly recommend that a shallow detention basin and fifter fabric trap be independent into the overland flow path to reduce the spread of weed growth beyond the compound. This should be done as part of a general weed eradication program for the compound.

#### CUT SLOPE SITE

Each of the proposed work areas displays the very similar landscape character of open forest, with trees to about 10m in height and forming moderate foliage cover. From distant views i.e. outside of the road condor, the foliage cover is generally fairly define screening the road completely. The shrub layer is generally sparse with low shrubs to 1m, occasionally to 3m in height. The groundcover consists of a variable layer of sparse grasses and herbs.

#### Common Species

#### Tree

Thin leaved Stringybark Facelyptus eagenoides and Southern Blue Gum Facelyptus broaders. Manna Gum Facelyptus eagenoides and the tall strubysmall tree Lightwood Acecta implexe.

#### Shrubs

Blackthom Bursaria spinosa, Everlasting Daisy Bracteantha bracteate, River Lomatia Lomatia mivicoides, Fireweed Giscoper Senecio linevidolico. Austral Indigo Indigophora australis, Broad-leaved Hickory Acada talcifornis, Native Cranberry respective strapsa and Large Mock Olive Noteliaea longifolia.

#### Groundcovers

Common groundcover species include Spiny Mat-rush Lomandra longifolia. Prickly Starwort Stellura pringens. Kicher VV or Dichondra repens. Kangaroo Grass Themeda australis. Wallaby Grass Austrodanthonia sp., Prickly Starwort Stellura pringens. Sickle Fern Pelisea falcaria. Maidenhair Fern Adiantum aethiopicum and Necklace Fern Asplanium flabeliticium.

#### Climbers

Old Man's Beard Clematis anstata and Scrambling Lity Geitonopiesium cymosum.



## Landscape and Visual Assessment

JENOLAN CAVES ROAD VISUAL	DATE:	CUT #
ASSESSMENT	January 2005	

Description of Existing Visgotation	Description of Adjacent Landform	Significance of Existing Landscape Type (Low/Medium/High)
Viewer Sensitivity To Alteration by the Proposal (Low/Medium/High)	Significance of Existing Views. (Local/State/Regional/ national/International)	Notes: The viewshed extends beyond 1 km to adjacent peaks and ridgelines (fine weather).
	Viewer Sensitivity To Alteration by the Proposal	Viewer Sensitivity To Alteration by the Proposal  Viewer Sensitivity To Alteration by the Proposal  Significance of Existing Views. (Local/State/Regional national/International)

	VISUAL SENSITIVI	TY	
VISHALLITTE	HIGH	MODERATE	LOW
HKSH	Н		
MODERATE		М	
LOW			L

Last demonstrate Sample Programs Stype!



#### JENOLAN CAVES ROAD TANDOCAPT 500 VISUAL ASSESSMENT

#### VISUAL ASSESSMENT

#### METHODOLOGY VISUAL ASSESSMENT

#### General Approac

The Visual Assessment was unrigitalism by a qualified landscape architect experienced in visual as a scanent. The Assessment took place on 12-14 January 2005 in fine, clear weather conditions of maximum visibility.

It should be noted that scene values after with location and sesting. What may be considered at leaver moderate scene value in one location could be at high scene, value in another. The setting of a proposal is therefore critical in determining its impact on the scene quality and value of the area. Similarly, the visual impact of a proposal will also change over time, as will the proposal militarion enteres. This Visual Assessment has carefully considered all of these aspects.

On visiting the site the relevant visual features were analysed, and recorded on a Proforma sheets (see opposite) including.

- Landscape Character
- Major topographical and geological features.
- Natural landscape features
- Cultural landscaue features
- Visual catchiner
- View compets, vistas ex

This Visual Assessment, determines the construction (short-term) and operational florig term) impacts, that would occur as an effect of the Proposal on its recural surroundings. Adverse impacts can occur, for example, as a result of earthweits or vegetation clearance, the alignment of a read or the siting of a component that is unsympachetic with the surrounding landscape or the use of materials that details from the advantagement plants.

Other aspects considered in our Visual Analysis included.

- Potential destruction or obscuring of existing views for capital users, adjoining owners and morenists.
- Creation of unattractive views such as stockpiles, plant and/or machinery.
- Alterations of the existing aesthetics of localities such as tree lined roads and natural settings.
- Aliconnent and design features, including details such as proposed materials, associated infrastructure and signage, that reinforce or detract from the existing landscape or rural area.

This Visual Assessment includes the fellowing components:

- An analysis of the existing landscape, rural and visual resources to assess:
  - the significance of existing language types (eg. Natural, Cultural,
  - Urbani, Rural esci-
  - sensitivity of the landscape units to alteration by the proposal
  - viewer sansitraty to alteration by the proposal
  - aquificance of existing cross and vista
- An ascessment of impacts identifying the potential impacts on the existing landscape/rural/stand resource if the proposal processes. The level of impact is based on the relative assessment of the significance of existing landscape/rural visual quality.
- Proposed strategies to minerate adverse impacts and improve the existing landscape rural visual resource.

A description of the visual implact of the Proposal activity requires an assessment of the scenic quality and value of the site within its broader landscape context. There levels of scenic quality and value are assessed.

- High careas with visually prominent features of landform, land cover, waterformer built of ments. These may include ascorpments, elevated indyclines, disually significant stands of vegetation, geolegical formations, men parts. Luddings built also received the prominent of the feature in the parts of the
- Medicase: areas with language, or built features which send to be common throughout the region and are not outspanding in visual goality.
- Levy areas with features of minimal diversity or variety.

A photographic record of the site was also made, including

- Panoramic photographs form pensitive and key view points
- Reserve of appearal features
- Record of teatures of particular visual sensitivity
- Fhotographic models, were developed for key view point analysis and hand discent photoers made assessments of the proposal wave applied in order to illustrate the visual assessment.



## Findings of Landscape and Visual Assessment



The stead in 5-a decision allowablest and 5-a along the inclined that distant views to the Frenchian and extendible from a instead auntion of sindiance position when the right of an the appropriate state of the right of the appropriate state of the right of the appropriate section of the right of the appropriate section that a propriation of the right of the right of the appropriate from the entire of the count of the right of the appropriate for one this count of the right of the appropriate for the appropriate for the appropriate for the count of the right of the appropriate for the appropriate fo



The Almas taken the road and so derively allowed and so stoogly modered had distant views to the Physician and early acceptable from a mater manner of warms as within taken the reset is usually of the comments may be shap to encount where the three stooglets of the road warms for the Proposal as of the metally a viewbarm have within the road's control than, and then the early are generally assistants. In the tent the time to all the stooglets are than a war.



#### JENOLAN CAVES ROAD. LANDSCAPE and VISUAL AND ESCAPE

#### SUMMARY OF FINDINGS

#### VIEWER SENSITIVITY AND VIEWSHED

Viewer sensitivity to alteration by the proposed works was assessed for all relevant viewer groups. These were assessed to be almost exclusively users of the Jenolan Caves Road.

The initial assessment of the works confirmed that visual access to the proposed works will be very limited owing to the detail foliage cover provided by existing vegetation both below and above the Jenolan Caves Road, virtually throughout the length of the Study Area.

Where this screening effect is not apparent the resultant view comidors have been noted and are generally framed to restrict clear perpendicular to the road and proposed works. The resultant visual catchment, or viewshed, extends only to the east, well begins 1 km distance (in fine weather) and is captured by the high surrounding ridge lines irefer diagram opposite).

To the west of Jenolan Caves Road the effective viewshed limit is the cut face of the Road itself, generally forming a shoot wall of an average 4m high above the road edge. There is no shoulder, hard or soft. It is possible to see above this vertical limit in leng views up, or down, the road comider as one travels along it. However, even these long views are limited and tramed by the dense vegetation immediately above the rock cut walls.

Where view comdors do exist across narrowly folded valleys to road sections opposite the viewing point the distance is such that the proposed scale of works is too small to observed from a moving car. Usually such view condors are also partially screenes is intermittent vegetation which, particularly when viewed from a moving vantage point, are effectively occluded.

View comdors within the Study Area are therefore almost exclusively confined to the road confider itself and therefore road uses, are the principal viewer group to be considered. This is a reasonable assessment that can be applied throughout the Study Area.

Other possible viewer groups were considered and assessed.

It was concluded that long views back to the road from adjacent high ridges would not provide sufficient visual necess to be of consequence due to the distance (over 1km) and due to the effective screening of the downhill slope vegetation in particular.

Long views up to the road from the camp site in the deep valley below CH7-8 were assessed. It was evident that there was no visual access to the road corridor from this vantage point.

View comdors from each of the existing Lookouts and rest areas within the Study Area were also assessed. If was evident that there was no visual access to the road comdor from these vantage points.

#### DISCUSSION OF POTENTIAL VISUAL IMPACTS OF THE PROPOSAL

#### Construction Phase

Viewer sensitivity to alteration during the proposal during the Construction Phase will depend on the methods adopted and the duration of the works. The existing works (for example, the cantilever bridging section at Wall 48) give us some indication of the potential construction impact. Clearly, the very necessary presence of warning signs, temporary safety tenong and construct in a equipment will have a negative impact upon the road condor for the duration of the works. However, taken in the context of the overall scale of the site and the comparatively small scale of the proposed works, and remembering that, unlike Wall 48; the proposed works will generally be executed above eye level, the overall impact is considered to be Moderate to Low.

#### Operational Phase

Viewer sensitivity to alteration during the Operational Phase will depend on the scale of the proposed works and their leng term offect of upon existing vegetation.


The amount of rock scaling works is limited to small well defined and easily controlled areas (refer to Work Preposal Summary Sheets). The nature of the scaling work is such that within a short time newly revealed rock face will weather to match the existing. The scaling work is generally considered to be of Low Impact.

The proposed rock bolt placements do not exceed of 300 x 300mm plates, and are to be constructed of galvanised stack which will quickly take on a neutral patina. Read against the scale of the average 4m high rock cut these are considered to be of Law Visual Impact.

The proposed rock tences do not exceed a height of 1200mm and are limited to only one Work area (Cut 8.13), one section of approximately 10th Long and another of 15m. Read against the scale of the average 4m high rock cut these are considered to the of Low Visual Impact

The proposed crest work is fairly uniform in extent at each of the cut slopes. It is assumed that the crest work will be limited on plan to within 2 3m of the crest of each cut face. The method of crest work requires careful consideration. Most of the work shower be carried out by experienced plant operators under careful supervision of the coordinating engineer in order control and final face extent of soil and vegetation disruption to the minimum. This said the scale of the work when read against the scale and centarty of the existing vegetation is comparatively small and this work is considered to be of moderate to Low Visual Impact.

UDO



#### RECOMMENDATIONS

Given the relatively small scale of the proposed works together with the dense structure of the existing Lucallyptus forest, obcurrents throughout the Proposel, no long-term rangiation strategies are considered essential. However, the following recommendations are offered.

#### Construction Phase

The Proposal must be is undertaken in an ecologically sustainable manner and each person of the works must be continually maintened with the objective of restricting the physical impacts of the work to the obsolute minimum required to achieve the proposal objectives.


- All areas that occur beyond the liners of the proposed works should be clearly defined on site to create they are not disjurted.
- An Fresien and Sediment Central Plan must be prepared for each out site. This plan should induce the stabilising of exposed surfaces as seen as possible to recince the potential for any crosion. The existing Lesson and Sediment Central Flunter the Compound area must be reviewed and updated to present the spread of weed send along the current overland flow path.
- The Erosion and Sedmentation Control Plans should ensure that no sediment leaves the Proposal sites and that the works
  do not adversely after the revenue containment. In particular care must be taken to ensure that no downsproom washerds
  can occur below the road itself.
- A Weed Eradication and Central Plan should be prepared for each work area and the compound site.
- Each work area should be as as a set after the works are complete to identify the next it any, for planting minimizer in the planting militarity is required to make good any loss of vegetation, the planting palette. Justifying and the endemic plant species for each individual size. The adopted planting palette should consist of a mix of busilyous and uncerstorey shrubs in an appropriate ratio to reflect the excessing plantings. Only tubestock grown on from locally sollected seed should be used.
- Cleared native vegetation should be mulched and used in the sites stabilising works peer treatment.
- Weeds and seed boaring exotic plants that are removed should not be mulched but should be taken to an approved Connot waste facility.
- If a chemical herbicide is used to act in the removal of weed species, a product should be selected that will readily break octor
  and red imposet on burns species.
- Cleared and disturbed areas should be stabilised with suitable native grasses and ground cover plants as soon as possible to provent soil erosion.

#### Operations Phase

- Work awas should be monitored regularly for up to 3 months following completion of the Works to identify any potential less of topsoil and or exceptation upball of the Works due to unforeseen washouts or soil dippage. The need for planting range to a leave accessed at the time.
- The general condition and placement of amonities at the various Lookouts and Rest Area's along the Jonalan Gazos Boad should be reviewed are unon-sted.

#### Legend
















Transfer san foreste constitute the morning a province of management

## VISUAL ASSESSMENT PROFORMA SHEETS

KEY TO VISUAL ASSESSMENT LOCATIONS (from north to south, up to down)

ASSESSMENT SITES	Cut No.	Chamage
COMPOUND SITE # 1		
KATOOMBA VIEW LOOKOUT SITE #	2	
PHOPOSED CUT SITE # 3	C1.74	1.72 - 1.86
PHOPOSED CUT SHE #4		2.26 - 2.4
PROPOSED CUT SITE # 5	C2.63	2.6 - 2.75
ACCESS THACK SITE # 6		
PROPOSED CUT SITE # 7	C3.64	3.6 - 3.9
PHOPOSED CUT SITE # 8	C4.22	4.2 - 4.4
INSPIRATION LOOKOUT SITE # 9		
PROPOSED CUT SITE # 10	C5.08 and C5.29	5.06 - 5.48
PROPOSED CUT SITE # 11	C7:02	7.0 - 7.18
PROPOSED CUT SITE # 12	Wall 40/41	7.4 - 7.5
PROPOSED CUT SITE # 13	C7.58	7.58 - 7.8
VALLEY CAMP SITESITE # 14		
PROPOSED CUT SITE # 15	C8.13	8.1 - 8.25

Note: The Study Team carried out the Visual Assessment in the order described above from north to south over 3 days. Befor to the Methodology below.

Note: On completion of the site assessment the RTA directed the Site #4/Wall 1 was to be excluded from the assessment

## Site # 1/Sheet 1: RTA Storage Compound

JENOLAN CAVES ROAD: LANDISCAPE, and VISUAL ASSESSMENT





RTA Storage Compound- view south



RTA Storage Compound-view north on western side of compound



Compound entry point due south



Compound entry point due north

Existing Landshape Character (4) the Herbit cuscription in text	Description of Existing Vegetation (Refer data) description in text)	Description of Adjacent Landform	Significance of Existing Landscape (Low Medium High)
ate fact, the on or characted section if the roled papers. 1900m above the kindle Appropried via 2-lane to extend, will be passed by dense true appring an beth settle or each from 11th or other Concentration or each transition or each papers are placed and the concentration of the papers are placed and the concentration of the papers are placed and the concentration of the papers.	Frees Evaluation variable, Example of Ethiland and Acader researchy brooker in the great surrounding the proposed compound site. Souther the training and Example on Characterists, Connections in the Composite property include Composite property. Stelling training, Austropational ser, and Paul Industrian.	Generally open forest, no abvicus physical matrices outside matrices outside made comider	HGH
Sensite to a El Sederapia B. Alberation to the Property Constitution (Feb.)	Memor Sentebuty to Alemenor by the Preparation of laste	Significance of Existing Views, Conditional Programal National Informationali	Nores
10%	EOVY to MEDIUM	State/Regional	Site already cleared and in use to some time. Wheel eradication and management pregram required. Site would benefit from additional screen planting at rote, area, rispersively street south.


	VISUAL SENSITIONS		
VISUAL SUBJECT	UIGH	MODERATE	LOW
HER	High	High	Moderate
MODERALL	High	Moderate	Low
LOW	Moderate	Low	Low

#### VISUAL ASSESSMENT SUMMAR

#### Visual Impact. Medicate to Lev

The visual impact of the RTA Compound area is limited to views into the compound for traffic travelling form the south from approx.250m due south of the entry.

This impact should be eliminated by the introduction of native screen planting (minimum 5mx30m) immediately south of the entry area. Refer Sheet 2.











## Landscape and Visual Assessment Proforma Sheet






WA Storage Compound view south




RTA Storage Compound-view north entry position



View east onto stock piles, weed infestation





Location; RTA Compound & Photo position

Wheel Caphiel

Sent temperature of the control of the sent temperature of the sent temperature of the control o

I file, en a Misser si Than of a sector secting short repaired and suckettern the scuttern approach jiella. Shout 1 photo #4 and pluster as a bound.

Vesses as a the range or diseased seals scarced from this wholespecial by planting an zine of native screen pluring the state of each special purposent and so the state of an artist special purposent special production scale and public would be contained by effects to describe the state of public would be contained by efficient







#### Site #2: Katoomba View Lookout

JENOLAN CAVES BOAD, LANDSCAPE and VISUAL ASSESSMENT



Katoomba Lookout- view east



Kaloomba Lookout- view south



Extent of viewshed (Approx.30 degree view corridor)



Katoomba Lookout facilities

VISUAL ANALYSIS			
Existina Exista ape Character differ detail description in texti	Description of Existing Vegetation (Reter detail description in text)	Liescoption of Adjacent Landform	Significance of Existing Lanciscape (Low Medium High)
Sterp to ber, steep wakes, sterp of its steps and crests. Ebselfions between viril and 1160 matrics above the first of the sterp of the steep of deep selface, mosted with a bystem of under a property of the steep	Open raiest of up to 10m high trees: Europpias broastata, E. biodenda. Europavaiden, E. ricenatis, and Acade europa. Understorre of 2m-3m high shrubs, og Blockthom, Broad-barved Hickory Cramon groundcover species include Lomandre, natives grasses and teins.	Steep to view steep villeys, strep rocky stepes and creats. Elevations between 740 and 1150 metres above sep level.	High
Residuals of Landscape to Africation to the Proposet direct Medicin Mich	Vewer Scholidity to Alteration by the Proposal Cow Madison High	Organization of Existing Views Local State Regional National International	Notes.
LOW	LOW to MEDILIM	National/Inforustional	Sitting area require weed enableation program, new furniture and general tidy-up.

	VISUAL DESSITIVITY		
ARTIN (TITE)	FOCA+	MURRAIL	LOW
HGH	High	High	Moderate
A. F. M. M. + (A. F.)	High	Moderate	Low
(7)3	Moderate	Low	Low


#### VISUAL ASSESSMENT SHAMARY

#### VISUAL IMPACT OF PROPOSAL LOV

An assessment was made of the proposal from the vantage point of this popular lookout in order to establish which, if any, of the proposed works could be seen from this vantage point.

Views out from Katoomba Lookout are framed by existing dense tree foliage to about 30 degrees. None of the proposed works were visible within this view corridor.

However, the Lookout would benefit from the addition of new, and more sensitively sited furniture, and a general tidy up.











## Landscape and Visual Assessment Proforma Sheet



C. 1.74- view south along Jonalan Caves Road



C.1.74- partial view to visual catchment (view south along Jenolan Caves Road)



C 1 74- view south along Jenelan Caves Read



C 1.14-1	new north a	ilong Jenokin	Caves Hoad
----------	-------------	---------------	------------


terphological adjustance with more tra-	Extend of the send Extractly Viscostations	Description of well-conditions	Sapata are est Exeding Lands upe
ethalis (Astalish semplement test)	(the figure 1 to the prophers in text)	Note of Mary or such your and ware	Law Median High
expension and the form the subject of the form of the subject of t	Likelia de deligione L'ambre dino. A live deligi	Haupe to consider water, doeps - XP Super and state the chains to the state ARC and That necessations - Chairman	1 (0.2) (
Care diale of the other que to even in in- ter the Propertial Cove Wealant, Phylo	Volumer Secondarity by effections by the Perspectal, theory Michigan I begin	Segration records to a fine of view of the Segration of the Segration Mathematical tests continuously	Notes.
CONSTRUCTION PHASE. COVY - MEDIUM	LOW to MILDIUM	Notional International	
OPERATION PHASE, LOW			


VISUAL EFFECT	VISUAL SENSITIVITY		
	HCd+	MODERATE	LOVV
HOH	High	High	Moderate
MODERATE	High	Moderate	Low
LUVV	Moderate	Low	Low

## VISUAL ASSESSMENT SUMMARY LOW VISUAL IMPACT

Proposed crest work will remove vegetation along the immediate lip of the cut. However, the depth of vegetation cover behind this is extensive and fairly dense. There is no significant scaling work proposed.

The proposal is therefore unlikely to have a significant long term effect.


















C 174- New South onto cut one just above the actual cut section




C 1.74- view north onto cut one from just below the actual cut section



C.1. 4. view wast onto start of cut section



C 1.74- view south- fallen vegetation




Legend

New your & technilers

JENOLAN CAVES ROAD







**GOLDERS WORKSHEET C 1.74** 




C2 63- view south along Jenolan Caves road . Note: Dense foliage below road screens-proposal.




C 2.63- view north along Jenolan Caves road



C 2.63- view north along Jenolan Caves road



C 2.604 view south along Jenolan Caves road



C 2.63- view north along Jenolan Caves road

MISHAL ANALYSIS			
Existing Carollacings Character Right ideast description in taxt	Description of Existing Vegetation (Rider detail description in toxt)	Lescription or Adjacent Landform	Significance of Existing Landscape (Low/Medium/Flight
state to time, state valleys, state time, actives and directs, bloodings at time above and time above as time and an interest and an interest and a system at time actives a state, and actives a state, and actives and actives and actives and actives and actives and active active and active ac	Open tarest of up to 10m high trees: Exculpation Standards, E. Wittender, and Academ applica. Understand of 2m-3m high shoulds, ay Blackhain, Brack-leaved Hickory Common groundcover species include Lomanded, natives grasses and terms.	Steep to very steep velleys, steep rocky slopes and crosts, Elevations between 740 and 1150 metres above sea level	HIGH
Scientists, of Lands, opens Albustion to the Proposest of a Northern Highs	Viewar Sensitivity to Alteration by the Coopes if I can Madium thicks	Scentisouro of Existing Viscos duesal State Regiment National International	Notes.
CONSTRUCTION PLASE LOW - MEDIUM	LOW to MEDIUM	National/International	
CINETATION CHARE.			


	OF IMPACT		
VISUAL FIFECT	MRUAL SENSITIVITY		
	HOH	MOLERAIL	LOW
HIGH	High	High	Moderate
MOORBATE	High	Moderate	Low
LOW	Moderate	Low	Low

VISUAL ASSESSMENT SUMMARY

FOW ARETHE IMPAC

This site is 150m long, and is typical of the rest of the proposed work package. Seen in the context of the scale of the surrounding landscape the proposal presents a low visual impact.

The scale of the proposed rock scaling is small compared with other sites. There are a number of closely grouped rock bolts that could create a moderate to low negative impact in the short term. Over time it is expected that thes will take on a neutral patina and not present a long term negative impact.















CONTRACTOR SERVICE




C 2.63- view north along Jenolan Caves road



C.2.63- wew-south



C.2.03- view nort














**GOLDERS WORKSHEET C 2.63** 





Access track - view south forstant shot a Dong



Acres to the Land South (100)



Access track, wow south, proposed entry point




Access track- view north west- under mined tree

VISUAL ANALYSIS			
r sentral for ethic que observation. Obtain electual de la policie de lest,	Description of Execute Verpladier. Ender Stilled Georgidian in Rest;	Demographen of Adjournal Constrain	Significance of Existing Cardscape et rev Mexicon (Tigt)
trope of the second of the sec	Les Profes Describe	often to any those shape of a person of the	) liCa) i
in that the of the prior great works and to be the frequency of the place of the pl	We want to smally decide to Albert de Leeby that the appropriate control budge	<ul> <li>(a) bittories, of Detains, Verwey,</li> <li>(b) Cold of Details of Main and</li> <li>(c) For expected</li> </ul>	iest
1 BC at 1	(IR.a) L	Psydical Albumpia and a d	Progress the attent of works access track to top of C. and Assumed width Islan.

VISUAL EFFECT	VISUAL SENSITIVITY		
	HIGH	MODERATE	LOW
HCall	Н	Н	М
MODERATE	Н	M	L
LOV	M	L	L

#### VISUAL ASSESSMENT SUMMARY

Proposed access track to top of C364 requires happir carthworks and loss of vegetation argund the spin Elevation (500m). The track would have substantially more impact than any of the proposed cuts, and impacts would be highly visible to vehicles approaching downhill from 200m+ and uphill from approx. CHS 00. The degree of visual impact would be (very) High.



Location: Access track & Photo position

Legend

Varietand dought from

JENOLAN CAVES ROAD

Lety of themselves (Charle)
 Figure (Livery pressure)

1. ffroito locutico & number INA Seorago compound






C 3 64- view south-east along Jenolan Caves Road



C 3.64- view north along Jendlan Caves Road



C 3.64 view south along Jenolan Caves Road



C 3.64- view north along Jenolan Caves Road

VISUAL ANALYSIS			
Exhibits Landscape Christoter Helio detail description in texts	Description of Existing Vegetation (Rote) detail description in lexit	Description of Adjacent Landto-m.	Significance of Existing Landscape (Low/Modium/High)
Study to every steep volleys, steep valves, appearand creats blevotrons between MD and 11:00 matrix above too every steep massed with a system to accept a system to accept which a system to accept which a system to accept when to accept and accept when to accept and accept and accept which because some acceptance and present which promise acceptance and acceptance acceptance and acceptance acceptance and acceptance acceptance and acceptance acceptance acceptance and acceptance	Open forest of up to 10m high frees; Examples blankmelli. Examples and Alacen imploya. Understorey of 2m-3m high shrubs, op. Blackfrom, Bread-laved Hickory Cramma groundsover spaces include Lamphilia, indires grasses and tems.	Steep to very steep velleys, steep rocky slopes and crests. Elevations between 740 and 1150 metros above sea level.	HIGH
Sensitive of Leading well to Alteretion in mostly ground in the Novice of Thems	Vince Sonsitivity to Alteration by the Proposal it are Maximo Users	Signer ance of Existing Virgos (Lor, d'Sinto Regional 'National Informational)	News
CONSTRUCTION OF IASE.  149 THE METHOD OF IASE.  149 SEA THAN PETASE.	LOW to MEDIUM	National/fotomational	


VISUALTHECT	VISUAL SENSITEMEY		
	HIGH	MODERATE	LOW
HIGH	High	High	Moderate
MODERATE	High	Moderate	Low
LOW	Moderate	Low	Low

At the time of this assessment no details were available for C 3.64. The current proposal assumes that the work will

be accessed via a track just to the north of C 3.64. This access track would create a FIGH visual impact and it is strongly recommended that other methods of achieving the necessary work be considered.

For example, the proposed works could be achieved by hand from above the cut, or using light weight bob-cats loisted up to that position form the road.

Provided the work can accessed in this way the proposal is insidered to be of low potential impact.




















C 3.64 - view north



C 3.64- view south

















C 4.22- view south along Jenolan Caves road



C 4.22- view north along Jenoton Caves road



C 4.22 view south along Jenolan Caves road




C 4.22 - view north along Jenolan Caves road

WELLAL ANALYSIS			
evisting Lindscape Character istate, and discappion in toxic	Description of Existing Vegetation (Robor detail description in text)	Description of Advicent Landform	Significance of Existing Landscape (Low Madium High)
about it view steep valleys, starp in a process and views. Elementors in severe in 70 and 1150 motions observed the control Hood controls a series of severe classes, instead with a resteem of septembers, instead with a resteem of septembers to books. Undiscape dependent of the prestment about excellent are class.	Open torest at up to 10m high trees; Liceasystes Machanin, & veninalia, and Acquire impease. Understores of 2m-sin high shribs; or; Bhosthiam, Broad-leaved Hickory Common groundcover species include Lomandre, natives grasses and turns.	Step to very step valleys, step rocky slopes and arests. Elevations between 740 and 1150 metres above sea level	EHIGI E
Sensitives of Langhdappe Co-Alterations by the Proposed is sen Medical Hints	Miscos Sensitiaty to Alforation by the Proposal 10 no Modium Hobil	Signerance of Existing Meyers (Local State Regional National International)	Notes
ONSTRUCTION PHASE ONE MEDITION OF ERATION PHASE	LOW IS MEDIUM	National International	

VISUALITATION	MEDIAL SENSITIVITY		
	HIGH	MODERATE	TOM
1.853.1	High	High	Moderate
MORRENA	High	Moderate	Low
LOW	Moderate	Low	Low

Although this site is 200m long, slightly longer than the average proposal, the scale of the proposal is typical of the whole package of work. Seen in the context of the scale of the surrounding landscape the proposal presents minimal impact. Refer to Photo #3 on Sheet 2 of C 4.2. This image dramatically illustrates the true scale of the Proposal in its






















C.4.22 were west from Mount Inspiration Lookout



Location: C 4.22 & Photo position















GOLDERS WORKSHEET C 4.22. Sheet 1 of 2





GOLDERS WORKSHEET C 4.22. Sheet 2 of 2

#### Site #9: Inspiration Lookout

JENOLAN CAVES BOAD, LANDOSAPE and VISUAL ASSESSMENT

#### Landscape and Visual Assessment Proforma Sheet





Inspiration Lookout- view southeast



Inspiration Lookout- view south from road approach



Preximity of Lookout to C 4.22

VISHAL ANALYSIS			
Foresting Londscape Character Refer defort description in texts	Description of Existing Vegetation (Beloi, dotal description in text)	Dascription of Adenoni Landiorni	Significance at Existing Land, capi- if ow Medium 1 hold
store to limit study valleys, attago- pine at pie, and prests. Elevations, between 30 and 1150 matres above less level. Braid overlooks a sense at frag lickings, incisod with a system a randerin upharmeral stractic and a construct water foores. Consissape few restales, passing natural arrestages	Open forest of up to 10m high trees; Executarities beautaful E. Elbaviarelle, E cogenocies, E. ventivalle, and Actual inspara. Understored of 2m-3m high shouts, en. Blacktnorn, Broad-feaved Hickory Common groundcover species include Lemandra, natices outsides and terns.	Shap to very steep veltoys, steep rooks steep and ordsts. Elevations butween 740 and 1150 metres above sea level.	LIIGH
Densitivity of Lands, use to Alteration to the Merchanism to the Merchanism.	Viewer Sensitivity to Attended by the Proposal 1. ce/Medium 1 feb	Significance of Existing Views (Local Strate-Region of National Informational)	Notes.
CONSTRUCTION PHASE, HOW OPERATION PHASE, LOW	LOW to MEDIUM	National/luterestional	Sitting area require weed cradication program, new furniture and general tidy-up


ASSESSMENT OF IMPACT			
MSGAL FEBRUAR	MENAL OF MEMBERS		
	118.41	2,900E134.11	LOW
10%	High	High	Moderate
MERITAL	High	Moderate	Low
LOW	Moderate	Low	Low

NOTE:

NOTE: An assessment was made of the proposal from the vantage point of this popular lookout in order to establish which, if any, of the proposed works could be seen from this van-

Views out from Inspiration Lookout are framed by existing , dense tree foliage to about 60 degrees. None of the proposed works were visible within this view corridor.

However, the Lookout would benefit from the addition of new, and more sensitively sited furniture, and a general tidy up. (Refer also. Site 8)
















C.5.08- view south along Jerickin Cines Rout - 150m to cut section



C.5.08 view east around hairpin bend section



C5.08- weer south along start of out section



C 5 08 view north along Jenolan Caves Road


VIDUAL ANALYSIS			
t sniwng turken qui China a ter (1949 a detail che, riginali er text)	Discoupling of Explain programming the property of the strain of the complete and text.	. Кол Тара че да жефилент С. да Ледо (в	ca jede, and b. Alt stating Lankbasapte d. ox (Author) Hejry
them to do they offer day  is a present out of the days  remain offer of the days  is need enable to be a marker of  trape them to wide out on their  charges classes of the control of the  remains out of days. I make you  denote the profession according  and the	Lookette erection and station and station and station Universities of Pin-Surface statuts, or pile with in the address of the bay tourness around trade species include.	Steep to vary steep edition of the steep the by Steppe of any simple the County 40 and the County 40 and the County 40 and the County and steep the steep	i Rica I
percentaged by the graphs wherear or over that Proposed of row Machines English	System Secondfolly to substitute (fig.) They will a sportherment legal	completion of the drap week.  Local distribution action Malparage.  Interest advantable.	Physics .
CONSTRUCTION PLASE. LOW - MEDIUM OFERATION PLASE. LOW	Ly NV to Miller HV	So the model the tractioning	

VISUAL EFFECT	VISUAL SENSITIVITY		
	1 HCP 1	MODERATE	LOW
FRCA F	High	High	Moderate
MODERATE	High	Moderate	Low
LOW	Moderate	Low	Low

VISUAL ASSESSMENT SUMMARY MODERATE TO LOW VISUAL IMPACT

Details of proposed cut section C5.250 - C5.360 were not available at the time of the site assessment. This section contains scaling work above the normal line of crest work that could have a Moderate Impact, thus raising the overall score from Low, to Moderate to Low.

However, if the scaling work is carefully managed to minimise disruption to the vegetation line above the crest the overall impact could be maintained as Modurate to Low.
















CEOR- UPW SOUTH C 5380




C 5.08- detail west on bend section



O.S. O.S. PROM. SOUT



C 5.08- view across valley to C 4.22



JENGLAN CAVES BOOK LANDSCAPE and VESTAL AGGLESMENT


Location; C 5.08 & Photo position












**GOLDERS WORKSHEET C 5.08** 





**GOLDERS WORKSHEET C 5.29** 

#### JENOLAN CAVES ROAD: LANDSCAPE and VISUAL ASSESSMELL

#### Landscape and Visual Assessment Proforma Sheet



Clifich were sentil short torrethin Cover floor.



C7.02- view south (east) just below cut section



C.2 d. yew south towrards cut section (distant).




C 7.02 view north along Jenolan Caves Road

Description of Estating Project Action to the Control of the Control of Contr	Convergings of Astyla unit Landluidi.	Significance of Existing Landscape (Lave MedicaryFligh)
Continue to the Continue to th	Charge to the stone of the Lieuthons to the Lieuthons between 500 and 11hr medical Charge are, but t	HGi I
Version Strongers subtraction des Estate and described high	regula, maarsa tee feet varse - a on dietate bleegewyk Matrikaa listerwisking	The decision
CONTRACTOR	National historialismal	
	dictar des armos replantaciones  operativos del factorios del free  orden del control del free del control  orden del free del control  torden d	The first design of the control of t

	VISUAL SENSITIVITY		
VISUAL EFFECT	FIICH	MODERATE	LOW
HIGH	High	High	Moderate
MODERATE	High	Moderate	Low
LOW	Moderate	Low	Low

LOW VISUAL IMPACT

The proposed work is crest work at C 7.16 and C 7.17 represents a major work area. However, most of the material to be removed appears to be fairly loose topsoil and herbaceous vegetation. There are a number of trees potentially affected by the work, but as the photographs demonstrate there is sufficient and substantial tree cover to maintain a solid screen of foliage after the proposed works, as is generally the case throughout the proposal.



Location; C 7.02 & Photo position












27.02 page 201th




C 7.02- view north





C 7.02- view north
















**GOLDERS WORKSHEET C 7.02** 



C 7.4 view south from C 7380



C 7.4- detail of rock tace that may require scaling and rock bolts



C 7.4- view north from end of Wall 40:41



17.4 view south from approx. C 7400



C 7.4- detail of unstable tree that may require removal



C 7.4 view north from approx. C 7500


VISIJAL AMALYSIS			
existence of stransport in text	Description of Existing Vegetation (Refer detail description in fext)	Description of Adjacent Landfrein	Segnificance of Existent Landscape Cow Modium Highs
they in the steep without steep with the steep with the steep with the steep steep with the steep steep with the steep s	Open rolest at up to 10m high treas. Executablish Trensfollins, Evergementes and Acades manches. The treates yet 2m-3m high shrubs, ay, Utlack them, Broad-Teawad Hickory. Common groundcaver openies include Locusados, natives grantes and terro.	Stop to very streep volkers, stopp rocky stopps and drests, blavitions between 740 and 1150 metres above shallows.	ERICLE
Septimes of Linefscape in Afteration to the Everyoral dissect from the first terms.	Microsoft Sonstrolly To Alteration by the Proposal (flow Medium Flich)	Significace of Existing Views it ocal State-Regional National Interestings	Notes.
1000	LOW to MEDIUM	National/International	

VISIAL TELE	VER IN SEMERINEY		
	111721	VRAM HUTE	LOW
+ BC2/-1	High	High	Moderate
MODERATE	High	Moderate	Low
LOW	Moderate	Low	Low

#### MISHA: ASSESSMENT SHMMARY

LOW VISUAL IMPAC

At the time of the on site assessment no details were available for Wall 40/41, C.7.4. However, an assessment was made based on the scale of work detailed for the other sites. It was assumed that most of the proposed work would consist of crest work to tidy up and remove unstable material/ vogetation, rock face scaling and rock bolts. This a relatively short section of cut face of only 100m.
















**GOLDERS WORKSHEET C 7.4** 

JENOLAN CAVES ROAD: LANDSCAPL and VISUAL ASSESSMENT

#### Landscape and Visual Assessment Proforma Sheet



C 7 58- view east towards visual catchment



C 7.58- view north



C 7.58- view south towards cut section



C 7.58- view north along Jenolan Caves Road


VISUAL ANALYSIS			
Existing Landscape Character Strug, defail description in toxil)	Discription of Existing Vagetation (Rater detail description in text)	Description of Adirocent Landform	Significance of Existing Landscape (Low Modium 1 light
Situate to viny steep relieval, sharp was steep and arrasts. Lieuterins a steep of the steep steep of the ste	Open forest at up to 10m high trides: Lessaharbis threvelata, Europenantes : and Acade kanalana. Understorev of 2m-3m high shrubs; in Blackthern, broad-lineved Heikery Common groundcover ascends include Lemandra, include grasses and terns.	Steep to very steep valleys, steep rocky slopes and creats. Elsystems between 740 and 1150 matres above sea layer.	FIIGH
Sections of Londor, ope to Africation to the PROposit Loss Mexicos Highs	Survey Straits to 15 Alteration by the Proposal it are Medium Hotil	Significance of Existing Views (Local State Resional Matricel International)	Ned, et.
CONSTRUCTION PHASE.  EVAN MEDIUM  OBERATION PHASE.  CON	LOW to MEDIUM	National informational	

MISUAL HITTE	VISUAL SENSIBIVEY		
	1.000.1	MODERATE	LOW
( RG) I	High	High	Moderate
MODEPAR	High	Moderate	Low
LOMA	Moderate	Low	Low

VISUAL ASSESSMENT SUMMAR

This section is longer than the average at 220m and the cut faces are quite high. However, the proposal, which consists of rock holts, crest and scaling works, is comparatively small in scale when compared with the landscape context. The apparently large areas of scaling in Photograph 1 above would have little impact as they will effectively have the same appearance of bare rock on completion.

As with the other cuts, the net result of the proposal will be to slightly after the existing combination of elements rather than make a major change.

















C 7.58 view porth from C 7760



C 7.58 view south from C 7770 . No work details available at time of assessment


















GOLDERS WORKSHEET C 7.58 SHEET 1 of 2





GOLDERS WORKSHEET C 7.58 SHEET 2 of 2





General View to Mount Inspiration Lookout

VISUAL ANALYSIS			
(Section 1) indiscape Character States should do coption in text)	Description of Existing Vegetation (Report data)! description in text)	Description of Adjacent Landlown	Significance of Existing Landscape Low Medium Hight
Steep to say steep entrys, steep as Styles and prests bloedions or styles and prests bloedions are been 740 and 1150 matrixs blove see the fitted available a sense of field available a system of existent enterminal streams and protection with budies. Landscape of entry to peruling returnal decally of available to peruling returnal decally of available.	Open forest of up to 10m high trees: LinealApitus Dicrestata, Elegerorides , Elegerorides, and Acade implicia. Understoray of 2m-3m high strubs; og. Blackthorn, Braad-legved Hickory Common groundcover species include Lamandra, nativos grassos and torns.	Steep to very steep valleys, steep rocky slopes and crests, Elevations between 740 and 1160 metres above sea level.	( HG( )
Sensitely of Landscape to Aferation by the Project I green Macham Highli	Viewer Sensitivity To Alteration by the Proposal If ow Machine Holi-	Significance of Existing Views (Local State Regional National International	Notes
CONSTRUCTION PLASE. LOW OPERATION PLASE. FOW	LOW to MEDIUM	National/International	Sitting area require weed gradication program, new furniture and general tidy-up.



View to Mount Inspiration Lookout - detail



General View to Mount Inspiration


ASSESSMENT OF IMPACT			
VESTAL FILLER	DESIGN SAMELINALLA		
	HIGH	VACADE ESVIT	LOW
18031	High	High	Moderate
MODERAIL	High	Moderate	Low
LOW	Moderate	Low	Low

### VISUAL ASSESSMENT SUMMARN

VISUAL IMPACT OF PROPOSAL

The campsite is approx. 150m below C. 7000. An assessment was made of the proposal from the vantage point of this popular campsite in order to establish which, if any, of the proposed works could be seen from this vantage point.

Views out from the campsite are framed by existing , dense tree foliage to about 60 degrees. None of the proposed works were visible within this view corridor.



Site #14: Valley Camping Area

JENOLAN CAVES ROAD HANDSCAPT, and VISHAL ASSESSMENT









#### JUNOLAN CAVES HOAD, LANDSCAPE and VISUAL ASSESSMENT

#### Landscape and Visual Assessment Proforma Sheet





CR 13- view south towards Jenokin caves



C 8.13- view north along Jenolan Caves road



C.S. L.C. previ south towards start of out section.




VISUAL ANALYSIS			
bording Careto que cheración (talen talent description de text)	Description of Existing Vegetation (1994) detect description in texts	the suptom of Adjusters Landh on	Segrateration of Executing Carobic appointment Administration (Egy)
where it is a standard order, it is a series of the Paper and the first end of a series to the series of the first end of the	Cases, ones, trapis, territaristicos, for carante remaining a requirement of a carante construction of the carante construction of the carante construction of the carante carante carante construction of the carante	cultrap to see strong calleys strong station displace and mestic elevations, sociations with stat 11 statinetics, above was known	FIRAT
Screening of Landa and territoring by the Proposal discommedical light	Victor Consultedly 10 Million high by the 13 period. it cossistion (13 by).	or pulse and a good first divergence.  Lower March of the properties of Albertach  Industrial properties.	Nate:
CONSTRUCTION PLASE, COW - MEDIUM OPERATION PLASE, LOW	LOW G MELICIA	Parties of International	

OF IMPACT		
VISUAL SENSITIVITY		
FIICH	MODERATE	LOW
High	High	Moderate
High	Moderate	Low
Moderate	Low	Low
	VISUAL SEL FIIGH High High	High High High Moderate

At the time of the on site assessment a number of recently felled trees were noted within the site area with no apparent loss of visual quality or apparent impact upon the landscape character of the site. (It was also noted that it may would be beneticial to trim back or remove selected trees in order to open up views to certain landscape features -in particular the views up to the Carlotta Arch.

Photographs 2 and 4 on Sheet #2 illustrate this.



Location: C 8.13 & Photo position




















Orthophoto Map of Study Area

UDO



C 3.26- view south along Jenolan Caves Road



C 2.26- view north along Jonolan Caves Road



C 126 view south along Jenolan Caves Road




C 2.26- view north along Jenolan Caves Road


VISUAL ANALYSIS			
Larving Limitscape Objector Fire Locatal description in text	Description of Existing Vigeration (Refer detail description in text)	Description of Adjacent Landrenn	Significance of Existing Landbezgo (Low/Modium/High)
M. in the environmentary, steep 1.1, steep and creats blevations of the matter above a first Polya creatops to the protops of the matter and the protops of the matter and the section of the matter and the today. Landscape of the period of t	Open terest et up to 10in high frees; Erwangetes blankmelk, E-vanendes and Actoin miplona. Understorey of 2in-3in high shrubs, eg. Blacktham, Broad-looved Hickory Common groundcover species include Lominidite, nativas grassas and teins.	Strep to very steep valleys, steep rocky slopes and crests. Elevations between 740 and 1150 metrus above sea level.	HIGH
in deals of Lander see to Alteration is the Proposit for Michael Richy	Viewer Sensitivity To Alteration by the Proposal (Low/Medium-High)	Significance of Existing Views. (Local/State/Regional/ National/ International)	Notes:
100	LOW to MEDIUM	National/International	

VISITAL FORM	MEDIAL SERVICE AND THE PROPERTY.		
	FROIT	RATE DE DATE	LOW
THOR	High	High	Moderate
MODERALE	High	Moderate	Low
LOW	Moderate	Low	Low

VISUAL ASSESSMENT SUMMARY

At the time of the on site assessment no details were available for Wall 1. C 2.26. However, an assessment was made based on the scale of work detailed for the other sites. It was assumed that most of the proposed work would consist of crest work to tidy up and remove unstable material/vegetation, rock face scaling and rock bolts. This a relatively short section of cut face of only 140m.


































# **Appendix C** Photographs of Proposal site

## SITE PHOTOGRAPHS – JENOLAN CAVES ROAD









# Appendix D Concept Design

Golder Associates Pty Ltd A.B.N. 64 006 107 857

88 Chandos Street St Leonards, NSW 2065, Australia (PO Box 1302, Crows Nest, NSW 1585) Telephone (02) 9478 3900 Fax (02) 9478 3901 http://www.golder.com



### DRAFT REPORT ON

# DESIGN OF SLOPE REMEDIATION WORKS MR 253 JENOLAN CAVES ROAD

Submitted to:

Roads and Traffic Authority Western Region 15-33 Cooerwul Road Bowenfels NSW 2790

### DISTRIBUTION:

2 Copies - Roads and Traffic Authority (electronic)

1 Copy - Golder Associates Pty Ltd

18 February 2005

04622081/007 (draft)

### TABLE OF CONTENTS

SEC	TION		PAGE
1.0	INTF	RODUCTION	2
2.0		HODOLOGY	
	2.1	Survey	3
	2.2	Photography	
	2.3	Remediation Assessment	3
	2.4	Additional Geotechnical Investigations	3
	2.5	Engineering Analyses and Design	4
	2.6	Design Documentation	4
	2.7	Remediation Works Cost Estimates	4
	2.8	Co-ordination meetings with RTA	4
3.0	DES	IGN APPROACH	
	3.1	Design Objectives	5
	3.2	Design Constraints and Philosophy	5
	3.3	Design Life	5
	3.4	Types of Remediation	6
	3.5	Tree Hazard	6
4.0	CON	ISTRUCTION WORKS	7
	4.1	Client's Geotechnical Representative	7
	4.2	Management Plans	7
	43	Standards and Specifications	7

### LIST OF DRAWINGS

A list of drawings is provided on Drawing no. 081D001 which follows the text of this report

### 1.0 INTRODUCTION

This report describes the development of the detailed design of proposed slope remediation works for nine rock cuts along MR253 Jenolan Caves Road. The designs are presented on a series of drawings presented with this report.

The remediation is to be undertaken as part of an ongoing program of improving the Assessed Risk Level (ARL) of selected cuttings and embankments along Jenolan Caves Road to ARL 3 or better. The work is along a section of Jenolan Caves Road known as "5 Mile Hill".

The design work was carried out by Golder Associates in accordance with the RTA brief issued by email dated 24 May 2004 and our proposal 03622122/005 dated 4 June 2004. The work was authorised by PJ Dearden in a letter dated 21 July 2004.

This report addresses the detailed design of nine cuttings, referenced C1.74, C2.63, C4.22, C5.08, C5.29, C7.02, C7.44, C7.58 and C8.13. These nine cuttings were selected following slope risk assessments (SRA) carried out by Golder Associates in 2002 and 2005 (C7.44). Eight of these cuts had an ARL of 2, one an ARL of 1 (C5.29). The SRAs were in accordance with the RTA's Slope Risk Analysis Manual Version 3.1. The location of the rock cuts is illustrated in Drawing 081D001.

The SRAs carried out in 2002 were presented in Golder Associates' report ref. 02622010/011 dated September 2002. Additional SRAs were carried out in January 2005 for two cuttings (C2.27 and C7.44) recently regraded by the RTA (2004) as part of the remediation works of drystone retaining walls along Jenolan Caves Road. An ARL of 2 to 3 was assigned to C7.44. The SRA indicated an ARL of 4 or better for C2.27, and hence remediation of C2.27 is not required. The 2005 SRAs are presented in Golder Associates' report ref. 04622081/08 dated February 2005.

In addition to the eight cuts included as an outcome of the SRAs in 2002 an additional cut (C3.64) is also to be remediated. C3.64 has an ARL of 1 but is significantly larger than the other cuts and is to be addressed in a separate design package.

In 2003 Golder Associates carried out concept designs for the nine rock cuts assessed in 2002 (Concept Design, Remediation Work For Rock Cuts, MR253 Jenolan Caves Rd, December 2003, report ref. 03622122/02). The concepts were discussed at a Value Management Workshop held at Jenolan Caves in January 2004.

The reference system for cut sites used by Golder Associates was described in our report ref. 02622010/011 dated September 2002. The reference refers to the distance of the uphill end of the cut from the top of 5 Mile Hill (in kilometres) measured in relation to chainage markers installed by the RTA.

### 2.0 METHODOLOGY

The methodology for the development of the slope remediation designs of the nine rock cuts is described in this section of the report.

### 2.1 Survey

As requested by Golder Associates, the RTA set out chainage markers along the centre line of the road at 10 m intervals at each of the cuttings to be remediated. The chainages are referenced in relation to the white chainage markers at the edge of the road installed several years ago by the RTA. Chainage 0 is at the top of the section known as "5 Mile Hill". In addition, the RTA sprayed chainage marks on the cuttings at 10 m intervals.

Golder Associates has also used longitudinal sections and plans developed by the RTA from a survey carried out by the RTA in 2004.

### 2.2 Photography

A geotechnical engineer photographed each of the cuttings with a digital camera. The objective of the photographs was to develop a base on which to illustrate the proposed remediation works.

The photographs were taken perpendicular to the face. As the distance between the cuttings and the far edge (downslope edge) of the road was generally not more than about 6 m, a series of photographs were taken to cover the extents of each of the cuttings. These photographs were then spliced together to form photomosaics.

To assist in the detailed design oblique aerial photographs of each of the cuttings were obtained from a helicopter. The photographs were taken using a high resolution digital camera by a professional photographer subcontracted by Golder Associates. The photographs have previously been provided to the RTA on a CD.

### 2.3 Remediation Assessment

Geotechnical engineers and engineering geologists from Golder Associates visited each of the cuttings and based on the slope risk assessments, assessed by visual observation geotechnical hazards requiring remediation to limit the ARL to 3 or better. Proposed remediation works to treat these hazards were plotted onto the photomosaics of the cuttings.

### 2.4 Additional Geotechnical Investigations

No additional geotechnical works were undertaken for the design of remediation of the nine cuts in this design package.

### 2.5 Engineering Analyses and Design

For each of the geotechnical hazards, the effectiveness of proposed remediation strategies to reduce the ARL to 3 or better was assessed. Where required, engineering analyses were carried out for the design of structural elements of the slope remediation, such as rock bolts.

### 2.6 Design Documentation

The proposed remediation works are documented on design drawings included with this design report. The drawings are based on the survey data provided by the RTA and the photomosaics developed by Golder Associates. The drawings illustrate indicative extents and types of remediation work. In some cases, actual treatments could be more or less extensive than illustrated depending on the actual conditions encountered.

The design drawings for each cutting includes an overview plan on A1 size paper showing the entire length of the cutting. Subsequent drawings (A3 size) illustrate the proposed remediation works along sections of the cut, and the extent of each drawing is shown on the overview. A list of the drawings is included on Drawing 081D001. General notes about the proposed treatment works are also shown on Drawing 081D001.

The proposed remediation work for the cuttings are summarised in a table on each drawing. Each individual section of proposed remediation works has been assigned a unique reference number, which is included in the summary table. Likewise, each rock bolt or catch fence has been assigned a unique reference number.

The summary table includes the chainage and location of the proposed work on the cutting, the unique reference number, an estimate of the maximum block size expected to be encountered and an estimate of the volume to be removed for crest treatment and scaling work. An additional table presents details for rock bolts (length, angle below horizontal).

### 2.7 Remediation Works Cost Estimates

An estimate of the cost of the proposed works is presented separately.

### 2.8 Co-ordination meetings with RTA

During the development of the remediation works, design co-ordination meetings have been held with the RTA. This has included site visits to discuss survey requirements and to meet the RTA geotechnical representative to review the proposed remediation strategies.

### 3.0 DESIGN APPROACH

### 3.1 Design Objectives

The objective of the remediation works is to reduce the ARL of the nine cuts to 3 or better. In achieving this objective, it needs to be recognised that the ARL is a temporal indication of the geotechnical risk of the cutting. Due to ongoing geological and environmental processes, it is possible that the ARL can change with time. With this in mind, an attempt has been made to incorporate into the remediation geotechnical hazards that are currently ARL 3 or 4, but which have the potential to develop into ARL 1 or 2 in the short term.

Some of the works proposed are intended to improve the appearance of cuttings which visually appear to present a risk to road users but are in the ARL 3 or better categories. These are typically cuts with loose rock on the surface. These works do not have an overall bearing on the ARL of the cuttings. The extent of these works is limited in relation to the overall works required and expected to involve relatively little effort, with the benefit of a better visual impression of the completed works.

### 3.2 Design Constraints and Philosophy

The design has considered the constraints imposed as a consequence of the physical and environmental site conditions. These include the limited site access, restricted work times, night work hours, safety and the high scenic quality of the area.

Where feasible the designs use solutions intended to have a relatively low visual impact (such as limiting 'non' natural works such as shotcreting).

### 3.3 Design Life

The required design life of the remediation works, other than structural components, has not specified by the RTA. For activities such as crest treatment, regrading and scaling, we would expect that the remediation works will result in achieving an ARL 3 or better for a period of at least 10 years following the completion of the proposed works.

Rock bolts are to have a design life of 100 years.

Rock catch fences are to have a design life of 50 years.

The proposed designs are based on the premise that a maintenance plan for the cuts will be developed after completion of the remediation works. The maintenance plan should document the frequency of reassessment of the ARL and inspections of the performance of the structural elements.

### 3.4 Types of Remediation

The proposed remediation works consists of:

- Crest treatment / regrading of cuttings Involves removal of geotechnically unstable soil and rock along the crest of the cutting and reprofiling of cutting faces. Structural support elements, such as rock bolts and shotcrete, are not intended as part of these works. The regrading is intended to create a reasonably smooth, stable face, where possible along natural discontinuities in the rock. The regrading is not to create overhangs. Tolerances for batter surface variations are given in the design specification. Manual (hand tools) and mechanical tools will be required for the crest treatment and regrading works.
- Scaling Involves the removal of selected soil and rock from the face of the cutting. The scaling is typically limited to soil and rock which is detached from the main rock mass and can be removed using hand tools.
- Rock Bolting Involves the installation of rock bolts to stabilise individual blocks or areas of the cutting.
- **Drainage** in general, the designs have not included significant drainage works. However, the remediation of Cut C7.44 requires that a catch drain is incorporated at the toe of the cut when the road surface is reinstated.
- Rock Catch Fence Involves the installation of a rock catch fence along the toe of selected lengths of the cutting to prevent soil and rock debris from reaching the road. The fence is generally to be installed at road level.

The extent of the types of treatment described above are indicated on the design drawings. The work quantities are indicative only and will depend on actual conditions exposed once the work commences.

### 3.5 Tree Hazard

Trees located on the cuttings and at or behind the crest of cuttings have only been identified for removal if they currently present a geotechnical risk. This risk usually arises due to root jacking which results in opening of joints and block detachment.

Other trees along the cuttings may not pose a geotechnical risk but are a potential risk if they fall onto the road. The requirement for tree removal for other than geotechnical purposes should be assessed by a tree specialist.

### 4.0 CONSTRUCTION WORKS

### 4.1 Client's Geotechnical Representative

An experienced geotechnical engineer (representing the RTA) will be available to provide guidance to the contractor during the remediation works. The geotechnical engineer will have the authority to direct changes to the work, as required, depending on actual conditions.

The geotechnical engineer is to be qualified to carry out RTA Slope Risk Assessments. This is critical to understand the intent behind the proposed remediation works and make adjustments to the remediation depending on conditions revealed during the works.

### 4.2 Management Plans

The Contractor is to prepare plans to demonstrate work procedures. Plans to be submitted are:

- Site Safety Management Plan;
- Environmental Management Plan;
- Work Method Statements, incorporating health, safety and environmental considerations.

The plans may be generic for each of the types of remediation. However, in some cases the Client's Representative may request that a specific plan is developed for a particular activity. This may be necessary to account for the specific physical and environmental conditions at different locations along the road.

### 4.3 Standards and Specifications

The designs described in this report are to be implemented in accordance with:

- Relevant RTA specifications;
- Relevant Australian Standards, and where those standards do not exist an alternative international standard to be approved by RTA; and
- Project Specifications.

### GOLDER ASSOCIATES PTY LTD

Glenn Wilson Geotechnical Engineer Graham Scholey Associate


\\SYD1-S-FILE01\JOBS\\04PROJ\\051-100\\04622081\_RTA\_SLOPES\_JCR\\081\W007R\_DRAFT\_DESIGN\_REPORT.DOC


# MR253 - JENOLAN CAVES ROAD SLOPE REMEDIATION

### DRAWING SCHEDULE

DR	A۱	VING SCHEDULE
Droving Number		Title Description
0810001	A1	Cover Sheet, Drowing Schedule and Construction Notes
0910100	A1	Cirthing Cl.74 Chairmage 1717 - 1860
0810101	A3	Certifing Cl.J4 Pages 1 of B Chairman 1717 - 1730
0810102	13	Ortifing C1.74 Poses 2 of 8 Charles 17-59 - 1751
0810103	AJ	Ortifing CI.24 Page 3 of 8 Charlesge 1741 - 1769
Ø1D104	A3	Ortifing C1.74 Page 4 of 8 Charlenge 1789 - 1788
OB1D106	A3	Cirting CI.74 Page 5 of 8 Chainings 1748 - 1810
091D104	A3	Cetting C1.74 Page 8 of 8 Ondreg : 1818 - 1835
Ø810107	A3	Certifreq C1.74 Page 7 of 8 Chairmage 1835 - 1852
00 ID I QU	A3	Cettino CIJ4 Page B of B Chainsa a 1847 - 1860
OB10200	Al	Ortifing (22,63) Charlesge 23-30 - 27:30
081 0201	A3	Criting C2.63 Page 1 of 7 Charlesg s 2636 - 2660
OB10202	A3	Cetting C2_63 Page 2 of 7 Chainsgs 2834 - 2568
OB10203	A3	Cartifing C2_63 Pege 3 of 7 Cheshage 2864 - 2863
OB10204	A3	Certifing C2.83 Page 4 of 7 Chairmage 2883 - 2700
0810205	A3	Certifina C1.63 Page 5 of 7 Chairman 1704 - 2715
08 (0.204)	A3	Cetting CLU3 Page 6 of 7 Chairson 2713 - 2726
OB10207	A	Ortiling C2.50 Page 7 of 7 Charlegs 2724 - 2730
<b>GB1D400</b>	A1	Ortiling CA.22 Chahaga 4226 - 4300
DB1 D4D1	A1	Cartifina CA.22 Charless 4300 - 4380
OB10402	A3	Cirting CA22 Page 1 of 10 Chahage 4226 - 4236
Ø81D403	A3	Certifus CA22 Page 2 of 10 Chairmage 4238 - 4280
081D404	A3	Crtting C4.22 Page 3 of 10 Chairsas 42M - 427l
OB10403	EA	Crtifing C4.27 Page 4 of 10 Charles 4279 - 4297
Ø81D406	A3	Criting C4.22 Page 5 of 10 Chahage 4217 - 4375 Criting C4.22 Page 5 of 10 Chahage 4316 - 4334
ØB1D407	A3	Criting CA27 Page 6 of 10 Charless 4318 - 4334
OB1D408	A3	Cirtifing CA.22 Page 7 of 10 Chairings 4884 - 4365
0810409	A3	Cetting CA22 Page 8 of 10 Chairage 4352 - 4376
081D4H0	A3	Cetting C4.22 Page 9 of 10 Chairses 4570 - 4385
DB1D411	A3	Crthro C4.22 Page 10 of 10 Chairson 4385 - 4384
0810300	Al	Criting CLUB Districte 5080 - 3230
0810501	A3	Cirting CALDE Page 1 of 8 Charles of 8080 - 3163
OB   D602	A3	Cirting CE.DB Page 2 of 8 Charlege 6103 - 3129
QB10603	A3	Cirting Ca.De Page 3 of 8 Charlege 6120 - 3136
0810504	A3	Cirting CS.DB Page 4 of 8 Chairs se 5138 - 5181
0810505	A3	Crthra CS.08 Poss 5 of 8 Chalman 5161 - 5185
	A	Criting CSLOB Page 6 of 6 Crisings S183 - 3210
OB10307	A3	Criting CSLOB Page 7 of 8 Challege S210 - \$650
GB1000B	A3	Crtifing Cd.DB Page B of 8 Charlege d230 - 3830
OB10620	A1	Cirtifing CS.29 Charlege 8250 - 6370
0810521	A3	Cirthrop CS.20 Peops 1 of 7 Cheshage 5250 - 5285
0810522	A3	Griffing CS.29 Page 2 of 7 Charlesgo 5215 - 5290
0010523	A3	Cettlers CS.29 Page 3 of 7 Chairson s 5291 - 5305
0810324	A3	Ortifing C1.29 Page 4 of 7 Charlege 3393 - 3320
Ø810020	A3	Ortifing Cd.29 Page 5 of 7 Charlengs 8324 - 6336
0810624	A3	Cirting C6.29 Page 8 of 7 Chahage 8888 - 6346
0B10627	A3	Orting 06.29 Page 7 of 7 Chehage 8348 - 6380
ØB10700	A1	Criting (7,02 Chalmage 7080 - 7125
0810/01	13	Crtthra C7.02 Page 1 of 7 Chairses 7424 - 7032
0810702	43	Criting C7.02 Page 2 of 7 Chahana 7932 - 7049
QB107Q3	A3	Ortifing 07.02 Page 3 of 7 Charlesge 7946 - 7054 Ortifing 07.02 Page 4 of 7 Charlesge 7464 - 7078
<b>GB10704</b>	A3	Crtifing C7_D2 Page 4 of 7 Charlesge 7464 - 7078
QB107Q6	A3	Cirtifing C7.02 Page 5 of 7 Chaining 1 7474 - 7094
CB10704	A3	Criting C7.02 Page 8 of 7 Orestage 7474 - 7094  Criting C7.02 Page 8 of 7 Orestage 7474 - 7094  Criting C7.02 Page 8 of 7 Orestage 7494 - 7110  Criting C7.02 Page 7 of 7 Orestage 7110 - 7120
0810707	A3	Criting C7.02 Page 7 of 7 Chalmage 7110 - 7120
0010740	A1	Crttina C/.44 Ondress 7044 - 7049
0810741	A	Ortifing 07.44 Page 1 of 3 Charlesge 7449 - 7400
@10742	A3	Ortiling C7.44 Page 2 of 3 Charlesge 7488 - 7470
Œ10743	A3	Ortific C7.44 Pose 3 of 3 Charles 7474 - 7490
GB10760	A1	Crtifus C7.58 Chainess 7880 - 7720
0810751	A1	Crting C7.58 Chahage 7720 - 7800
0810752	A3	Cetting C7.58 Page 1 of 18 Chairson 7574 - 7589
0010733	43	Critina C7.50 Page 2 of 19 Chahana 7294 - 760b
GE10734	AJ	Ortiling C7.58 Page 3 of 18 Charlesge 7898 - 7855
GB10766	A3	Criting C7.58 Page 4 of 18 Charlege 7838 - 7849
Ø10764	A3	Cirtifing C7.58 Pega 5 of 18 Challege 7846 - 7866
0810757	A3	Criting C7.58 Page 8 of 18 Chairage 7858 - 7876
Ø10758	A3	Certifreq C7.58 Page 7 of 18 Chalmage 7670 - 7885
0010750	13	Cettless C7.50 Page 8 of 18 Chalman 7665 - 7686
QB10790	A2	Ortifing C7.28 Page 9 of 18 Charlesge 7856 - 7719
0810791	A3	Cirting C7.56 Page 10 of 18 Charlege 7714 - 7723
Œ10742	A3	Ortifine C7 58 Perm 11 of 18 Divisions 7736 - 7736
@10743	A3	Criting C7.88 Page 12 of 18 Chahapt 7782 - 7743
OB10764	A3	Cetting C7.58 Page 13 of 18 Chairage 7743 - 7755
0010745	A3	Critica C7.50 Page 14 of 18 Chairean 7755 - 7765
0010744	A3	Cetters (7.58) Page 15 of 18 Chairean 7785 - 7775
QB10747	AZ	Ortifing C7.38 Page 16 of 18 Chairson 7773 - 7794
GB10746	A3	Ortifing C7.58 Page 17 of 18 Charless 7784 - 7783
0810748 0810748	A3	Crtifing C7.58 Page 18 of 18 Chahase 7793 - 7899
Œ10800	A1	Crifing CT.III Page 12 of 18 Owthings 7783 - 7713 Culfon, CT.SII Page 13 of 18 Owthings 7784 - 7775 Culfon, CT.SII Page 13 of 18 Owthings 7784 - 7775 Culfon, CT.SII Page 13 of 18 Owthings 7784 - 7775 Culfon, CT.SII Page 15 of 18 Owthings 7785 - 7775 Crifing CT.SII Page 15 of 18 Owthings 7778 - 7774 Orthing CT.SII Page 17 of 18 Owthings 7784 - 7713 Crifing CT.SII Page 16 of 18 Owthings 7784 - 7780 Crifing CT.SII Owthings 5786 - 8210 Crifing CT.SII Owthings 5786 - 8210 Crifing CT.SII Page 1 of 8 Owthings 4790 - 8015 Crifing CT.SII Page 1 of 8 Owthings 4790 - 8015 Crifing CT.SII Page 1 of 8 Owthings 4790 - 8015 Crifing CT.SII Page 1 of 8 Owthings 4790 - 8015
0810801	A3	Criting CE.13 Forgs 1 of B Chairean J 100 - 8015
0010802	A3	
COLUMN	A	
0810804	A)	Ortifing CB.13 Page 4 of 8 Challenge 4140 - 8115 Ortifing CB.13 Page 4 of 8 Challenge 4140 - 8158
GB10800	A3	Criting DR 13 Perm 5 of 8 Chebras JAM - 8177
Œ10604	A3	Criting C8.13 Page 8 of 8 Chahaje 8174 - 8185
ØB10807	A3	Griffing CSL13 Page 7 of B Chairman J180 - 8185
0010000	A3	Cetting CL13 Page B of B Chairson 4195 - 8210
	_	

# REMEDIATION NOTES ROCK GATCH FENCE 1 CEMERAL NOTES 1.1 These roots apoly to all drowings farted in the Drowing Schedule univers noted otherwise. 1.2 Survey Information provided by RTA. 1.3 All levels are in nettre to Australian Height Detum (AHD). 1.4 AL Charless and Eventries are in motions unless solded otherwise. 1.5 All directions soil and be abodied off develope. 1.5 All directions soil and be abodied off develope. 1.7 Distriction soil and be abodied off develope. 1.7 Distriction should not be abodied off develope. 1.8 All vents in the octual quantities. 1.8 All vents in the bin develope match to implicate the RTMs Review of Employment Rene/Nort. Method Districtions to the RTMs Review of Employment Enteroy. B.1 Fencing shall be supplied and installed in eccontance with the specificables. B.2 Typical Rock Cotch Ferza Debail (below). \_ DOUBLE TWIST MESH 1.5 re work is to be in decentations that approved are sormly senagement. He half that, featherd Statements. The decision rejects in relation to the RU'e Review of Environmental Feathers and an approved Environmental Management Plan. The work is not to commence until the Contractor has extended a Site Safety Plan which addresses each of the indifficult investments shown so the develope. 1.6 Tractoment adaptates include Creat Tractoment, Reginating, Sooling, Rock Batting and Rock Creat Features. Notice for each of the oringenies are included below. 1.1.0 All procedures are shown creat tractoment, recording, section and for most halfs are in classes. Forces. Notes for each of the contegeries are included below. 1.10 All namediation sortes means creat tructment, regrading, scaling and/or rack below are in close provintly are to be establised to land the potarbial for further geotestrated lazards to develop. 1.11 The ebjective of the works shall be to reduce the Assessed Risk Level (AFL) of slopes from ARL 1 or AFL 2 to AFL 3 or better. TYPICAL ROCK FENCE DETAIL 2 DEFINITIONS To be developed in conjunction with RTA. 3 CREST TREATMENT / REGRADING 3.5 Dische that on he removed without excessive use or tarte using a securing for shall be removed. 3.6 Where requesting of reck cuttings is undertaken, the single of the cut is to be an elevated by the Principola Authorities Representative. Where collishing particularly defect places are bentified as a Body failure plane (as specified by the Principola Authorities discrete places are believed to be out during or believe this place. 3.5 Where the restable larger of the cent is set during suggesting. It shall be cut at one revoved as per CL3.2. 3.6 Care shall be failed to limit the removed of gross and follogs cover above the crust. 3.7 Its areas with remarkations involving the chaning of blacks above the crust, the zone of classifing shall estend 3 in from the crust. 3.6 Times present during the overtiers not to be removed unlesse they present a gentlocked hazard (in most places) blocks). 3.9 Is the course of gesteral crust treatment vertice, these along the street that present on UHICS risks may be removed falsoning approved by the Principals Authorities Representative. 3.10 Remarkation betweeness will be as per out out in the specification. 4.1 The extent of scaling of such location is so shown on the drawings and to be confirmed on also by the Principals Authorized Representation. ace by the instead is Advisional Representative. 4.2 Sooling is to Involve the selected removed of blacks that represent a geotechnical hexamal. In general this includes black which are detected from the rock mass each have moved from their inspired in-situ location. 4.5 Blacks that can be removed without successive use of terms using a easing ber shell be removed. At Large blocks libertified (by the Principals Aethorised Representativa) as being losses can be convisity minimated by an acceptant. 4.6 is areas where targe areas at saciling are propused (it. areas of root jucking), an executor our be used. 5 ROCK BOLTS 5.1 Rack Bots shell be CT Bats supplied and introlled in accordance with the specification 5.2 Typical Rock Bot Datall below.







NFORMATEN DONTANED ON THE DRAWING IS THE DOPTING TO OF SOLDER ASSOCIATES PTY. LTD.

UNUTHORISED USE OR REPRODUCTION OF THIS PLAN EITHER WHOLLY OR IN PART WITHOUT WRITTEN PERMISSION INFRINGES COPPRINT.

COPPRINT.

C) BOLDER ABBOCATER PTY, LTD.



STONEY OFFICE

88 CHANDOS STREET

ST LEDIMARDS, MSW 2088 AUSTRALM
PH (02) 8478 3800

FAX (02) 8478 3801

TYPICAL ROCK BOLT DETAIL


	ROADS AND TRAFFI	CAUTHORI	TY	
JC	09.02.05	GKW	09.0	02.05
GKW	09.02.05	GKS	09.0	02.05
GKS	09.	.02.05	NOT TO SCALE	A1

COVER SHEET,
DRAWING SCHEDULE
AND REMEDIATION NOTES


04622081

081D001

T0



REMEDIATION WORK SUMMARY CUTTING C2.63 2.630 - 2.730 LEGEND: Rock Boll Details Rock Bott Details.... continued... Rock Botts Block Size Approx. Height from toe / Height to Volume Eufrente (m² Crest Treatment / Dieor Ve CREST TREATMENT/REMOVE VEGETATION/REGRADE Scoling of loose blacks
Rock Fence (mm) Crest (mrs.) RB 202 RB 203 3600 3600 2500 3500 - 4500 2000 - 5000 SCALING OF LOOSE BLOCKS 36D0 3600 3600 + RB221 ROCK BOLT 2000 - 5000 3000 2000 - 4000 2000 - 4000 to 1000 NOTE: SURVEY DATA SUPPLIED BY RTA 3600 to 500 2697 2700 Remove blocks 2700 2705 6 x Rock Bolts 36D0 36D0 RB 230 2400 RB 231 2400 C 248 2701 2705 Remove blocks above C 247 2711 2715 Scale blocks to 500 4500 INTERPRETIVE ONLY DO NOT SCALE 3600 CREST OF ROOFINGS-FL (m) TUE OF ROCKOACE - FL (M) CHE SPROKEE Drawing 081D204 Drawing 081D203 Drawing 081D201 CREST OF ROCKFROS-FS.(w) TUE OF ROOMPROD - FL. (m) INFORMATION CONTINUED IN THIS DRAWING IS THE COPYRIGHT OF COLDER ASSOCIATES PTY, LTD. ROADS AND TRAFFIC AUTHORITY SLOPE REMEDIATION, JENOLAN CAVES ROAD RTA SYDNEY OFFICE BB CHINICOS STREET 09.02.05 09.02.05 REMEDIATION WORK SUMMARY GKW ST LEDNARDS, NEW 2000 AUSTRAL CUTTING C2.63 CHAINAGE 2.605 - 2.730 Golder PH (02) 9478 3900 09.02.05 09.02.05 Associates GKW GKS STAD CTM STAD CTM FAX (02) 9478 3901 C COLDER ASSOCATES PTY. LTD. 09.02.05 NOT TO SCALE A1 GKS 081D200 TO DHEDRED 04622081



INTERPRETIVE ONLY DO NOT SCALE

### LEGEND:

CREST TREATMENT/REMOVE VECETATION/REGRADE SCALING DF LOOSE BLDCKS

+ RB401 ROCK BOLT

## **REMEDIATION WORK SUMMARY** CUTTING C4.22 4.220 - 4.370


	Chai	inage	Remediation	Estimate Max.	Approx. Height from toe /	Volume Estimate
ID	Start	Finish	Kariosidioii	Block Size (mm)		(m³)
5 420	4224		Remove loose block	to 500	2500	<1
C 421	4225	4230	Crast Treatment		1500 - 5000	20
C 422	4230	4237	Scale loase blocks below crest	to 500	4000 - 5000	<1
C 423	4239	4252	Scale lange radio below crest	to 500	3500 - 4500	2
5 424	4243	4244	Remove loose blocks	to 400	3000 - 3500	<1
	4249	4252	Pottern Rock Botts (Needs to be coordinated with scaling)		1500 - 4500	
5 425	4249	4252	Scale loase blocks	to 300	2500 - 5000	2
5 426	4253	4257	Scale base blacks (Patential for RB's ofter scaling)	la 1000	2000 - 4000	5
5 427	4250	4264	Sodie loose blocks	to 300	2500 - 4000	1
C 428	4280	4300	Scale blocks at prest	to 500	4000	2
C 429	4289		Remove tree on great		4000	
5 430	4302	4311	Scale dead vegetation and loase blacks	bo 400	1500 - 5000	2
C 431	4312	4347	Scale loose blocks at crest	to 400	4500	5
S 432	4320	4326	Scale dead vegetation and large blacks	to 400	3000 - 4000	<1
C 433	4351	4360	Crest Treatment	to 1000	4500	3
	4358		2 x Rock Bolls		3000	
5 434	4350		Remova block	to 600	2500	<1
C 435	4373	4377	Scale loose blocks at crest	to 300	2500 - 3000	<1
5 436	4382		Scale loase blocks	to 400	1000 - 2000	<1
C 437	4388		Scale base black and soil above black	ln 300	2500	2

### Rock Ball Dalada

Bolt	Langth	
No.	(mm)	Inclination
RB 401	2100	207
R9 402	2100	207
RB 403	2100	207
RB 4D4	2100	207
RB 405	2100	207
RB 408	2100	207
RB 407	2100	20"
R8 408	2100	207
RB 409	2100	207
RB 410	2100	20"
RD 411	2100	20
RB 412	2100	20
RB 413	2100	20
RB 414	3000	ď
RB 415	3000	0

### Estimated Quantities

Rock Botta	15
Creet Treatment / Clear Vegetation	50 m <sup>3</sup>
Scaling of loose blocks	12 m <sup>3</sup>
Rock Fence	_



TENDER ISSUE NTS DATE NES DATE D-EDGD







PH (02) 9478 3900


	ROADS AND TRAFFI	CAUTHORI	ITY	
JC	09.02.05	GKW	09.	02.05
GKW	09.02.05	GKS	09.	02.05
CKC	00	02.05	NOT TO SOME	Δ1

SLOPE REMEDIATION, JENOLAN CAVES ROAD REMEDIATION WORK SUMMARY CUTTING C4.22 CHAINAGE 4.300 - 4.390

NOTE: THE \* BESDE THE TYPED INITIALS DENOTES THE ORIGINAL DRAWING ISSUE WAS SIGNED OR INITIALLED BY THAT RESPECTIVE PERSON.







## REMEDIATION WORK SUMMARY CUTTING C7.44 7440 - 7490

	Che	ihege	Remarkation	Epilmete Mex.	Approx. Height from toe / Height to	Volume Estimate (m²)
ID	Start	Finish		Block Size (mm)	Creat (mm)	
C743	7443	7045	Regrade	to 500	1500 - 4000	<20
	7443	7444	2 x Rock Bolt		2000	
C744	7486	7497	Regrade	to 500	4000 - 5000	5

NOTE: RECONSTRUCTION OF PANDLENTS IS TO INCLUDE PROVISION OF TOE DRAIN ALONG LENGTH OF CUTTING ESTIMATED VIDTH OF DRAIN IS 1000 mm and 3000 nm.

### Estimated Quantities

Rock Botta	2
Crest Treatment / Clear Vegetation	25 m <sup>3</sup>
Scoring of loose blocks	-
Rock Fence	-

INTERPRETIVE ONLY DO NOT SCALE



LEGEND:

### Rock Boll Details

No.	(max)	Indination
RE741	2400	10
RB742	2400	10"

CREET OF RECEIVED -R. DO TOP OF RECEIVED -R. (H)	28						
CREST OF ROCKINGS -RL (H)	70 .					•	
RE.							
lan a	THE VIEW						
	C744	1, 12	200	rawing D81D742		C743  Drowing 081D741	7 M

		CHE	DED	APPROVED	
REVISION	DESCRIPTION	NID	DAJE	NIE	DAJE
Р	PRELIMINARY ISSUE	GKW	17.1.05	GKS	17.1.05
TO	TENDER ISSUE	GKW	09.2.05	GKS	09.2.05



© BOLDER ASSESSATES PTY. LTD.




SYDNEY DFFICE TEERTZ SOCIANIO 88 ST LECHARDS, NOV 2065 AUSTRALIA


JC	09.02.05	GKW	09.02.0
GKW	09.02.05	GKS	09.02.0


SLOPE REMEDIATION, JENOLAN CAVES ROAD REMEDIATION WORK SUMMARY CUTTING C7.44 CHAINAGE 7440 - 7490 081D740 TO

11

NOTE: THE \* BESIDE THE TYPED INTIALS DENOTES THE DRIGINAL DRAWING ISSUE WAS SIGNED OR INITIALLED BY THAT RESPECTIVE PERSON.







# **Appendix E** Results of Database Searches

Your Ref: H/43094 Our Ref: AHIMS #9706

Rta Environment Technology Level 5, Pod D, 99 Phillip Street Parramatta NSW 2150

Friday, 30 April 2004

Attention:

Dear Sir or Madam:

PARKS & WILDLA

NSW NATIONAL PARKS ANI WILDLIFE SERVICE

ABN 30 841 387 27

Re: AHIMS Search for the following area at Jenolan Caves
Zone 56 Eastings: 222000-228000 Northings: 5250000-6260000

I am writing in response to your recent inquiry in respect to Aboriginal objects and Aboriginal places registered with the NSW National Parks and Wildlife Service (NPWS) at the above location.

A search of the NPWS Aboriginal Heritage Information Management System (AHIMS) has shown that 18 Known Aboriginal objects and Aboriginal places are recorded in or near the above location. Please refer to the attached report for details.

The information derived from the AHIMS search is only to be used for the purpose for which it was requested. It is not to be made available to the public.

The following qualifications apply to an AHIMS search:

- AHIMS only includes information on Aboriginal objects and Aboriginal places that have been provided to NPWS;
- Large areas of New South Wales have not been the subject of systematic survey or recording of Aboriginal history. These areas may contain Aboriginal objects and other heritage values which are not recorded on AHIMS;
- Recordings are provided from a variety of sources and may be variable in their accuracy. When an AHIMS search identifies Aboriginal objects in or near the area it is recommended that the exact location of the Aboriginal object be determined by re-location on the ground; and
- The criteria used to search AHIMS are derived from the information provided by the client and NPWS assumes that this information is accurate.

All Aboriginal places and Aboriginal objects are protected under the *National Parks* and *Wildlife Act 1974* (NPW Act) and it is an offence to destroy, damage or deface them without the prior consent of the NPWS Director-General. An Aboriginal object is considered to be known if:

- It is registered on AHIMS;
- It is known to the Aboriginal community; or
- It is located during an investigation of the area conducted for a development P.O. Box 1967 application.

Head Office 43 Bridge Street P.O. Box 1967 Hurstville NSW 2220 Australia

Tel: (02) 9585 6444 Fax: (02) 9585 6555 www.npws.nsw.gov.au If you are considering undertaking a development activity in the area subject to the AHIMS search, NPWS would recommend that an Aboriginal Heritage Assessment be undertaken. You should consult with the relevant consent authority to determine the necessary assessment to accompany your development application.

Yours Sincerely

Paul Houston

Aboriginal Information Officer Information Systems Unit Cultural Heritage Division

Phone: (02) 9585 6471 Fax: (02) 9585 6094



# National Native Title Tribunal

Printer-friendly versio keywords

MATINE TITLE APPLICATIONS

### Claimant application summary

Application

Gundungurra Tribal Council Aboriginal

name:

Corporation #6

**Application** 

Claimant application

type:

State/Territory: **New South Wales** 

Date filed:

29/04/1997

Register of

Registered

**Native Title** Claims status:

**Federal Court** 

NG6060/98

file no .:

Tribunal file

NC97/7

no.:

Status:

Active

Area

South of Katoomba to Goulburn

description:

ATSIC region

(s):

Binaal Billa Regional Council Queanbeyan Regional Council

Sydney Regional Council

Representative A/TSI Body

area(s):

NSW Native Title Services Ltd

Local government region(s):

Bathurst City Council Blayney Shire Council

Blue Mountains City Council

Camden Council City of Lithgow Cowra Shire Council

Eastern Capital City Regional Council

Greater Argyle Council Liverpool City Council Oberon Council Penrith City Council Upper Lachlan Council

Wingecarribee Shire Council Wollondilly Shire Council

Applicants' representative: Murray Craddock Nuemann



### About the Tribunal

### Native Title Applications

\* Overview

- \* Information material
- \* Maps and spatial data
- \* How to apply
- \* Tribunal assistance
- \* Registration test
- \* Procedures and guidelines
- \* Sample clauses and agreements
- \* Search applications
- \* Browse determinations
- \* National Native Title Register
- \* Register of Native Title
- Claims
- \* Other organisations
- Contact for applications

#### Indigenous Land Use Agreements

**Future Acts** 

Registers

What's New

**Current Projects** 

Media Centre

#### Information and Publications

For definitions of specific native title words and terms see the Glossary.

Notification

**Notification Complete** 

status:

Notification

14/02/2001

closing date:

In mediation:

Yes

Case manager: Nicole Maher

Member:

G Sculthorpe

Home | Text only | Sitemap | Glossary | Links | Contact us

Privacy statement | Disclaimer and copy

© Commonwealth of Australia 2004









# National Native Title Tribunal

### Search results

Your search for native title applications using the criteria: in the local government region of oberon\* lodged between January 1994 and January 2005 returned **5** results. Showing **1 to 5**. Search again

Date filed	Application name	Application type	Status	State/ Territory	Tribunal file no.	Federal Court file no.
25/11/1996	Gundungurra Tribal Council Aboriginal Corporation #4	Claimant application	Active	New South Wales	NC96/36	NG6050/98
26/11/1996	Wiradjuri (Oberon)	Claimant application	Finalised Dismissed	New South Wales		NG6051/98
29/04/1997	Gundungurra Tribal Council Aboriginal Corporation #6	Claimant application	Active	New South Wales	NC97/7	NG6060/98
30/04/1999	Kim Moran #3	Claimant application	Finalised Dismissed	New South Wales	NC99/3	N6006/99
31/08/1999	Molong Tribe	Claimant application	Finalised Discontinued	New South Wales	NC99/5	N6013/99

Page: 1



#### About the Tribunal

### Native Title Applications

- \* Overview
- \* Information material
- \* Maps and spatial data
- " How to apply
- \* Tribunal assistance
- \* Registration test
- \* Procedures and guidelines
- \* Sample clauses and agreements
- \* Search applications
- \* Browse determinations
- \* National Native Title Register
- \* Register of Native Title Claims
- \* Other organisations
- \* Contact for applications

### Indigenous Land Use Agreements

**Future Acts** 

Registers

What's New

**Current Projects** 

Media Centre

Information and Publications

nnu search: Site Search Page 2 of z

For definitions of specific native title words and terms see the Glossary.

Home | Text only | Sitemap | Glossary | Links | Contact us


© Commonwealth of Australia 2004

Privacy statement | Disclaimer and copyright













### FISH FILES Search Results



NSW Fisheries Home | About FISH FILES | Need Assistance? | Disclaimer

Download as PDF

Download as CSV (spreadsheet)

View Map

Search Again

Scientific Name: Bidyanus bidyanus

Family: Terapontidae

NSW:Threatened Status: Vulnerable

Common Name: Silver perch

CAAB: 37321008

Protected Status: (N/A)

Catch Record ID	Nearest Town	Bioregion	Basin Name	River or Dam	Sighting Date	No. Observed	Source
134838	Appin	Sydney Basin	HAWKESBURY	Cataract Dam	2002	3	Freshwater Fish Research Database

Scientific Name: Macquaria australasica

Family: Percichthyidae

NSW Threatened Status: Vulnerable

Common Name: Macquarie perch

**CAAB:** 37311088

Protected Status: (N/A)

Catch Record ID	Nearest Town	Bioregion	Basin Name	River or Dam	Sighting Date	No. Observed	Source
53338	Kurrajong	Sydney Basin	HAWKESBURY	Wheeny Creek	2001	1	Community
134635	Wollongong	Sydney Basin	HAWKESBURY	Cordeaux River	2001	1	Freshwater Fish Research Database
53733	Appin	Sydney	HAWKESBURY	Glenbrook	2002	7	Freshwater Fish Research

		Basin	Creek			Database
134719	Glenbrook	Sydney Basin	HAWKESBURY Glenbrook Creek	2002	1	Freshwater Fish Research Database
134723	Glenbrook	Sydney Basin	HAWKESBURY Glenbrook Creek	2002	1	Freshwater Fish Research Database
134728	Glenbrook	Sydney Basin	HAWKESBURY Glenbrook Creek	2002	1	Freshwater Fish Research Database
134731	Glenbrook	Sydney Basin	HAWKESBURY Glenbrook Creek	2002	2	Freshwater Fish Research Database
134734	Glenbrook	Sydney Basin	HAWKESBURY Glenbrook Creek	2002	1	Freshwater Fish Research Database
134735	Glenbrook	Sydney Basin	HAWKESBURY Glenbrook Creek	2002	2	Freshwater Fish Research Database
134736	Glenbrook	Sydney Basin	HAWKESBURY Glenbrook Creek	2002	1	Freshwater Fish Research Database
134825	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	5	Freshwater Fish Research Database
53732	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	37	Freshwater Fish Research Database
134822	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	1	Freshwater Fish Research Database
134827	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	9	Freshwater Fish Research Database
134830	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	3	Freshwater Fish Research Database
134832	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	7	Freshwater Fish Research Database
134833	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	1	Freshwater Fish Research Database
134834	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	10	Freshwater Fish Research Database
134839	Appin	Sydney	HAWKESBURY Cataract Dam	2002	3	Freshwater Fish Research

		Basin				Database
134842	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	7	Freshwater Fish Research Database
134844	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	1	Freshwater Fish Research Database
134846	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	2	Freshwater Fish Research Database
134848	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	1	Freshwater Fish Research Database
134819	Appin	Sydney Basin	HAWKESBURY Cataract Dam	2002	2	Freshwater Fish Research Database
134974	Wollongong	Sydney Basin	HAWKESBURY Cordeaux River	2002	2	Freshwater Fish Research Database
134972	Wollongong	Sydney Basin	HAWKESBURY Cordeaux River	2002	2	Freshwater Fish Research Database
53653	Bargo	Sydney Basin	HAWKESBURY Cordeaux River	2002	1	Community

View Map Search Again

Download as PDF Download as CSV (spreadsheet)



### NSW DEPARTMENT OF PRIMARY INDUSTRIES | AGRICULTURE

Home » Farm management » Pest and weeds management » Weeds management » Noxious weed declarations »

### Noxious weed declarations in NSW

### **Upper Macquarie County Council**

The following weeds are declared noxious in the Upper Macquarie County Council control area (including Bathurst, Blayney, Evans, Lithgow and Oberon council areas). The 'details' link on each listing provides further information on the legal requirements of the weed's listing and any variation in status within the local control area. A complete list of all weeds in all control areas is also available as a PDF document.

Common name	Scientific name	Category	
African boxthorn	Lycium ferocissimum	W2	details
African love grass	Eragrostis curvula	W3	details
Alligator weed	Alternanthera philoxeroides	W1	details
Bathurst Noogoora Californian Cockle burrs	Xanthium spp.	W2	details
Black knapweed	Centaurea nigra	W1	details
Blackberry	Rubus fruticosus (agg. spp.)	W3	details
Broomrape	Orobanche spp.	W1	details
Cabomba	Cabomba spp.	W4g	details
Columbus grass	Sorghum x almum	W2	details
Dodder	Cuscuta campestris	W2	details
Gorse	Ulex europaeus	W2	details
Green cestrum	Cestrum parqui	W2	details
Harrisia cactus	Harrisia spp.	W4f	details
Hawkweed	Hieracium spp.	W1	details


1			
Hemlock	Conium maculatum	W2	details
Horsetail	Equisetum spp.	W1	details
Johnson grass	Sorghum halepense	W2	details
Karroo thorn	Acacia karroo	W1	details
Kochia	Kochia scoparia	W1	details
Lagarosiphon	Lagarosiphon major	W1	details
Longstyle feather grass	Pennisetum villosum	W2	details
Mexican feather grass	Nassella tenuissima syn Stipa tenuissima	W1	details
Miconia	Miconia spp.	W1	details
Nodding thistle	Carduus nutans	W3	details
Pampas grass	Cortaderia spp.	W2	details
Parthenium weed	Parthenium hysterophorus	W1	details
Prickly pears	Opuntia spp.	W4f	details
Privet - broadleaf	Ligustrum lucidum	W4b	details
Privet - narrowleaf	Ligustrum sinense	W4b	details
Rhus tree	Toxicodendron succedaneum	W2	details
Salvinia	Salvinia molesta	W1	details
Scotch English broom	Cytisus scoparius	W2	details
Scotch Illyrian Stemless thistles	Onopordum spp.	W3	details
Senegal tea plant	Gymnocoronis spilanthoides	W1	details
Serrated tussock	Nassella trichotoma	W3	details
Siam weed	Chromolaena odorata	W1	details
Silverleaf nightshade	Solanum elaeagnifolium	W2	details
Spiny burrgrass	Cenchrus incertus	W2	details
Spiny burrgrass	Cenchrus longispinus	W2	details
Spotted knapweed	Centaurea maculosa	W1	details
St John's wort	Hypericum perforatum	W3	details

· ·			1
Star thistle	Centaurea calcitrapa	W2	details
Sweet briar	Rosa rubiginosa	W3	details
Tree of heaven	Ailanthus altissima	W2	details
Water hyacinth	Eichhornia crassipes	W1	details
Water lettuce	Pistia stratiotes	W1	details
Wild radish	Raphanus raphanistrum	W2	details
Willows	Salix spp.	W4g	details

Return to start page

The information contained in this web page is based on knowledge and understanding at the time of writing. However, because of advances in knowledge, users are reminded of the need to ensure that information upon which they rely is up to date and to check currency of the information with the appropriate officer of NSW Department of Primary Industries or the user's independent adviser.

© State of New South Wales, NSW Department of Primary Industries, 2005





**Protected Matters Search Tool** 

You are here: DEH Home > EPBC Act > Search


17 January 2005 12:25

# EPBC Act Protected Matters Report

This report provides general guidance on matters of national environmental significance and other matters protected by the EPBC Act in the area you have selected. Information on the coverage of this report and qualifications on data supporting this report are contained in the <u>caveat</u> at the end of the report.

You may wish to print this report for reference before moving to other pages or websites.

The Australian Natural Resources Atlas at <a href="http://www.environment.gov.au/atlas">http://www.environment.gov.au/atlas</a> may provide further environmental information relevant to your selected area. Information about the EPBC Act including significance guidelines, forms and application process details can be found at <a href="http://www.deh.gov.au/epbc/assessmentsapprovals/index.html">http://www.deh.gov.au/epbc/assessmentsapprovals/index.html</a>



Search Type:

Area

Buffer:

10 km

Coordinates:

-33.78118,150.02404, -33.78567,150.02389, -33.78927,150.02718, -33.79076,150.03048, -33.79301,150.03093, -33.79271,150.02808, -33.80154,150.02583, -33.80604,150.03452, -33.80783,150.03033, -33.80768,150.02853, -33.81247,150.02868, -33.81577,150.03122, -33.81816,150.02868, -33.81831,150.02269, -33.82041,150.02284, -33.82131,150.02868, -33.82026,150.03078, -33.81637,150.03407, -33.80963,150.02973, -33.81083,150.03212, -33.80813,150.03452, -33.81142,150.03706, -33.81008,150.03886, -33.80334,150.03886, -

33.80304,150.03661, -33.80439,150.03452, -33.80050,150.02898, -33.79526,150.02943, -33.79511,150.03227, -33.78972,150.03347, -33.78762,150.02808, -33.78537,150.02613, -33.7816,150.02628

### Summary

Matters of National Environmental Significance

This part of the report summarises the matters of national environmental significance that may occur in, or may relate to, the area you nominated. Further information is available in the detail part of the report, which can be accessed by scrolling or following the links below. If you are proposing to undertake an activity that may have a significant impact on one or more matters of national environmental significance then you should consider the Administrative Guidelines on Significance - see <a href="http://www.deh.gov.au/epbc/assessmentsapprovals/guidelines/index.html">http://www.deh.gov.au/epbc/assessmentsapprovals/guidelines/index.html</a>.

World Heritage Properties: 1

National Heritage Places: None

Wetlands of International Significance: 1

(Ramsar Sites)

Commonwealth Marine Areas: None

Threatened Ecological Communities: None

Threatened Species: 18

Migratory Species: 8

### Other Matters Protected by the EPBC Act

This part of the report summarises other matters protected under the Act that may relate to the area you nominated. Approval may be required for a proposed activity that significantly affects the environment on Commonwealth land, when the action is outside the Commonwealth land, or the environment anywhere when the action is taken on Commonwealth land. Approval may also be required for the Commonwealth or Commonwealth agencies proposing to take an action that is likely to have a significant impact on the environment anywhere.

The EPBC Act protects the environment on Commonwealth land, the environment from the actions taken on Commonwealth land, and the environment from actions taken by Commonwealth agencies. As heritage values of a place are part of the 'environment', these aspects of the EPBC

Act protect the Commonwealth Heritage values of a Commonwealth Heritage place and the heritage values of a place on the Register of the National Estate. Information on the new heritage laws can be found at http://www.deh.gov.au/heritage/index.html.

Please note that the current dataset on Commonwealth land is not complete. Further information on Commonwealth land would need to be obtained from relevant sources including Commonwealth agencies, local agencies, and land tenure maps.

A permit may be required for activities in or on a Commonwealth area that may affect a member of a listed threatened species or ecological community, a member of a listed migratory species, whales and other cetaceans, or a member of a listed marine species. Information on EPBC Act permit requirements and application forms can be found at <a href="http://www.deh.gov.au/epbc/permits/index.html">http://www.deh.gov.au/epbc/permits/index.html</a>.

Commonwealth Lands:

Commonwealth Heritage Places: None

Places on the RNE: 2

Listed Marine Species: 12

Whales and Other Cetaceans: None

Critical Habitats: None

Commonwealth Reserves: None

#### **Extra Information**

This part of the report provides information that may also be relevant to the area you have nominated.

State and Territory Reserves: 2

Other Commonwealth Reserves: None

Regional Forest Agreements: None

#### **Details**

### Matters of National Environmental Significance

World Heritage Properties [ Dataset Information ]

The Greater Blue Mountains Area NSW

Wetlands of International Significance [ Dataset Information ]

(Ramsar Sites)

MACQUARIE MARSHES NATURE RESERVE Within same catchment as Ramsar

site

Threatened Species [ Dataset Information ] Status Type of Presence

Birds

Lathamus discolor Endangered Species or species habitat may

Swift Parrot occur within area

Rostratula australis Vulnerable Species or species habitat may

Australian Painted Snipe occur within area

Xanthomyza phrygia Regent Honeyeater	Endangered	Species or species habitat likely to occur within area
Fishes		
Maccullochella peelii peelii Murray Cod, Cod, Goodoo	Vulnerable	Species or species habitat may occur within area
Macquaria australasica * Macquarie Perch	Endangered	Species or species habitat may occur within area
Prototroctes maraena * Australian Grayling	Vulnerable	Species or species habitat likely to occur within area
Frogs		
Heleioporus australiacus * Giant Burrowing Frog	Vulnerable	Species or species habitat likely to occur within area
Mammals		
Chalinolobus dwyeri Large-eared Pied Bat, Large Pied Bat	Vulnerable	Species or species habitat may occur within area
Dasyurus maculatus maculatus (SE mainland population) Spot-tailed Quoll, Spotted-tail Quoll, Tiger Quoll (southeastern mainland population)	Endangered	Species or species habitat likely to occur within area
Nyctophilus timoriensis (South-eastern form) Eastern Long-eared Bat	Vulnerable	Species or species habitat may occur within area
Petrogale penicillata Brush-tailed Rock-wallaby	Vulnerable	Species or species habitat may occur within area
Potorous tridactylus tridactylus Long-nosed Potoroo (SE mainland)	Vulnerable	Species or species habitat may occur within area
Pteropus poliocephalus Grey-headed Flying-fox	Vulnerable	Species or species habitat likely to occur within area
Reptiles		
Hoplocephalus bungaroides * Broad-headed Snake	Vulnerable	Species or species habitat likely to occur within area
Plants		
Acacia flocktoniae *	Vulnerable	Species or species habitat likely to occur within area
Caladenia tessellata Thick-lipped Spider-orchid, Daddy Long-legs	Vulnerable	Species or species habitat likely to occur within area
Eucalyptus pulverulenta Silver-leaved Mountain Gum, Silver-leaved Gum	Vulnerable	Species or species habitat likely to occur within area
Thesium australe Austral Toadflax, Toadflax	Vulnerable	Species or species habitat likely to occur within area
Migratory Species [ Dataset Information ]	Status	Type of Presence
Migratory Terrestrial Species		
Birds		
Haliaeetus leucogaster White-bellied Sea-Eagle	Migratory	Species or species habitat likely to occur within area
Hirundapus caudacutus	Migratory	Species or species habitat may

White-throated Needletail		occur within area
Monarcha melanopsis Black-faced Monarch	Migratory	Breeding may occur within area
Myiagra cyanoleuca Satin Flycatcher	Migratory	Breeding likely to occur within area
Rhipidura rufifrons Rufous Fantail	Migratory	Breeding may occur within area
Xanthomyza phrygia Regent Honeyeater	Migratory	Species or species habitat likely to occur within area
Migratory Wetland Species		
Birds		
Gallinago hardwickii Latham's Snipe, Japanese Snipe	Migratory	Species or species habitat may occur within area
Rostratula benghalensis s. lat. Painted Snipe	Migratory	Species or species habitat may occur within area
Other Matters Protected by the	e EPBC	Act
Listed Marine Species [ <u>Dataset Information</u> ]	Status	Type of Presence
Birds		
Apus pacificus Fork-tailed Swift	Listed - overfly marine area	Species or species habitat may occur within area
Ardea alba Great Egret, White Egret	Listed - overfly marine area	Species or species habitat may occur within area
Ardea ibis Cattle Egret	Listed - overfly marine area	Species or species habitat may occur within area
Gallinago hardwickii Latham's Snipe, Japanese Snipe	Listed - overfly marine area	Species or species habitat may occur within area
Haliaeetus leucogaster White-bellied Sea-Eagle	Listed	Species or species habitat likely to occur within area
Hirundapus caudacutus White-throated Needletail	Listed - overfly marine area	Species or species habitat may occur within area
Lathamus discolor Swift Parrot	Listed - overfly marine area	Species or species habitat may occur within area
Merops ornatus Rainbow Bee-eater	Listed - overfly marine area	Species or species habitat may occur within area
Monarcha melanopsis	Listed -	Breeding may occur within area

Black-faced Monarch overfly

marine area

Myiagra cyanoleuca

Satin Flycatcher

Listed overfly

marine area

Breeding likely to occur within area

Rhipidura rufifrons

Rufous Fantail

Listed overfly marine

area

area

Breeding may occur within area

Rostratula benghalensis s. lat.

Painted Snipe

Listed overfly marine

Species or species habitat may occur within area

Commonwealth Lands [ Dataset Information ]

Transport and Regional Services - Airservices Australia

Places on the RNE [ Dataset Information ] Note that not all Indigenous sites may be listed.

#### **Natural**

Jenolan Caves and Reserve NSW Kanangra Boyd National Park (1977 boundary) NSW

#### Extra Information

State and Territory Reserves [ Dataset Information ]

Jenolan Karst Conservation Reserve, NSW

Kanangra-Boyd National Park, NSW

#### Caveat

The information presented in this report has been provided by a range of data sources as acknowledged at the end of the report.

This report is designed to assist in identifying the locations of places which may be relevant in determining obligations under the Environment Protection and Biodiversity Conservation Act 1999. It holds mapped locations of World Heritage and Register of National Estate properties, Wetlands of International Importance, Commonwealth and State/Territory reserves, listed threatened, migratory and marine species and listed threatened ecological communities. Mapping of Commonwealth land is not complete at this stage. Maps have been collated from a range of sources at various resolutions.

Not all species listed under the EPBC Act have been mapped (see below) and therefore a report is a general guide only. Where available data supports mapping, the type of presence that can be determined from the data is indicated in general terms. People using this information in making a referral may need to consider the qualifications below and may need to seek and consider other information sources.

For threatened ecological communities where the distribution is well known, maps are derived from recovery plans, State vegetation maps, remote sensing imagery and other sources. Where threatened ecological community distributions are less well known, existing vegetation maps and

point location data are used to produce indicative distribution maps.

For species where the distributions are well known, maps are digitised from sources such as recovery plans and detailed habitat studies. Where appropriate, core breeding, foraging and roosting areas are indicated under "type of presence". For species whose distributions are less well known, point locations are collated from government wildlife authorities, museums, and non-government organisations; bioclimatic distribution models are generated and these validated by experts. In some cases, the distribution maps are based solely on expert knowledge.

Only selected species covered by the <u>migratory</u> and <u>marine</u> provisions of the Act have been mapped.

The following species and ecological communities have not been mapped and do not appear in reports produced from this database:

- threatened species listed as extinct or considered as vagrants
- some species and ecological communities that have only recently been listed
- some terrestrial species that overfly the Commonwealth marine area
- migratory species that are very widespread, vagrant, or only occur in small numbers.

The following groups have been mapped, but may not cover the complete distribution of the species:

- non-threatened seabirds which have only been mapped for recorded breeding sites;
- seals which have only been mapped for breeding sites near the Australian continent.

Such breeding sites may be important for the protection of the Commonwealth Marine environment.

### **Acknowledgments**

This database has been compiled from a range of data sources. Environment Australia acknowledges the following custodians who have contributed valuable data and advice:

- New South Wales National Parks and Wildlife Service
- Department of Sustainability and Environment, Victoria
- Department of Primary Industries, Water and Environment, Tasmania
- Department of Environment and Heritage, South Australia Planning SA
- Parks and Wildlife Commission of the Northern Territory
- Environmental Protection Agency, Queensland
- Birds Australia
- Australian Bird and Bat Banding Scheme
- Australian National Wildlife Collection
- Natural history museums of Australia
- Queensland Herbarium
- National Herbarium of NSW
- Royal Botanic Gardens and National Herbarium of Victoria
- Tasmanian Herbarium
- State Herbarium of South Australia
- Northern Territory Herbarium

- Western Australian Herbarium
- · Australian National Herbarium, Atherton and Canberra
- University of New England
- Other groups and individuals

ANUCLIM Version 1.8, Centre for Resource and Environmental Studies, Australian National University was used extensively for the production of draft maps of species distribution. Environment Australia is extremely grateful to the many organisations and individuals who provided expert advice and information on numerous draft distributions.

#### Last updated:

Department of the Environment and Heritage GPO Box 787 Canberra ACT 2601 Australia Telephone: +61 (0)2 6274 1111

© Commonwealth of Australia 2004

### Australian Heritage Database

### Search Results

edit search | new search | about the Australian Heritage Database | Heritage home | Australian Heritage Council home

25 results found.		
Brisbane Valley Catholic Cemetery	Brisbane Valley via Essington, NSW	(Indicative Place) Register of the National Estate
Catholic Cemetery	Black Springs, NSW	(Indicative Place) Register of the National Estate
<u>Duckmaloi Geological Places</u> Hampton Rd	Duckmaloi via Oberon, NSW	( <u>Registered</u> ) Register of the National Estate
Hazelgrove Cemetery Tarana Rd	Hazelgrove, NSW	(Indicative Place) Register of the National Estate
Indigenous Place	Kanangra Walls via Jenolan Caves, NSW	(Registered) Register of the National Estate
Indigenous Place	Oberon, NSW	(Indicative Place) Register of the National Estate
Jenolan Caves and Reserve Jenolan Caves Rd	Jenolan Caves, NSW	(Registered) Register of the National Estate
Kanangra Boyd National Park (1977 boundary) Kanangra Rd	Kanangra, NSW	(Registered) Register of the National Estate
Kanangra Wilderness Area Kanangra Rd	Oberon, NSW	(Indicative Place) Register of the National Estate
Lone Grave (Delaney)	Honeysuckle Flat via The Meadows, NSW	(Indicative Place) Register of the National Estate
Lone Grave (Hogan) Oberon St	Oberon, NSW	(Indicative Place) Register of the National Estate
Lone Grave on Springvale Black Springs Rockley Rd	Springvale via Black Springs, NSW	(Indicative Place) Register of the National Estate
O'Connell Settlement Bathurst - Oberon Rd	O'Connell, NSW	(Registered) Register of the National Estate
O'Connell Settlement (redefinition) Bathurst - Oberon Rd	O'Connell, NSW	(Indicative Place) Register of the National Estate
Oberon General Cemetery Black Springs Rd	Oberon, NSW	(Indicative Place) Register of the National Estate
Private Cemetery on Mary Vale Oberon Goulburn Rd	Porters Retreat, NSW	(Indicative Place) Register of the

St Barnabas Anglican Church Cemetery Ross St	Oberon, NSW	National Estate (Indicative Place) Register of the National Estate
St Peters Anglican Church Cemetery Lowes Mount Rd	Mutton Falls via Tarana, NSW	(Indicative Place) Register of the National Estate
St Thomas Anglican Church Beaconsfield - O'Connell Rd	O'Connell, NSW	(Registered) Register of the National Estate
St Thomas Anglican Church Group Beaconsfield - O'Connell Rd	O'Connell, NSW	(Registered) Register of the National Estate
St Thomas Anglican Rectory (former) Beaconsfield - O'Connell Rd	O'Connell, NSW	(Registered) Register of the National Estate
Sydmouth Valley Homestead Carlwood Rd	Sydmouth Valley via Tarana, NSW	( <u>Registered</u> ) Register of the National Estate
The Blue Mountains	Katoomba, NSW	(Indicative Place) Register of the National Estate
The Cliff Beaconsfield - O'Connell Rd	Wisemans Creek, NSW	(Indicative Place) Register of the National Estate
The Greater Blue Mountains Area Geat Western Hwy	Katoomba, NSW	(Declared property) World Heritage List

Report Produced: Mon Jan 17 12:44:40 2005

#### Oberon Local Environmental Plan 1998

### Schedule 2 Heritage items

(Clause 6 (1))

### Part 1 Archaeological sites

Study reference No
_
900
901
902
903


### Part 2 European heritage items

. art = =a. opoar normago it	31110
List of items	Study reference No or Property description
Rowes Homestead	Lot 49 DP 728898
Limestone Bridge (near Grand Arch)	Lot 49 DP 728898
Tarana—Oberon Rail Line	202 & 602
Sidmouth Valley—O'Connell Road	Pt Lot 73 DP 757058
Phills Falls	601
Old Bathurst—Sydney Road	603
The Six Foot Track	604
Brisbane Valley Creek—Gold Diggings	Lot 85 DP 757039
Lone Grave on "Springvale"	_
Jenolan Caves House	Lot 39 DP 728898
Hazelgrove Cemetery	Pt Lot 1 DP 544230
National Australia Bank, Oberon Township	Lot 5 Sec 21 DP 2418
Ramsgate (house), Oberon Township	Pt Lot 2A Sec 21 DP 427257
Malachi Gilmore Hall—Oberon Township	Lot 6 Sec 21 DP 17887
O'Connell Hotel	Lot 1 DP 783230
O'Connell Road Store Group:	
Store	Lot 1 DP 783230
Pise Barn	Lot A DP 418324
Slab Barn	Lot A DP 418324
O'Connell Roman Catholic Church Group:	
Roman Catholic Church	Lot 1 DP 621591
School House	Lot 2 DP 621591
Post Office	Lot A DP 418324
Shop	Lot A DP 418324
Cottage	Lot A DP 418324
St Thomas' Anglican Church Group:	
St Thomas' Anglican Church	Lots 81 & 82 DP 854881 & Lot 1 DP 119280
Former Rectory	Lots 81 & 82 DP 854881 & Lot 1 DP 119280
Ruins: Pise Chapel	Lots 81 & 82 DP 854881 & Lot 1 DP 119280
Stable	Lots 81 & 82 DP 854881 & Lot 1 DP 119280
Bolton Vale, Oberon Road, O'Connell	Lots 22 DP 852574

### Part 3 Heritage conservation areas

Jenolan Caves Reserve Conservation Area O'Connell Urban Conservation Area







### Listing Heritage Items

State Heritage Inventory Search Results

#### **Statutory Listed Items**

Information and items listed in the State Heritage Inventory come from a number of sources. This means that there may be several entries for the same heritage item in the database. For clarity, the search results have been divided into two sections.

- Section 1. contains items listed by the **Heritage Council** under the NSW Heritage Act. This includes listing on the State Heritage Register, an Interim Heritage Order or protected under section 130 of the NSW Heritage Act. This information is provided by the NSW Heritage Office.
- Section 2. contains items listed by Local Councils & Shires and State Government Agencies.
   This section may also contain additional information on some of the items listed in the first section.

#### Section 1. Items listed under the NSW Heritage Act.

The search results can be re-sorted by clicking on the (sort) option at the top of each column.

Item Name (sort)	Address (sort)	Suburb (sort)	LGA (sort)	State Heritage Register	
Jenolan Caves Reserve	Caves Road	Jenolan	Oberon	Yes	
Malachi Gilmore Memorial Hall	124 Oberon Street	Oberon	Oberon	Yes	
Oberon Railway Station group	Tarana-Oberon railway	Oberon	Oberon	Yes	

There were **3** records in this section matching your search criteria.

#### Section 2. Items listed by Local Government and State agencies.

Item Name (sort)	Address (sort)	Address (sort) Suburb (sort)		(sort)	
Bolten Vale	Oberon Road	O'Connell	Oberon	LGOV	
Brisbane Valley Creek Gold Diggings		Oberon	Oberon	LGOV	
Cooerwull (Lithgow) Footbridge	On Top Of Up Side Cutting On Display	Cooerwull	Oberon	SGOV	
Cooerwull, Lithgow Footbridge Over Main West, W Lithgow Station		Lithgow	Oberon	SGOV	
Cottage	O'Connell Road	Oberon	Oberon	LGOV	
Hazelgrave Cemeterey		Oberon	Oberon	LGOV	
Jenolan Caves		Oberon	Oberon	LGOV	
JENOLAN CAVES		Oberon	Oberon	LGOV	
Jenolan Caves Reserve Conservation Area		Oberon	Oberon	LGOV	
Kanangra Boyd National Park		Oberon	Oberon	LGOV	
	the framework of the property of the second	AS TO SEARCH OF THE WAY SERVICES AND	n all sections of the all and a passes of all these over a last of the region of the passes of the section of t	to display the selection of the second and all a major is also contained the structure and the absence of containing and	

Limestone Bridge (near Grand

Arch)		Oberon	Oberon	LGOV
Lone Grave on Springvale		Oberon	Oberon	LGOV
Lowes Mount Road		Oberon	Oberon	LGOV
Malachi Gilmore Hall		Oberon	Oberon	LGOV
National Australia Bank		Oberon	Oberon	LGOV
O'Connell Hotel		Oberon	Oberon	LGOV
O'Connell Road Store Group		Oberon	Oberon	LGOV
O'Connell Roman Catholic Church Group	O'Connell Road	Oberon	Oberon	LGOV
O'Connell Urban Conservation Area		Oberon	Oberon	LGOV
Oberon Station Group		Oberon	Oberon	SGOV
Oberon Area		Oberon	Oberon	LGOV
Oberon Fire Station (not to be included at this stage)	7 North Street	Oberon	Oberon	SGOV
Old Bathurst	Sydney Road	Oberon	Oberon	LGOV
Phills Falls		Oberon	Oberon	LGOV
Pise Barn	O'Connell Road	Oberon	Oberon	LGOV
Pise Chapel Ruins	· ·	Oberon	Oberon	LGOV
Post Office	O'Connell Road	Oberon	Oberon	LGOV
Ramsgate		Oberon	Oberon	LGOV
Rectory (former)		Oberon	Oberon	LGOV
Roman Catholic Church	O'Connell Road	Oberon	Oberon	LGOV
Rowes Homestead		Oberon	Oberon	LGOV
School House	O'Connell Road	Oberon	Oberon	LGOV
Shop	O'Connell Road	Oberon	Oberon	LGOV
Sidmouth Valley	O'Connell Road	Oberon	Oberon	LGOV
Slab Barn	O'Connell Road	Oberon	Oberon	LGOV
St Thomas Anglican Church Group		Oberon	Oberon	LGOV
St Thomas' Anglican Church		Oberon	Oberon	LGOV
Stable		Oberon	Oberon	LGOV
Store	O'Connell Road	Oberon	Oberon	LGOV
Tarana Oberon Rail Line		Oberon	Oberon	LGOV
The Six Foot Track		Oberon	Oberon	LGOV
Wiseman's Creek		Oberon	Oberon	LGOV

There was a total of  ${f 45}$  records matching your search criteria.

Key:

LGA = Local Government Area
GAZ= NSW Government Gazette (statutory listings prior to 1997), HGA = Heritage Grant Application, HS = Heritage Study, LGOV = Local Government, SGOV = State Government Agency.

Note: The Heritage Office seeks to keep the State Heritage Inventory (SHI) up to date, however the latest listings in Local and Regional Environmental Plans (LEPs and REPs) may not yet be included. Always check with the relevant Local Council or Shire for the most recent listings.



| Home | Terms of Use | Site Map



Contact us

About us

Sitemap

Related websites

## Western region

<u>Home > Environment > Heritage > Heritage and conservation register > Western region</u>

Abercrombie Bridge over the Abercrombie River	430016
Beryl Bridge over Wyaldra Creek	430016
Bitumen Kettle	430072
Boonanga Bridge over Barwon River	430017
Brewarrina Bridge over Barwon River, The	430166
Bridge over Turon River at Wallaby Rocks	430015
Holman Bridge over Lachlan River at Gooloogong	430013
Iron Bridge over Lachlan River at Forbes	430169
Iron Bridge over Namoi River near Boggabri	430168
Ironpot Creek Bridge	430953
Lagoon Creek (Centre) Bridge	430953
Limestone Creek Bridge	430956
Marara Creek Bridge	430954
Marrangaroo Creek Bridge	430951
Masonry Well	430266
McKanes Falls Bridge, Lithgow	430000
Mudgee Overpass Road Cutting	430102
Mulyandry Creek Bridge	430954
Mungindi Bridge over Barwon River at Mungindi	430015
Paytens Bridge over Lachlan River at Colletts Crossing	430016
Queen Charlottes Bridge over Vale Creek, Perthville	430169
Rawsonville Bridge over Macquarie River	430018
Road Grader	430072
Road Plough	430072
Sandstone Culvert - Great Western Highway	430047
Scabbing Flat Bridge over Macquarie River	430017
Spring Creek Bridge	430952
Stone Culvert & Retaining Wall near 'Emoh', Old Bowenfels	430102
Victoria Pass Mitchell's Pass	430102
Warroo Bridge over the Lachlan River	430017
Yamble Bridge over Cudgegong River	430018
Yaminba Creek Bridge	430952

#### In This Section

- Hunter region
- Northern region
- South West region
- Southern region
- Sydney region
- Western region

↑ Back to top

Terms of Use | Online Privacy Policy | Copyright
© Roads and Traffic Authority (NSW) Last Updated: 16 March 2004

#### **Emission report**

You are here: NPI Home > Database Search

8 February 2005 15:06

### Substance Emission Details - Reporting Facilities: Oberon (A), NSW

Industrial facilities are required to report emissions to the NPI if they use more than a certain amount of one or more substances on the NPI reporting list, or consume more than a specified amount of fuel or electric power, or emit more than a certain amount of nitrogen or phosphorus to water. Emissions are estimated using techniques outlined in industry handbooks and related manuals - see further details on industry reporting. Note that toxicity of listed substances varies, and a small amount of a highly toxic substance may be of more concern than a larger emission of a less toxic substance.


Reporting Year: 2003 - 2004

#### This report includes:

- Emissions from facilities in Oberon (A), NSW.
- Top substances emitted by each facility.
- Ranking for each substance emission -1=lowest; 100=highest.

Explanation of rankings: Individual substance emissions from each facility are compared against the maximum emission of that substance from all of the facilities reported on the NPI, on a scale of 1-100 (from lowest to highest) - if the total emission of a substance is 10% of the maximum reported to the NPI, the emission ranking would be 10; if the total emission is 95% of the maximum, the ranking would be 95. A score of 100 means that the facility is the highest facility emitter of that substance - in some cases many facilities may score 100, due to rounding. Top substances are those substance emissions that are ranked highest for any individual facility.

For example, a small rural sewage treatment plant may report a very small Total nitrogen emission in comparison with a large metropolitan facility. If the Map of Oberon (A), NSW: rural facility reported an emission that is 7% of the Selected NPI facilities are shown as ■ maximum Total Nitrogen emission in Australia it would attract a ranking of 7. This ranking tells you that there are many other facilities that have much larger emissions of Total Nitrogen. On the other hand a metropolitan sewage treatment plant may have a very large Total Nitrogen emission and therefore attracts a ranking of 100 for this substance. This only means that this particular



facility has approximately the largest individual emission of that substance in Australia.

Facilities (alphabetic order)	Top Substance Emissions and Rankings  Rankings are shown as: □=0-25; □=26-50; □=51-75; □=76-100.  [actual rankings are shown in brackets: 1=lowest; 100=highest]				
Carter Holt Harvey Wood Products Australia Pty Limited (Carter Holt Harvey	Formaldehyde (methyl aldehyde)	Polychlorinated dioxins and furans		Particulate Matter 10.0 um	Polycyclic aromatic hydrocarbons
MDF Oberon facility, Oberon NSW)		O[Low - 14]	© [Low - 2]	© [Low - 1]	ூ[Low - 1]
Carter Holt Harvey Wood Products Australia Pty Limited ( Structaflor Oberon,		Polychlorinated dioxins and furans	Particulate Matter 10.0 um	Total Volatile Organic Compounds	Polycyclic aromatic hydrocarbons
Oberon NSW)	O[Low - 12]	<sup>©</sup> [Low - 3]	O[Low - 1]	<b>○</b> [Low - 1]	© [Low - 1]
Highland Pine Products Pty Limited ( Highland Pine Products Oberon	Polychlorinated dioxins and furans	Particulate Matter 10.0 um	Polycyclic aromatic hydrocarbons	Oxides of Nitrogen	Chromium (VI) compounds
Sawmill, Oberon NSW)	© [Low - 20]	O [Low - 2]	<b>○</b> [Low - 1]	<b>○</b> [Low - 1]	ூ[Low - 1]
Jeld Wen Fibre of Australia ( Jeld Wen Fibre Oberon, Oberon	Formaldehyde (methyl aldehyde)	Total Volatile Organic Compounds	Particulate Matter 10.0 um	Oxides of Nitrogen	Carbon monoxide
NSW)	<sup>©</sup> [Low - 1]	<sup>©</sup> [Low - 1]	<sup>©</sup> [Low - 1]	<sup>©</sup> [Low - 1]	<sup>©</sup> [Low - 1]
Woodchem Australia Pty Ltd ( Woodchem Australia Oberon,	Methanol	Formaldehyde (methyl aldehyde)	Total Volatile Organic Compounds	Phenol	
Oberon NSW)	<b>©</b> [Low - 6]	©[Low - 1]	© [Low - 1]	<b>○</b> [Low - 1]	

The disclaimer has further information about the use of NPI data.

NPI Home | Make a Map | Substances Background | Download Data | Data Changes

Top | About us | Advanced search | Contact us | Information services | Publications | What's New

Accessibility | Disclaimer | Privacy | © Commonwealth of Australia

Department of the Environment and Heritage GPO Box 787 Canberra ACT 2601 Australia Telephone: (02) 6274 1111

#### **Emission report**

You are here: NPI Home > Database Search

31 January 2005 17:29

Substance Emissions - All Sources : Oberon (A), NSW

The NPI holds data reported by larger industrial facilities, and aggregated emission data for smaller facilities and mobile and non-industrial sources, collected by participating jurisdictions. Accuracy of data varies along with estimation techniques - see explanation of data below. The listed substances span a wide range of toxicities, and a small amount of a highly toxic substance may be of more concern than a larger emission of a less toxic substance. This report includes data for industrial facilities and aggregated emission data (if available for this area).

Reporting Year: 2003 - 2004 (for facilities only)

Data Source: All sources - Reporting Facilities + Aggregated Emission

Data

(click to exclude Aggregated Emission Data)

This report includes:

 Summary of emission sources for this area -Oberon (A), NSW.


- Top sources for each substance, and amounts emitted.
- Explanation of data and calculations.


See also other reports on:

Facility emission details for this area (new window).

# Source Summary - Oberon (A), NSW

- 20 substances from 21 sources were found.
- 5 facilities reported to the NPI.
- Additional aggregated emission data was collected for 18 sources.
- Indicative top sources for this region are shown in the pie chart. Note that only substances listed on <u>Table 1</u> were used in the NPI facilities are shown as calculation these substances were required to be reported for the first three reporting years.





The indicative top sources, a broad snapshot of all emissions reported in this area, are derived by converting each emission into proportional units, and then pooling those proportional units. This calculation does not account for any variation in toxicity or ground level concentration of these substances - see further <u>explanation</u> below. For more accurate information, refer to individual substance information in the table below under Top Sources By Substance.

### Top Sources by Substance - Oberon (A), NSW

The table shows emissions of all substances in this area, and the top sources for each substance. All emission amounts have been rounded to two significant figures. Note that totals may differ from the sum of the individual amounts because of this rounding. Source names for reporting facilities are shown as ANZSIC Groups; source names for any aggregated emission data are marked with \*. See <a href="explanation">explanation</a> for information on NPI data, or click on the source name.

Substance					
(sort by total emission)	Emissions (kg)	Distribution (pie chart)	Name ( Aggregated Data Source * or ANZSIC Group )	Sub-total (kg)	
Arsenic & compounds	40		Log Sawmilling and Timber Dressing [ 231 ]	5.2	
(Table 1)	10		Other Wood Product Manufacturing [ 232 ]	4.8	
Cadmium &	2.5		Log Sawmilling and Timber Dressing [ 231 ]	1.3	
compounds (Table 1)	2.5		Other Wood Product Manufacturing [ 232 ]	1.2	
Carbon monoxide	F20 000		Other Wood Product Manufacturing [ 232 ]	480,000	
(Table 1)	520,000		Log Sawmilling and Timber Dressing [ 231 ]	34,000	
Chromium (III)	18		Log Sawmilling and Timber Dressing [ 231 ]	10	
compounds			Other Wood Product Manufacturing [ 232 ]	8	
			Log Sawmilling and Timber	2.8	

			Dressing [ 231 ]	
Chromium (VI) compounds (Table 1)	5.2		Other Wood Product Manufacturing [ 232 ]	2.4
Copper & compounds	44		Log Sawmilling and Timber Dressing [ 231 ]	23
			Other Wood Product Manufacturing [ 232 ]	21
Formaldehyde (methyl aldehyde)	37,000		Other Wood Product Manufacturing [ 232 ]	37,000
			Basic Chemical Manufacturing [ 253 ]	200
Lead & compounds (Table 1)	39		Log Sawmilling and Timber Dressing [ 231 ]	20
			Other Wood Product Manufacturing [ 232 ]	19
Mercury & compounds (Table 1)	0.60		Other Wood Product Manufacturing [ 232 ]	0.30
			Log Sawmilling and Timber Dressing [ 231 ]	0.30
Methanol (Table 1)	13,000		Basic Chemical Manufacturing [ 253 ]	13,000
Nickel & compounds	7.6		Log Sawmilling and Timber Dressing [ 231 ]	4
			Other Wood Product Manufacturing [ 232 ]	3.6
Oxides of Nitrogen (Table 1)	190,000		Log Sawmilling and Timber Dressing [ 231 ]	140,000
			Other Wood Product Manufacturing [ 232 ]	58,000
Particulate Matter 10.0 um (Table 1)	670,000		Log Sawmilling and Timber Dressing [ 231 ]	340,000
			Other Wood Product Manufacturing [ 232 ]	320,000
				11

Phenol	2.2		Basic Chemical Manufacturing [ 253 ]	1.2
			Other Wood Product Manufacturing [ 232 ]	1
Polychlorinated dioxins and furans	0.0054		Log Sawmilling and Timber Dressing [ 231 ]	0.0030
			Other Wood Product Manufacturing [ 232 ]	0.0024
Polycyclic aromatic hydrocarbons (Table 1)	450		Log Sawmilling and Timber Dressing [ 231 ]	230
			Other Wood Product Manufacturing [ 232 ]	220
Sulfur dioxide (Table 1)	3,200		Log Sawmilling and Timber Dressing [ 231 ]	1,900
			Other Wood Product Manufacturing [ 232 ]	1,400
Total Nitrogen (Table 1)	510,000		Unimproved pasture- Murray-Darling Basin *	160,000
			Cropping-Murray-Darling Basin *	130,000
			Bushland-Hawkesbury- Nepean River *	120,000
			Improved pasture-Murray- Darling Basin *	56,000
			Unfertilised grazing- Hawkesbury-Nepean River *	24,000
Total Phosphorus (Table 1)	43,000		Cropping-Murray-Darling Basin *	17,000
			Bushland-Hawkesbury- Nepean River *	8,000
			Unimproved pasture- Murray-Darling Basin *	7,300
			Improved pasture-Murray- Darling Basin *	5,200
			Unfertilised grazing- Hawkesbury-Nepean River	3,700
Total Volatile Organic Compounds	720,000		Other Wood Product Manufacturing [ 232 ]	720,000
			Basic Chemical Manufacturing [ 253 ]	3,800
			Log Sawmilling and Timber Dressing [ 231 ]	1,600

#### **Explanation of Data and Calculations**

The NPI reports on emissions of chemical substances and where and from what sources they are generated. The ultimate fate of these substances and therefore exposure to humans and the environment as pollution cannot be determined from the NPI. Numerous factors such as height of emission (high stacks versus ground level vehicle exhausts), nature of receiving environment, chemical reactivity of the substance and prevailing meteorological conditions determine whether an emission is felt as ground level pollution. Since NPI does not attempt to collect these parameters, the data can only reflect pollutant generation at source.

The NPI holds emission data reported by industrial facilities, and aggregated emission data collected by participating jurisdictions. Industrial facilities are required to report emissions to the NPI if they use more than a certain amount of one or more substances on the NPI reporting list, or consume more than a specified amount of fuel or electric power, or emit more than a certain amount of nitrogen or phosphorus to water. Aggregated data include smaller facilities that are not required to report, and mobile and non-industrial sources such as transport, domestic activities and for water catchments and land use type (see <u>further details</u> on NPI data).

The techniques used to estimate emissions in the NPI have been variously approved by Commonwealth, State and Territory environment agencies but it is important to note that the accuracy of these estimates is likely to vary according to the technique used. For the aggregated emissions data in particular, comparative analysis of the data may be misleading, because jurisdictions may have used different approved estimation techniques. Industrial facilities estimate emissions using a technique described in an appropriate NPI handbook, or else otherwise approved.

The <u>listed substances</u> span a wide range of toxicities. A small number may not necessarily imply an insignificant emission; for example, a small emission of a highly toxic substance may be of more concern than a larger emission of a substance of relatively lower toxicity. All emission amounts reported here have been rounded to two significant figures - totals may differ from the sum of the individual amounts on these reports because of this rounding. Some minor discrepancies may also occur with catchment and airshed data, particularly when queried at a fine spatial resolution such as a postcode. This is because these data are collected at varying spatial resolutions.

Indicative top sources are derived by converting each emission into proportional units - this provides an equal weighting for each substance, and does not consider any variation in hazard or possibility of exposure to substances. The following worked example illlustrates the calculation of equivalent percentage units in a queried area: If the total emission of Chromium (VI) compounds is 4.4kg, and motor vehicles emit 3.7kg, the proportional units for motor vehicles for Chromium (VI) compounds are calculated as (3.7/4.4)X 100 = 80.8. Similarly, if the total reported emission for Benzene is 30,000kg, and motor vehicles emit 28,000kg, the proportional units for motor vehicles for Benzene (28,000/30,000) X 100 =94.1. This calculation is repeated for each substance/source combination, and the proportional units for a source are then summed to provide a total contribution of that source to the emission profile for this area.

Substance	Total Emissions	Motor Vehicles		Repeat for all sources
		Emission	Proportional Emission Units [(Emission/Total)*100]	
Benzene	30,000kg	28,000kg	(28,000/30,000) *100=94.1	

Chromium (VI) compounds	4.4kg	3.7kg	(3.7/4.4)*100=80.8	
Repeat for all substances				
Total proportional units			Sum for each source	

The disclaimer has further information about the use of NPI data.

NPI Home | Make a Map | Substances Background | Download Data | Data Changes

Top | About us | Advanced search | Contact us | Information services | Publications | What's New

Accessibility | Disclaimer | Privacy | © Commonwealth of Australia

Department of the Environment and Heritage GPO Box 787 Canberra ACT 2601 Australia Telephone: (02) 6274 1111 **Appendix F:** Pejar LALC and Gundungurra Tribal Council

EJAR LOCAL ABORIGINAL LAND COUNCIL

PO Box 289 Goulburn NSW 2580 Phone (O2) 4822 3552 • Fax (O2) 4822 3551 email address: pejar@goulburn.net.au

ABN: 72 662 632 151

26 May 2004

Chris Barnett RTA 15 – 33 Cooerwull Rd Bowenfells NSW 2790 Fax: 02 – 63528915

Dear Chris

#### RE: SECTION 1 AND SECTION 2 JENOLAN CAVES RD

Mr Patrick Little, a representative from this organisation, recently carried out an Aboriginal site inspection on the above proposal. Upon inspection nothing of Aboriginal Significance could be located. Therefore, the Pejar LALC have no objections with the proposal going ahead, our only recommendation is that:

- If any Aboriginal Objects are located during the development, then work is to cease immediately and Department of Environment and Conservation along with ourselves, are to be contacted as soon as possible.
- If there is any further information that you may require, then please do not hesitate to contact me on the above numbers.

Yours sincerely

Delise Freeman

Approved to

Delive Freman

Jundungurra Tribal Council Aboriginal Corporation 14 oak Street KATOOMBA 2780 Phone 02 4782 9354 Fax 02 4782 9354 ABN 84 578 695 549

Friday, May 28, 2004

Chris Barnett
Technical Services Manager
Western Region
RTA
Cooerwell Rd
Lthgow 2790

Chris,

The Gundungurra Tribal Council has no objection to the proposed treatment program for the retaining walls on Jenolan Caves Road.

My inspection with yourself on the 21<sup>st</sup> May 2004 showed that the works are urgently needed and we only too pleased to allow any ground disturbance in the area so the road will be safe to use for any traffic that travels that road.

Yours truly,

Bill Hardie chairperson.